

GOVERNMENT OF INDIA

ARCHAEOLOGICAL SURVEY OF INDIA

Central Archaeological Library

NEW DELHI

ACC. NO. 70824

CALL NO. R 417.05/E.I

D.G.A. 79

enl
25-11-83

EPIGRAPHIA INDICA

Vol. XX (1929 - 30)

70824



PUBLISHED BY
THE DIRECTOR GENERAL
ARCHEOLOGICAL SURVEY OF INDIA
JANPATH, NEW DELHI-110001
1983

GOVERNMENT OF INDIA

ARCHAEOLOGICAL SURVEY OF INDIA

Central Archaeological Library

NEW DELHI

ACC. NO. 70824

CALL NO. R 417.05 | E.I.

D.G.A. 79

EPIGRAPHIA INDICA

Vol. XX. 1929-30.

70324



PUBLISHED BY
THE DIRECTOR GENERAL
ARCHAEOLOGICAL SURVEY OF INDIA
JANPATH, NEW DELHI-110011

1983

Reprinted 1983

70324
प्राप्त सख्या 70324 दिनांक 24.11.83
निर्देश संख्या R 417.05 E-I
राष्ट्रीय पुरातत्व पर्यवेक्षण
केंद्रीय पुरातत्व पर्यवेक्षण

©
ARCHAEOLOGICAL SURVEY OF INDIA
GOVERNMENT OF INDIA
1983

Price : Rs. 40.00

PUBLISHED UNDER THE AUTHORITY OF THE GOVERNMENT OF INDIA

EPIGRAPHIA INDICA

AND

RECORD OF THE ARCHÆOLOGICAL SURVEY OF INDIA.

Vol. XX. 1929-30.

EDITED BY

HIRANANDA SASTRI, M.A., M. O.L., D. LITT.,
GOVERNMENT EPIGRAPHIST FOR INDIA.

DELHI: MANAGER OF PUBLICATIONS
1933

CONTENTS.

The names of contributors are arranged alphabetically.

	PAGE
JIYER, SUBRAHMANYA, K. V., B.A., M.R.A.S.—	
No. 3. Three Tamil Inscriptions of Lalgudi	46
BANERJI, R. L., M.A.—	
No. 10. Patna Museum Plates of Ranabhanja—the year 22 ✓	100
,, 11. The Kadambapadraka Grant of Naravarman—V. S. 1167	105
DIKSHIT, K. N., M.A.—	
No. 5. Paharpur Copper-plate Grant of the [Gupta] year 159 ✓	59
HALDER, R. R.—	
No. 9. Samoli Inscription of the time of Siladitya [Vikrama-Samvat] 703	97
,, 13. Dabok Inscription of the time of Dhavalappadeva ; [Harsha-] Samvat 207	122
HIRALAL, RAI BAHADUR—	
No. 14. Four Chandella Copper-plate Inscriptions ✓	125
JAYASWAL, K. P., M.A. AND BANERJI, R. D., Prof., M.A.—	
No. 7. The Hathigumpha Inscription of Kharavela	71
PANCHAMUKHI, R. S., M.A.—	
No. 6. Kotavumachgi Inscription of Vikramaditya V	64
,, 12. Two Sinda Inscriptions from Benachamatti, Saka 1088 and Saka 1109	109
RAO, LAESHMINARYAN, N., M.A.—	
No. 8. Kap Copper-plate of Keladi Sadasiva-Nayaka ; Saka 1479	89
SAHNI, DAYA RAY, M.A., RAI BAHADUR—	
No. 4. A Sunga Inscription from Ayodhya ✓	54
SASTRI, HIRANANDA—	
No. 2. Nalanda Stone Inscription of the reign of Yasovarmmadeva /	37
VOGEL, J. PH., PROF., PH.D.—	
No. 1. Prakrit Inscriptions from a Buddhist site at Nagarjunikonda	1
INDEX	137
Appendix—A List of the Inscriptions of Northern India written in Brahmi and its Derivative Scripts from about A.C. 200. By Professor D. R. Bhandarkar, M.A., PH.D. ✓	43—266
Title-page, Contents, List of Plates and Additions and Corrections	i—viii

LIST OF PLATES.



No. 1.	Prakrit Inscription from a Buddhist site at Nagarjunikonda (I)	. . . between pages	16 & 17
" 2.	" " " " " (II)	. . . " "	18 & 19
" 3.	" " " " " (III)	. . . to face page	21
" 4.	" " " " " (IV)	. . . between pages	22 & 23
" 5.	" " " " " (V)	. . . " "	24 & 25
" 6.	Nalanda Stone Inscription of the reign of Yasevarmmadeva	. . . to face page	43
" 7.	Three Tamil Inscriptions of Lalgudi	. . . between pages	52 & 53
" 8.	Baharpur Copper Plate Grant of the (Gupta) year 159	. . . " "	62 & 63
" 9.	Kotavumachgi Inscription of Vikramaditya V	. . . " "	66 & 67
" 10.	Samoli Inscription of the time of Siladitya—[Vikrama-Samvat] 703.	. . . to face page	89
" 11.	Patna Museum Plates of Ranabhanja—the year 22	. . . between pages	102 & 103
" 12.	Kadambapadraka Grant of Naravarman—V. S. 1167	. . . " "	106 & 107
" 13.	Debok Inscription of the time of Dhavalappadeva ; [Harsha-] Samvat 207	to face page	124
" 14.	Charkhari Plate of Hamiravarmadeva, [Vikrama-] Samvat 1346	. . . " "	136

ADDITIONS AND CORRECTIONS.

- Page 7, l. 26.—*For Kasmīra read Kasmira.*
- „ 15, l. 7 of G.—*For Bhaṭṭidēvā read Bhaṭṭidevā.*
- „ 22, l. 26.—*For mahāvi[hā*]re read Mahāvi[hā*]re.*
- „ 23, l. 11.—*For Taṁbapaṁṇa read Taṁbapaṁṇi.*
- „ 32, l. 38 —*For (G. l. 12) read (H. l. 12).*
- „ 35, l. 17.—*For Aśoka read Aśōka.*
- „ „ penultimate line.—*For Chīna read Chīna.*
- „ 36, l. 17.—*For Naharāḷlabōḍu read Nāharāḷlabōḍu.*
- „ 39, l. 8.—*For he read the.*
- „ 44, f.n. 3.—*For hould read should.*
- „ 45, penultimate line in translation of Verse 1.—*For fishes (engraved) read makaras (wrough)*
(suggested by Dr. A. Coomaraswamy.—ed.).
- „ „ l. 2. in translation of Vv. 4-6.—*For asif read as if*
- „ „ l. 3 „ „ V. 9.—*For coplous read copious.*
- „ 47, l. 35.—*For Parāntak n read Parāntakaṇ.*
- „ 48, l. 25.—*For latter read later.*
- „ „ l. 36.—*For Vēlūrāpālaiyam read Vēlūrālaiyam.*
- „ „ l. 2 of f. n. 5.—*Insert (before Stambha).*
- „ 49, l. 6.—*Insert ^a after Aparājita.*
- „ „ f. n. 5.—*For Tillasthānam read Tillaisthānam.*
- „ 50, col. 4 in the table.—*For Prithvipati I read Prithvipati L*
- „ „ l. 1 of f. n. 3.—*For Varaguna read Varagaṇa.*
- „ 51, penultimate line of the letterpress.—*For Iḷamperuṅgāy- read Iḷamperuṅkāy-.*
- „ 53, l. 5 of translation.—*For th esun read the sun,*
- „ „ l. 5 of text of C.—*For l-ppon read i-ppon.*
- „ 56, l. 29.—*For writer read writers.*
- „ 58, l. 30.—*For karamisra read karamīśra.*
- „ 61, l. 2 of f. n. 5.—*For Nātha-śarmā read Nāthaśarmma.*
- „ 63, f. n. 7.—*For mahimatām read mahimatām. •*
- „ 65, l. 10.—*For Gōvinda-Bhaṭṭa read Gōvinda-Bhaṭṭa.*
- „ 66, l. 20.—*Omit be.*
- „ „ f. n. 1.—*For Hebbal read Hebbāḷ.*
- „ „ f. n. 6.—*For elonged read belonged.*
- „ 67, text l. 24.—*For bhatta- read bhaṭṭa-.*
- „ 68, text l. 43.—*For mukkyarggaṁ read mukhyarggaṁ.*
- „ 69, f. n. 4.—*For साधदेहिजितेन्द्रियः read साधदेहिजितेन्द्रियः*
- „ 70, l. 2 of translation of Ll. 46-48.—*For Vāraṇāsi read Vāraṇāsī.*
- „ 79, text line 6.—*For Rāja-s[u]ya[m] read Rājas[ū]ya[m].*
- „ 83, l. 2.—*For Kaliṅgapatanam read Kaliṅgapataṇam.*
- „ 86, t. n. 5 l. 3.—*For Bhaṭṭoji read Bhaṭṭōji.*
- „ 87, f. n. 11.—*For Fori nstance read For instance.*

- Page 88, f. n. 6.—*For* D. P. J. *read* K. P. J.
 „ 89, l. 5 of translation of l. 15.—*For* **Sindhulā** *read* **Sindhulā**.
 „ 90, f. n. 2.—*For* Viramitrōdaya *read* Viramitrōdaya.
 „ 91, l. 6.—*For* Yaśōdharachariyā *read* Yaśōdharachariya.
 „ 92, l. 16.—*For* Girnar *read* Gīrnār.
 „ 95, translation of Ll. 19 ff.—*For* Paramēśvara *read* Rājaparamēśvara.
 „ 96, „ 28 ff.—*For* Kāṇūr- *read* Kāṇūr-.
 „ 97, l. 2.—*Insert* a comma *after* Saṁkara-setṭi.
 „ 99, text l. 7.—*For* अष्टादशवे° *read* अष्टादशवे(वे)°.
 „ „ text l. 11.—*For* देवुवळे *read* देवुवळ
 „ 102, text l. 25.—*For* Dakhi(kshi)ṇa-pa(pā)li- *read* Dakhi(kshi)ṇapa(pā)li-.
 „ 103, text l. 41.—*For* Bhu(Bhū)mi -*read* bhu(bhū)mi-.
 „ „ text l. 42.—*For* -saṁkā *read* -śaṁkā.
 „ 104, text l. 45.—*For* Hara[n*]= *read* hara[n*]=.
 „ „ f. n. 13.—*For* utkirṇṇañ° *read* utkirṇṇañ°.
 „ 110, l. 5.—*For* Yogēśvara- *read* Yōgēśvara-.
 „ 112, l. 32.—*For* Vira-Pāṇḍya *read* Vira-Pāṇḍya.

EPIGRAPHIA INDICA.

VOLUME XX.

1.—PRAKRIT INSCRIPTIONS FROM A BUDDHIST SITE AT NAGARJUNIKONDA.

BY PROFESSOR J. PH. VOGEL, PH. D., LEIDEN.

In March 1926 Mr. A. R. Sarasvati, Telugu Assistant in the office of the Assistant Archaeological Superintendent for Epigraphy at Madras, made a discovery of great interest at the hill of Nāgārjunikoṇḍa which belongs to the Palnāḷ *taluk* of the Guṇṭūr district of the Madras Presidency.¹ The hill, which is described as a big flat-topped hill some 200 acres in extent, overhangs the right bank of the river Kistna or Kṛishṇā, the Kaṇṇapennā or Kaṇṇavaṇṇā (Skt. *Kṛishṇavarṇā*) of Pali literature, at a distance of some 15 miles from Mācherla and on the border of the Nizam's Dominions. The top of the hill shows traces of fortifications, now in ruins. The find of a Buddhist sculpture led to the discovery of three vast mounds of large bricks in different parts of the valley, each, apparently, marking the site of a *stūpa*. In the vicinity of these mounds marble pillars were found, some of them standing erect in rows. Several more were reported to lie scattered in the neighbouring villages and on the other side of the river. Among the pillars left on the site there were three, one on each mound, bearing inscriptions in Prakrit and in Brāhmī characters.

At the request of Dr. Hīrānanda Śāstrī, Government Epigraphist, I undertook to edit the inscriptions in the *Epigraphia Indica*. A set of excellent estampages prepared under instructions from that officer, reached me in September 1926; but it was not until the end of that year that I could find the necessary leisure to decipher and study them. Early in March 1927, Dr. Hīrānanda Śāstrī informed me that trial excavations carried out on the site of Nāgārjunikoṇḍa by Mr. Hamid Kuraishi, then officiating as Superintendent of Archaeology in the Southern Circle, had yielded no less than eighteen more inscriptions and that their estampages would be sent to my address, in case I should be willing to edit them. I gladly consented to undertake this laborious but attractive task. As, however, there was a likelihood of the recently discovered inscriptions being of some help in elucidating doubtful points in those found previously, I suggested that the epigraphical finds of Nāgārjunikoṇḍa might be best dealt with in one article. Dr. Hīrānanda Śāstrī accepted this proposal and in October 1927 supplied me with a complete set of estampages admirably executed.

During the cold season of 1927-28 the excavations at Nāgārjunikoṇḍa were continued under the supervision of Mr. A. H. Longhurst, Superintendent of the Archaeological Survey, Southern Circle. These explorations have resulted in the discovery of a number of very remarkable Buddhist sculptures, some of them bearing inscriptions. The style which they exhibit is clearly that of

¹ A preliminary account of the discovery will be found in the *Annual Report on South-Indian Epigraphy for the year ending 31st March 1926*, Madras, pp. 4 and 92 f. Cf. also *Annual Bibliography of Indian Archaeology for the year 1926*, Leyden, 1928, pp. 14-16.

Amarāvati, although perhaps they cannot boast of the high artistic merit which we admire in the best work from that place. Among the sculptural decoration of the two pillars discovered by Mr. Longhurst there are figures which clearly betray Roman influence. The full report of his excavations will be received with the greatest interest. There cannot be the slightest doubt that Nāgārjunikoṇḍa represents, next to Amarāvati, the most important Buddhist site hitherto found in Southern India. The results which Amarāvati might have yielded have, for a large part, been irreparably lost owing to the deplorable vandalism perpetrated on that monument more than a century ago. It is all the more gratifying that the site of Nāgārjunikoṇḍa is now being systematically explored so that no piece of evidence is likely to be overlooked. Mr. Longhurst estimates that the complete excavation of the site will require three years more.

When in February 1882 Dr. Burgess excavated the site of the Jaggayyapeta *stūpa*, on the Pālēr river, a tributary of the Kṛishṇā and about four miles north of their junction, he chanced upon three inscribed pillars, bearing each an identical dedicatory inscription in Prakrit.¹ These epigraphs record the gift of five *āyaka-khaṁbhas* at the eastern gate of the Mahāchetiya or Great Chaitya by a certain artisan (*āvesani*) Siddhattha in the twentieth year of King Māḍhariputa Siri-Virapurisadatta of the Ikḥāku dynasty. The corresponding form in Sanskrit would be Māṭhariputra Śrī-Virapurushadatta. Dr. Burgess expressed the opinion that the Jaggayyapeta inscriptions "belong to about the third or fourth century A.D., but are possibly earlier." Dr. Bühler², while editing them, placed the reign of King Purisadatta in the third century of our era, and "before the accession of the Pallavas to the throne of Veṅgi."

The position of such *āyaka*-pillars on the monument to which they once have belonged becomes perfectly clear from the *chaitya*-slabs which have been found in such remarkable numbers on the site of Amarāvati. These *chaitya*-slabs exhibit the effigy in relief of a *chaitya* or *stūpa* in all its details, in other words, they represent the great monument which they once adorned. Now, one of the most prominent features of the main edifice—a feature not met with, as far as we are aware, in other parts of India—is a row of five columns surmounting a kind of projecting balcony which seems to form part of the procession-path running around the body of the monument. These pillars invariably occupy a position right opposite the entrances to the sacred enclosure, and as the stone railing surrounding the sanctuary has an entrance on each of the four cardinal points, it follows that the monument, when entire, must have had four sets of such pillars. They do not appear to have had any structural function as supporting members, but, besides carrying well-known Buddhist emblems, they were utilised for dedicatory inscriptions, as have been noticed at Jaggayyapeta. The word *āyaka-khaṁbha* mentioned in these epigraphs is evidently the technical term by which they were known³.

There can be little doubt that the great *stūpa* of Amarāvati, when entire, was decorated with such pillars, but only a few fragments have been recovered.⁴ In the case of the monument of

¹ J. Burgess, *The Buddhist Stupas of Amaravati and Jaggayyapeta*; London, 1887, pp. 110 f., plates LXII and LXIII. Cf. H. Lüders, *List of Brahmi Inscriptions*, Nos. 1202-1204 (*Ep. Ind.*, Vol. X, app., pp. 139 f.); G. Bühler, *Indische Palæographie*, p. 44.

² *Ind. Ant.*, Vol. XI (1882), pp. 256 ff.

³ The word *āyaka* occurs also in the compounds *dakṣiṇ-āyaka* (Burgess, *Amaravati, etc.*, p. 86, pl. LX, no. 47) and *utār-āyaka* (*ibidem*, p. 93), which have been rendered "the south entrance" and "the northern gate". It is questionable whether this translation is correct. The word "gate" is rendered by *dāra* (Skt. *dvāra*). Most probably the word *āyaka* indicates that part of the monument where the *āyaka-khaṁbhas* were placed.

⁴ Burgess, *op. cit.*, pl. XLV, 1-4. The finest specimen is the square lower end of a pillar decorated on the four sides with as many Buddhist symbols—a *stūpa*, a *bōdhi*-tree, a *chaitya*-hall, and a wheel. There is an inscription in four lines beneath the figure of the *stūpa* (pl. LX, no. 47) in which the pillar is called *chetiya-kha* {*m*}-*bho* *śadhādūko*.

Jaggayyapēṭa three inscribed specimens were found, only one of them being complete. These, as we have seen, must have belonged to a set of five such pillars which were placed on the east side. Dr. Burgess noticed large pillars or stelæ at three of the sides of the *stūpa*, but it would seem that those found on the other sides were uninscribed.

The explorations at Nāgārjunikoṇḍa have brought to light no less than seventeen specimens of *āyaka*-pillars, all inscribed. In thirteen cases the inscription is complete or nearly so. The technical execution of these epigraphs is as remarkable as the state of their preservation. Evidently, these pillars once served the purpose of adorning the main monument of the site, mentioned in the inscriptions under the name of Mahāchetiya (Skt. *Mahāchaitya*), i.e., the Great Chaitya. It is clear that here, too, there must have stood a row of five such pillars at each of the four cardinal points, their total number being twenty. The original position which each of the seventeen columns so far recovered once occupied, could still be ascertained. A complete list of the inscriptions will be given below.

The mound which covered the ruins of the Mahāchetiya is nowadays known by the name of Nibaguṭṭa. Close to the east side of the great monument the excavations revealed the remains of an apsidal temple containing a small *chaitya* as an object of worship. The floor of this shrine retains the record of its foundation in an inscription (E) of two very long lines, remarkably well preserved.

At a distance of about a furlong to the east of the Great Chaitya there is another mound called Nāharāḷlabōḍu. According to Mr. Longhurst, this site contains the most important group of monastic buildings, including a large monastery built of brick and plaster, and the remains of two *stūpas*. At the side of the former building were found the remnants of another apsidal shrine or *chaitya*-hall. Here, too, a long inscription (F), incised on the floor of the temple, was found to be the record of its foundation.

There is a third mound known by the name of Iṭikarāḷlabōḍu to the north-west of the Great Chaitya and at a distance of about two furlongs from it. Here a number of stone pillars, apparently still occupying their original position, indicate the existence of another ancient building. From the inscription (G) found on one of these pillars (this inscription is one of the three recovered in March 1926), it appears that the edifice in question was a *vihāra* somewhat later in date than the buildings previously noticed. If this conclusion is correct, the stone pillars may have formed part of the verandah enclosing the central court-yard of the convent.

A third *vihāra* must have stood in a locality now known as Koṭṭampalugu to the north of Nāgārjunikoṇḍa. Here, too, the record of its foundation is inscribed on a stone pillar. The inscription (H), which is one of the three copied in March 1926, is probably the latest in date, the writing being smaller and less distinct than in the case of the earlier inscriptions.

The Jaggayyapēṭa inscriptions, as we have noted above, are dated in the twentieth year of the reign of a king who calls himself Māḍhariputa Ikhākunaṁ Siri-Virapurisadatta. The epigraphical records now recovered on the Buddhist site of Nāgārjunikoṇḍa refer to the same Ikhāku dynasty of Southern India. They mention not only Māḍhariputa Siri-Virapurisadatta,¹ in whose reign the principal sanctuaries of this locality were founded, but also his father, Vāsiṭhiputa Siri-Chāmtamūla, and his son and successor Vāseṭhiputa Siri-Ehuvuḷa-Chātāmūla.² In a passage which occurs in several of the inscriptions, the former is eulogized as a performer of the

¹ This is the usual spelling of the name. The more correct form Siri-Virapurisadatta occurs in inser. G.

² It is somewhat difficult to decide whether Chāmtamūla or Chātāmūla is the correct form of these two names. In some cases there appears to be the sign of the *anusvara* over the ā. We may, therefore, assume, that elsewhere it has been omitted by mistake.

Vedic sacrifices Agnihōtra, Agnishtōma, Vājapēya and Aśvamēdha. It follows that Siri-Chāntamūla was a devotee of Brahmanism. His son, Siri-Virapurisadata, though partaking in the religious merit, does not seem to have had an active part in the foundation of the religious monuments of Nāgārjunikoṇḍa. They owed their existence to the piety of certain queens and princesses belonging to the royal house of Ikshāku and evidently devotees of the Buddhist faith.

The principal founder was a lady called Chāntisiri¹ (°siriṇikā in inscr. B 3) who is praised for her munificence in a passage which recurs in not less than nine of the *āyaka*-pillar inscriptions. In these inscriptions she is called the uterine sister of Siri-Chāntamūla and the paternal aunt of Siri-Virapurisadata. She was married to the *Mahāsēnāpati*, the *Mahātālavara* Vāsithīputa Kāṁdasiri of the Pūkiya² family, and, in consequence, she herself bears the title of *Mahātālavarī*. Moreover, she is called the mother of Khamdasāgaramnaka. In one of the pillar inscriptions (B 5) it is distinctly stated that it was she who erected the Great Chaitya of the Great *Vihāra* or Monastery. It is curious that here the instrumental plural (*mahātālavarīhi* *Chāntisiriṇikāhi*) is employed, but it will be noted that several ladies of that name took part in the donation. Or, can it be a *pluralis majestatis*? The date regularly found at the end of the pillar inscriptions—the sixth year of Siri-Virapurisadata, the sixth fortnight of the rainy season, the tenth day—marks, no doubt, the time when the great monument was consecrated. Chāntisiri was, moreover, the foundress of the apsidal shrine (No. I), built opposite the eastern or principal side of the Great Chaitya.³ This is distinctly stated in the long inscription (E) cut on the floor of that building. In this document the edifice founded by Chāntisiri is designated first as a *chētiya-ghara*, and subsequently as a stone *maṇḍapa* surrounded by a cloister (*chatusāla-parigahitaṁ sela-maṇḍaram*).⁴ The building was dedicated to the *āchāryas* of the Aparamahāvinaseliya sect. The time of the dedication is expressed by the date found at the end of the inscription—the eighteenth year of Siri-Virapurisadata, the sixth fortnight of winter, the fifth day. The date is given both in words and in figures.

It deserves notice that in the earlier inscriptions Chāntisiri is called the paternal aunt (*pituchhā*)⁵ of the reigning king, whereas in the later inscription (E), noted above, she refers to the king as her son-in-law. It would seem that Siri-Virapurisadata between the 6th and the 18th years of his reign had married the daughter of his aunt and consequently his cousin.

Two of the pillar inscriptions (C 2 and 4) mention another sister (*sōlarā bhaginī*) of King Siri-Chāntamūla, whose name was Haṁmasiri or Haṁmasiriṇikā, and two of her daughters named Bapisiriṇikā and Chhaṭhisiri. Both these princesses were married to the reigning king, their cousin, and consequently bear the title of *Mahādēvī*.

The same title of *Mahādēvī* is borne by a lady, Rudradharabhaṭārikā, whose name occurs in the inscription on the fifth pillar of the southern row (B 5). It may be concluded that she, too, was a consort of the reigning king, though in the inscription she is not expressly designated as such. She appears to have been a princess from Ujjain (Skt. Ujjayinī), the well known town in Central India, if at least we are justified in correcting the reading *Ujanikā mahārabalikā* of the text into *Ujenikū mahārāja-bālikā*. Among the rulers of the house of Chashtana, the so-called Western Kshatrapas, whose capital was Ujjain, we find a certain preference for personal names containing the name of the god Rudra, such as Rudradāman, Rudrasēna and Rudrasimha. This renders it

¹ Here, too, there prevails some uncertainty whether the name is Chāntisiri or Chāntisiri.

² Inscr. E has *Pūgiya*.

³ The eastern side being the principal side of the Great Chaitya, it is significant that the three *āyaka*-pillars recovered on that side of the monument were all dedicated by Chāntisiri.

⁴ In Sanskrit: *chatusāla-parigrihitam śāla-maṇḍapam*.

⁵ Pali *pituchhā*.

all the more plausible to assume that the Queen Rudradharabhaṭārikā mentioned in the inscription belonged to that illustrious house.

The pillar inscriptions acquaint us with three more noble ladies who were associated with Chāmtisiri in her pious foundation. The one mentioned on the second pillar of the south side (B 2) is called Aḍavi (?)—Chā[m]tisiri. The inscription calls her the daughter of King Siri-Chāmtamūla, the sister of King Siri-Virapurisadata, and the wife of the *Mahāsēnāpati Mahātālavara Mahādzṇḍanāyaka* Khamdavisākhamṇaka (= Skt. Skandavisākha) of the house of the Dhanakas. She herself is distinguished by the title of *Mahātālavarī*.

The other lady, who was the donor of the fourth pillar of the southern row (B 4), is called Chula-Chā[m]tisiriṇikā, i.e., Chā[m]tisiriṇikā the Less or the Younger, the adjective *chula* evidently being added to distinguish her from her namesake, the foundress of the Mahāchetiya. The junior Chā[m]tisiriṇikā, as stated in the inscription, was a daughter of the Kulahakas and the spouse of the *Mahāsēnāpati Mahātālavara* Vāsithīputa Khamdachalikireṇṇaṇaka of the Hiramṇakas. She herself bears the title of *Mahāsēnāpatinī*.

The fifth pillar of the western side (C 5) was dedicated by a lady whose personal name is not mentioned, but who is called the wife of the *Mahāsēnāpati Mahātālavara* Vāsithīputa Mahākamdasiri of the Pūkiyas and the mother of the *Mahāsēnāpati Mahātālavara* Viṇḥusiri (=Skt. Vishṇusri). She is, moreover, distinguished by the title *Mahātālavarī*. If we may assume that Mahākamdasiri and Kamdasiri are one and the same person, it would follow that the anonymous lady of the pillar-inscription C 5 was a co-wife (*sapatnī*) of Chāmtisiri.

We must now consider the two separate pillar-inscriptions G and H which, as we have noted above, must belong to a somewhat later date. The inscription G is found on one among a number of pillars, decorated with lotus-rosettes, which were found standing about two furlongs to the north-west of the Mahāchetiya. Mr. Longhurst informs me that the tops of these pillars are each provided with a mortice evidently meant to receive the beams of a wooden roof. This would well agree with our supposition that these stone columns once belonged to the verandah enclosing the central court of the *vihāra*. The inscribed stone shows several cracks running through the inscribed surface and the letters are worn owing to exposure.

The inscription records the foundation of a *vihāra* by *Mahādēvī* Bhaṭidevā who is called the daughter-in-law of Siri-Chā[m]tamūla, the wife (?) of Siri-Virapurisadata, and the mother of a *Mahārāja*, whose name appears to be Siri-Ehuvuḷa-Chātamūla. The three syllables which we read—*huvuḷa*—are uncertain. The same is the case with the one or two initial syllables of the word following the name Siri-Virapurisadata, so that it is doubtful what relation existed between that king and the lady Bhaṭidevā. The word in question, however, can be hardly anything but *bhayāya*. Thus it would follow that Bhaṭidevā was the consort of the king. The last two lines of the document seem to have contained a date, but unfortunately this part of the inscription has been obliterated to such an extent that our reading must be regarded as conjectural. Evidently the *vihāra* was founded during the reign of Bhaṭidevā's son, the *Mahārāja* whose name is mentioned in the inscription.

The inscribed pillar of Kottampalugu is also the foundation record of a *vihāra*. The foundress was a *Mahādēvī* who was the granddaughter of Siri-Chā[m]tamūla, the daughter of Siri-Virapurisadata, and the sister of *Mahārāja* Vāsethīputa Siri-Ehuvuḷa-Chā[m]tamūla. It is, moreover, stated in the inscription that she was the consort of the *Mahārāja* of Vanavāsa. Her personal name is somewhat indistinct but may be read as Kodabalisiri. It will be noted in the sequel that Vanavāsa, the ancient name of North Kanara, occurs also among the countries which in the *chaitya*-inscription F are stated to have been converted to Buddhism by the Ceylonese monks.

The pillar inscription of Koṭṭampalugu is dated in the eleventh year of the reign of Siri-Ehuvuḷa-Chāṁtāmūla.

The historical information furnished by these inscriptions regarding the three rulers of the Southern Ikhāku dynasty, whom they mention, is very meagre. Siri-Chāntāmūla is extolled in a passage which recurs in several of the inscriptions but which appears to be entirely conventional. It has been pointed out above that the king must have been an adept of Brahmanism. From the expression *Virūpakhapati-Mahāsena-parigahitasa*, which is applied to Chāntāmūla, it may perhaps be concluded that he was a votary of the god Mahāsena or Skanda, "the lord of the Virūpakhas". The term Virūpakha (=Skt. *Virūpāksha*) seems to be used here to indicate the hosts of which Skanda is the lord and leader.¹ Dr. Bühler's assumption, based on palaeographical evidence, that Siri-Virapurisadata flourished in the third century of our era, may be accepted as probably correct.

Although the inscriptions tell us nothing about the *faits et gestes* of these kings, it is interesting to meet with a line of rulers, settled in the Telugu country, which claimed descent from Ikhāku, i.e., Ikkhāku (=Skt. *Ikshvāku*), the mythical progenitor of the famous Solar dynasty of Ayōdhyā. It is well known that not only Rāma belonged to that illustrious house, but the Buddha, too, is called a scion of the race of Ikshvāku (Pali *Okkāka*). It is clear, in any case, that these Southern Ikhākus were rulers of some importance, as they formed matrimonial alliances not only with the *Mahārājas* of Vanavāsa, but also with the kings, presumably the descendants of the Satrap Chashṭana, who resided at Ujjayinī in Central India. The nomenclature of these Southern Ikhāku kings, coupling their personal names with metronymics like Mādhariputa and Vāsīthiputa seems to be a practice borrowed from the earlier rulers of the Āndhra dynasty. It will hardly be necessary to quote the instance of Vāsīthiputa Siri-Puḷumāyi and Gotamiputa Sātakaṇṇi. On the other hand, there are in these inscriptions certain expressions which are also found in the Prakrit copper-plate grants of the early Pallavas, as will be pointed out in our glossary.

There are two more points to be noted in connection with these kings. We see that the name Chāntāmūla, borne by the father of Siri-Virapurisadata, re-occurs in the name of the latter's son. This seems to point to the custom of naming a child after its grandfather, which, as far as we are aware, is not an indigenous practice in India.² It further deserves notice that among the consorts of king Siri-Virapurisadata we meet with two of his cousins.

Chāntisiri, the sister of king Chāntāmūla, was married to a personage who bore the titles of *Mahāsēnāpati* and *Mahātālavara*. The same is stated with reference to other princesses of the ruling house. The title *Mahāsēnāpati* (lit. "great chief of the army" or general) denoted feudatory chieftains in charge of *rāshṭras* or districts under the Āndhras, and the same meaning may perhaps be assumed here. The word is, therefore, to be taken as a title of nobility. We may compare the Anglo-Saxon *heretoga* (Dutch *herzog*, German *herzog*), which etymologically means an army-leader, but has become a title of nobility. The word *mahāsēnāpati* could, therefore, be best rendered by "duke."

The curious term *mahātālavara* which is also met with in other inscriptions of Southern India, must likewise denote a high dignitary whose exact function, however, is not clear. The second member of the compound is not a Sanskrit word, but seems to be a term borrowed from some

¹ The word *Virūpakha* (=Skt. *Virūpāksha*), indicating a class of snakes, occurs in an ancient snake-charm, *Vinaya Piṭakam* (ed. Oldenberg), Vol. II, p. 110; *S. B. E.*, Vol. XX, p. 76.

² [This custom was known to several ruling families of ancient India, such as the Guptas, the Vākātakas, the Chālukyas and the Pallavas. (Cf. V. Smith, *Ind. Ant.*, Vol. XXXV, p. 125). Besides, as shown by the *Mahābhārata*, I. i. 1. ... निपुणप्राज्ञः... आनं कृतं पुत्रान् and Kaiyyaka on it "विना तस्य ये वयः पुत्रास्तानमुक्तावयवमिच्छते", it had a śāstric sanction behind it.—Ed.]

Dravidian language.¹ Evidently it penetrated also into Northern India, for there can be little doubt that it is identical with the mysterious word *taravara* which, coupled with *mahāpatihāra* (=“a great chamberlain”) is found in the legend of one of the clay sealings excavated by the late Dr. Bloch at Basāṛh, the site of ancient Vaiśālī. This document belongs to the Gupta period. It was suggested by Dr. Bloch that the word *tarika*, which occurs in lists of officials in mediæval copper-plate charters, may quite well be a corrupted form of *taravara*.²

In the inscriptions of Nāgārjunikoṇḍa not only frequent mention is made of persons bearing the title of *mahātālavara*, but they also contain the feminine form *mahātālavari* (more correctly *talavari*) indicating the wife of a *mahātālavara*. In the same way the consort of a *mahāsēnāpati* bears herself the title of *mahāsēnāpatini* (Skt. *sēnāpatnī*). It is found in B 4 (1.5).

A third official title, which occurs in B 2 (1.4), is the well-known term *mahādāṇḍanāyaka*. The early use of this expression is also attested by a fragmentary inscription, found at the village of Māt in the Mathurā district, which contains the name of King Huvishka.

The first apsidal shrine (No. I), as we have seen, was dedicated by Chāntisiri, the foundress of the Mahāchetiya, at the foot of which it is built. The other building of this type, on the contrary, as stated in the inscription F on the floor, was raised by a simple *upāsikā*, Bodhisiri by name, who does not appear to have been related to the royal family of the Ikshvākus. Her relatives, who were to share in the merit of her pious enterprise, are enumerated at great length. They include a *Koṭh[ā]kārīka* (Skt. *Koṣṭhāgārīka*), either a treasurer or, perhaps, a superintendent of a royal store-house.³

The inscription opens with an invocation of the Buddha who is extolled in a long string of laudatory epithets. Next comes the date which unfortunately is incomplete. This much is certain that the inscription is dated in the fourteenth regnal year of a king Mādhariputa, who in all likelihood is identical with the Mādhariputa Siri-Virapurisadata of the *āyaka*-pillar inscriptions of Jaggayyapeta and Nāgārjunikoṇḍa. The shrine is further stated to have been dedicated to the fraternities of Ceylonese monks who had converted Kasmīra (Kashmir), Gandhāra, China, Chīlāta (=Skt. *Kirāta*), Tosali, Avarānta (=Skt. *Aparānta*), Vamga (i.e., Bengal), Vanavāsi (i.e., North Kanara), Yavana (?), Damila (?), . . . lūra and the Isle of Tambapanni (i.e., Ceylon). Some of the countries are mentioned in the *Mahāvamsa* among the territories which had been converted to Buddhism after the Third Council, namely, Kasmīra and Gandhāra, Vanavāsa, Aparantaka and Yona.⁴ We may also compare two passages in the *Milindapañha* mentioning a number of

¹At the end of the Koṇḍamuṇi copper-plate grant (*Ep. Ind.*, Vol. VI, pp. 315 ff.) the late Dr. Hultzsch read *Mahātagi-varena mahādāṇḍanāyakena Bhāpāhānavammena kaṭati*. There can be little doubt that *mahātagivarena* is a mistake, due either to the scribe or to the engraver, for *mahātālavarena*. This term occurs also in a fragmentary Prakrit inscription found at the village of Allūru, in the Nandigāma taluk, Kistna district. Cf. *Annual Report on South-Indian Epigraphy*, 1924, p. 97 and *A. S. R.* for 1923-24, p. 93.

We must leave this question to the decision of students of South-Indian languages. Can the word have any connection with Tamil *talavāy* (=a general), Tamil *talaiyāri* (=a village watchman), or Canarese *talavara*, *talavāra* (=a watchman, a beadle)? [The Mahātālavaras are mentioned in early Jaina literature along with 18 Gaṇarājās. So Mahātālavara must be taken as a title of nobility. Cf. *Kalpasūtra* (ed. Jacobi, Leipzig 1879) 61, ll. 21-25. The *Subōdhikā*, a Sanskrit commentary on it by Vinayavijaya (Nirṇaya-sāgara Press, Bombay, leaf 60, ll. 6-7) explains the term *talavara* thus: *talavarāḥ tuskta-bhūpāla-pradatta-paṭṭabāṇḍha-vibhūṣitā Rājasthānīyāḥ*. In the Punjab there is a sub-division of high class Khatris (=Sanskrit *Kshatriyas*) which goes by the name of Tālwar.—Ed.]

² *A. S. R.* for 1903-04, p. 108, No. 16; plate XL, 6.

³ Cf. *koṭhaya* in Sohagaura copper-plate inscription (Lüders, *List*, No. 937) and *bhātāgārīka* in Nāsik inscription (Lüders, *List*, No. 1141).

⁴ *Mahāvamsa*, Ch. xii. Cf. *Dīpavamsa*, Ch. viii

regions which used to be visited for purposes of trade.¹ In these two passages the first countries mentioned are Saka-Yavana and China-Chilāta. The printed text has Vilāta, but, as has been pointed out by Professor Sylvain Lévi,² this is an error for Chilāta. The Chilātas are the same un-Aryan tribe often met with in Sanskrit literature under the name of Kirāta. In a well-known verse of the *Pañchatantra* they are characterized as dishonest traders. We find them, moreover, referred to both in the *Periplus* and by Ptolemy. The former says: "Beyond this [Dōsarēnē], the course trending towards the north there are many barbarous tribes, among whom are the Cirrhadae, a race of men with flattened noses, very savage." Ptolemy locates them along the Gulf of Bengal, "beyond the Ganges mouth called Antibolei." Their country is said to produce the best *malabathron* (*tamālapatram*). In his chapter on Trans-Gangetic India (VII, 2; 15) the same author describes the Tilādai (V. 1. Pilādai), also called the Saesādai, as hairy dwarfs, with a flat face and a white skin. Evidently this passage too refers to the Kirātas, the name Tilādai (Τιλᾶδαί) being an attempt to render in Greek the alternative form Chilāda.³

It is very interesting to meet here with the name Tosali. It will be remembered that Aśōka's two separate Rock-Edicts of Dhauli are addressed to the Governor and the magistrates (*Mahāmātras*) of Tosali. This enables us to locate Tosali in Kalinga. James Prinsep identified it with the "Tosalei metropolis" of Ptolemy, although this place is located in the regions beyond the Ganges. We may, perhaps, connect the name Tosali with the Dōsara of Ptolemy and with Dōsarēnē, the name of a country beyond Masalia mentioned in the *Periplus*. The name Dōsarēnē is usually explained to be the Greek rendering of Sanskrit Daśārṇa,⁴ but there are serious difficulties in the way of this identification. First of all, a Prakrit form of Daśārṇa, from which the Greek form must be derived, would certainly not have retained the *r* which we find in Dōsara and Dōsarēnē. The long *ō*-vowel of the Greek would also be difficult to account for. Besides, the tribe of the Daśārṇa, as far as we can make out from Indian sources, appears to have been settled in Central India and not along the coast.⁵ On the other hand, Dōsara may have been a dialectic form of Tosala. The *Periplus* states that Dōsarēnē yielded the ivory known as Dōsarēnic. Hiuen Tsiang in his account of Kalinga says that it produced the great tawny wild elephant which was much prized by neighbouring provinces.

Avaranta (Skt. Aparānta) is the designation of the tract of the country lying along the western coast of the Peninsula, the capital of which was Sopārā. According to the Ceylonese Chronicles, it was converted to Buddhism by Dhammarakkhita. Aśōka mentions it in his Fifth Rock-Edict in connection with the appointment of Dhamma-mahāmātas.

Vaṅga is the ancient name of Bengal. Vanavāsi, also mentioned as Vanavāsaka in inscription H, is North Kanara, the name being still preserved in Banavāsi, a village or small town in the Shimoga district of the Mysore State in latitude 14° 33', longitude 75° 5'. The *Mahāvamsa* mentions Rakkhita as the apostle of Vanavāsa.

The three words following Vanavāsi are uncertain. The first one can be hardly anything but Yavana, the *aksharas ya* and *va* being still legible. Next comes a name which I read tentatively as Damila, meaning the Tamil country. The third word seems to consist of three *aksharas*, the second and third of which are clearly *lu* and *ra*. It is tempting to restore the name as Palura, the town mentioned by Ptolemy and identified by Professor Sylvain Lévi with Dantapura, "the Town of the Tooth" on the coast of Orissa.⁶

¹ *Milindapañha* (ed. Trenckner), pp. 327 and 331.

² *Études Asiatiques*, Vol. II, p. 24.

³ Sylvain Lévi, *op. cit.*, pp. 23-24. Cf. *Bijdragen*, sixth series, Vol. VI, p. 7, no. 2.

⁴ *Periplus*, transl. by W. H. Schoff, p. 253, and N. L. Dey, *Geogr. Dict.*, 2nd ed., 1927, p. 54, s. v. *Daśārṇa*.

⁵ Kātyāyana in his *Mēghadūta* locates the Daśārṇas between the Vindhya and Vidiśā.

⁶ *Journal Asiatique*, Vol. CCVI (1925), pp. 46ff.; and *Ind. Ant.*, Vol. LV (1926), pp. 94ff.

The latter part of inscription F enumerates the various pious foundations—several of them evidently additions to existing buildings—dedicated by Bodhisiri, and mentions, moreover, the localities at which each of them was found. It is a point of considerable importance that this list includes “a stone *maṇḍapa* at the eastern gate of the Mahāchetiya at Kaṇṭakasela.” Evidently this locality Kaṇṭakasela (Skt. *Kaṇṭakasaila*, lit. “Thorn-hill”) must be identical with “the emporium Kantikossūla” which Ptolemy mentions (VII, I, 15) immediately after “the mouths of the Maisōlos.” It follows that the river known to the Greeks under the name Maisōlos has been rightly supposed to be the Kistna.¹ The country watered by the lower Kistna is consequently called Maisōlia by Ptolemy. The *Periplus* speaks (§62) of “the region of Masalia stretching a great way along the coast before the inland country,” and adds that “a great quantity of muslins is made here.” The ancient name by which this part of Southern India was known to the Greeks is preserved in that of the town Masulpatam.

We are perhaps justified in identifying it with the country which Hiuen Tsiang describes under the name of T'o-na-kie-tse-kia.² This seems to correspond to Dhaññakataka, Dhana-kataka (Skt. Dhānyakataka), found in two inscriptions from Amarāvati.³ The country in question the Chinese pilgrim locates between the Āndhra country and that of the Chōlas, the latter being situated at a distance of some 1,000 *li* to the south-west. In the course of his description he says: “The convents are numerous, but are mostly deserted and ruined; of those preserved there are about twenty with 1,000 or so priests. They all study the law of the Great Vehicle.”

Hiuen Tsiang further relates that to the east of the capital on a mountain there stood a convent called Pūrvaśilā and on a mountain to the west was another, called Avaraśilā. Perhaps it would be preferable to render the names of these two monasteries by Pūrvaśaila and Avaraśaila, the Sanskrit word for a mountain being *śaila*, whereas *śilā* means “stone.” Now, it is worthy of note that among the localities mentioned in inscription F, we meet with the name Puvasela, which is clearly a Prakrit form corresponding to Sanskrit Pūrvaśaila. A name, meaning “Eastern Mountain or Hill,” may, of course, have been used at different places of India. But it is a point worth considering whether the remains of Nāgārjunikoṇḍa can possibly represent the ancient capital of Dhaññakataka, which archaeologists have sought both at Dharanikōṭa near Amarāvati and at Bezwādā.

Another point of interest is the mention of Siripavata (*i.e.*, Siripavvata) in inscription F. The Prakrit word corresponds to Sanskrit Śripavata. Now, there is a tradition preserved in Tibet that Nāgārjuna spent the concluding part of his life in a monastery of that name in Southern India.⁴ If this convent is the same as the “*vihāra* on the Siripavata to the east of Vijayapurī” of our inscription, it would follow that the association of the great divine of the Mahāyāna with this locality has been preserved up to the present day in the name Nāgārjunikoṇḍa. We may confidently hope that these and other questions of great import will be finally settled by further systematic excavations.

Among the religious foundations enumerated in F, we wish to draw attention to the two monasteries, called Kulaha-*vihāra* and Sihaḷa-*vihāra*. The former appears to have owed its existence to the same noble family which is mentioned in one of the *āyaka*-pillar inscriptions (B 4)

¹ E. H. Warmington, *The Commerce between the Roman Empire and India*, Cambridge 1928, p. 116.

² *Si-yu-ki*, transl. by S. Beal, Vol. II, pp. 221 ff.; Thomas Watters, *On Yuan Chuang's Travels in India*, Vol. II, pp. 214 ff.

³ Prof. Lüders' *List*, Nos. 1225 and 1271. The form *Dhaññakaka* occurs in the Mayidavōlu copper-plate grant of the Pallava Yuvamahārāja Śivaskandavarman.

⁴ W. Wassiljew, *Der Buddhismus*, Vol. I, pp. 220 f.

under the name of Kulahaka. The other, if we may judge from its appellation, must have been a convent founded either by a Singhalese or, more probably, for the accommodation of Singhalese monks. This "Ceylonese Convent" appears to have contained a shrine with a Bodhi-tree (Bodhi-rukha-pāsāda = Skt. Bōdhi-vṛksha-prāsāda) which is, indeed, a necessary adjunct of the Buddhist monasteries of Ceylon up to the present day. Not only the mention of a Sihaḷa-vihāra, but also the dedication of a *chetiya-ghara* to the *theriyas* or "fraternities" of Tambapaṇṇi point to relations which must have existed between the Buddhist community of Dhañṇakataḷa and their co-religionists in the Isle of Ceylon. The existence of such relations can be easily accounted for from the sea-borne trade which was carried on between the ports of the Island and Kaṇṭaka-sela, the great emporium on the right bank of the Kistna river.

This trade was, no doubt, also largely responsible for the flourishing state of Buddhism in this part of India. The devotees of the Good Law were largely recruited from the commercial classes and it was their wealth which enabled not only the merchants themselves, but also their royal masters, to raise monuments of such magnificence as the great *stūpa* of Amarāvati. Both Amarāvati and Nāgārjunikoṇḍa are situated on the right bank of the Kistna, the former being situated at a distance of some 60 miles from the mouth of the river. Nāgārjunikoṇḍa lies considerably higher up the river, the distance between this place and Amarāvati being another 60 miles as the crow flies, but considerably longer by river. On the opposite side of the river we have Jaggayyapeṭa, containing another monument of the reign of the Ikshvākus. The village of Allūru in the Nandigāma taluk of the Kistna district has yielded a fragmentary Prakrit inscription, referred to above, which appears to record a donation to a Buddhist monastery. At the village of Gummaḍiduru in the Kistna district the remains of a large *stūpa*, adorned with marble reliefs in the Amarāvati style, have recently come to light together with the remnants of monastic buildings. All these monuments attest to the piety and the wealth of the Buddhist community in these parts during the second and third centuries of our era. In the days of Hiuen Tsiang the monasteries were mostly deserted and ruined. The collapse of Buddhism on the lower Kistna may have had various causes; besides the general wane of that religion all over India, there may have been economic agents at work, like the decline of the sea-borne trade with the West, which had caused vast quantities of Roman gold to pour into the Peninsula. There was also the conquest of Southern India by the Gupta Emperor Samudragupta and the rise of powerful dynasties devoted to Brahmanism like the Pallava in the South and the Chālukya in the West.

In connection with Buddhism attention must be drawn to the mention of sect-names in the Nāgārjunikoṇḍa inscriptions. In Nos. C 1, line 10 and E, line 2, the dedication is stated to be made for the benefit or acceptance of the Aparamahāvinaseliyas. In both cases the sign for *i* over the fifth *akshara* is quite distinct so that we are not allowed to read *-mahāvāna-*, as was done by Drs. Burgess and Hultzsch in the case of an Amarāvati inscription.¹ The latter was inclined to associate the name with the Mahāvānaśālā at Vāsālī, well-known from the Buddha legend. The Amarāvati inscription in question, however, has certainly *Mahāvinaseliyānam*. At the end of the fragmentary Prakrit inscription from Allūru we read: *ayirāna[m] Puvaseli-y[ā]na[m] niḡāyasa* (Skt. *āryānām Pūvaśālīyānām nikāyasya*).

The Pali chronicles of Ceylon make mention of the Iubla- and the Apara-selikas, the two sub-divisions of the Mahāsaṅghikas.² The latter of those two expressions is perhaps an abbreviated form of the Avaramahāvinaseliyas in our inscriptions. Can it be that the two sects,

¹ Burgess, *Amarāvati*, p. 105, No. 49; and Hultzsch, *Z. D. M. G.*, Vol. XXXVII, pp. 550 f., and XL, p. 314.

² *Mahāvamsa*, V, 12, and *Dipavamsa*, V, 54.

known as Pubba- and Aparas-elikas, originated from the two Buddhist convents of Pubbasela and Aparasela which, according to Hiuen Tsiang, existed on the hills to the east and the west of the capital of Dhaññakataka ?

The inscription G, line 8, contains the name of another Buddhist sect—Bahusuttiya—which corresponds to Pali Bahusuttiya (Skt. Bahuśrutiya). Besides, we have Ayira-haṁgha (Skt. *Ārya-saṅgha*) in C 1, line 11 and C 2, line 10, and Mahi[sā]saka (Skt. Mahīśāsaka) in H, line 12.

Language and Script.

A considerable difficulty in the way of interpreting the Nāgārjunikoṇḍa inscriptions is the want of precision of which they show ample evidence. Considering that these inscriptions were meant to be perpetual records of pious donations made by ladies of royal blood, the careless manner in which they have been recorded is astonishing. Not only single syllables but whole words have been omitted. We find, moreover, that only in one instance it has been considered necessary to correct such an omission, *i.e.*, in the word *Mahāchetiya* (E, line 1) where the *akshara hā* has been placed under the line. In other instances syllables have been repeated (C 2, lines 1 and 3), or interchanged (*e.g.*, *bhaṁkham* for *khaṁkham* in C 4, line 7). Very often the length of the vowels *ā* and *ī* is not marked. Even the name of the reigning monarch, Siri-Virapurisadata, is written with *vi* instead of *vī* except in a very few cases where we find the correct spelling with *ī*. Much less frequently the long *ī* has been substituted for the short one, *e.g.*, in *Mahāchetiya*. Considering the frequency of the omission of the *ā*-stroke, we have ventured to assume that this omission has twice taken place in the long compound *samaṇa-baṁhāṇa-kavaṇa-vaṇija-dīn-ā-nugaha-velāmika-dāna-paṭibhāga-rochhina-dhāra-palāyini*, which re-occurs several times in the passage relating to the principal donor, Chāntisiri. This compound, as far as we can see, does not yield an intelligible sense, unless we read *-dān-āpaṭibhag-ārochhina*, thus assuming that the two adjectives required here are *apaṭibhaga* and *arochhina*. With regard to the latter word we may compare the use of the Sanskrit equivalent *avyavachchhinna* in the following line from the *Harivaṁśa* (verse 3580) where we read : *avyavachchhinna-dhār-aughaiḥ samudr-ugha-samair-dhanaiḥ*.

The sign for *dha* is sometimes substituted for that of *tha*, whereas a certain confusion seems to prevail between *tha* and *tha*. The looped characters *ta* and *na* are very similar and are not always clearly distinguishable. The same is the case with the *aksharas*, the initial *a* and *su*.

The sign for *anusvāra* too has often been omitted, while in several cases it is difficult to decide whether what appears to be a dot over the *akshara* may not be a depression in the surface of the stone merely due to accident. In consequence, there prevails a certain amount of uncertainty with regard to the correct form of the personal names Chāntamūla and Chāntisiri. In several cases where these names occur, there is no trace of an *anusvāra*, but as in a few instances such a sign can be made out, we are perhaps justified in assuming that its non-occurrence is due to the inadvertence so noticeable throughout these records.

This want of precision becomes especially manifest if we compare the various redactions of the inscription recording the grant of a stele by the chief donor, the lady Chāntisiri. It is clear that these redactions are all based on the same text, but none of them produces that text without some omissions or mistakes. We may refer the reader to the text of C 3 given below with the various readings found in the corresponding inscriptions.

It is difficult to say who is to be held responsible for the negligent treatment which we have noticed in these epigraphs. The additional passage found in two of the pillar inscriptions of Chāntisiri, namely C 1 and 2, mentions a “Bhadanta Ānanda, carrier of the *Dīgha*- and the *Majjhima-nikāya*” who acted as the *navakammika* of the Mahāchetiya. In the case of the apsidal temple

and other religious works founded by the *upāsikā* Bodhisiri there were even three *navakammikas*, the *theras* Chaṇḍamukha, Dhammanandi and Nāga (F, lines 3 & 4). As the *navakammika* was the monk commissioned by the *Saṅgha* to superintend the foundation (*navakamma*) dedicated by some lay-member, his responsibility may be supposed to have extended also over the inscriptional records of the *deyadhamma*. It is, however, quite possible that the author of the inscriptions was some other learned member of the *Saṅgha*. We may perhaps assume that, the text of the inscriptions having been fixed, some copyist, either a *bhikkhu* or a professional writer, was employed to prepare one or more copies in the very ornamental writing of the period for the use of the stone-mason. At the end of inscription F we find the name of the stone-mason (*sela-vaḍḍhiki*) Vidhika recorded immediately after those of the three *navakammikas*. It must be admitted that, as regards its technical execution, not only this epigraph but also the sixteen *āyaka*-pillar inscriptions leave nothing to be desired. It is noteworthy that inscription H which, as we saw, must belong to a somewhat later period, shows at once a marked deterioration in technical skill.

With regard to the style of writing used in the Nāgārjunakoṇḍa inscription, it will suffice to refer to the observations made by Dr. Bühler with regard to the inscriptions from Jaggaya-peṭṭa.¹ Here we wish only to draw attention to the use of *la* in *Sihala-talākam*, and *aḷaṇḍā* in F, line 3, and to the occurrence of the following ligatures: *dra* in *Rudradhara*° (B 5, line 4), *nhā* in *sumnhanam* (F, line 3), *ṇhu* in *Vinhusirisa*, *mha* in *bamhaṇa* (A 3, line 6 etc.), *mhi* in *inamhi* (A 3, line 2) and *mahāchetiyamhi* (C 4, line 2 and X, line 8), and *tī* in *nattiya* (H, line 8).

The inscriptions contain the numerical symbols for one, three (F, line 1), four (F, line 1), five (E, line 2), six (*passim*), seven (F, line 3 and H, line 4), eight (E, line 2), ten (*passim*), seventy (B 5, line 6), and hundred (B 5, line 6).

As regards the language, the following peculiarities may be noted:—

The *ri* vowel is represented by *a* in *kavaṇa* (Skt. *kripaṇa*) and *vasabha* (Skt. *vrishabha*), but elsewhere, by *u*. Examples: *bhatuno* (F, line 2) from Skt. *bhatṛi*-; *putuno* (F, line 2) from Skt. *pitṛi*-; *bhātuno* (F, line 3), *bhātunam* (F, line 2) and *bhātuputānam* (F, line 2) from Skt. *bhrātṛi*-; *mātuya* (F, line 2 and G, line 7) from Skt. *māṭṛi*-; *mahāmātukāya* (F, line 2) from Skt. *mahāmāṭṛi*-; *dhūtuya* (F, line 3; H, line 9) from Skt. *duhṛi*-; *jām[ā]tukasa* (E, line 1) from Skt. *jāmāṭṛi*-; *mātuk[ā]* (C 1, line 11 and C 2, line 9) from Skt. *māṭṛikā*.

We notice *Svarabhakti* in *bharyā* (*passim*) from Skt. *bhāryā*; *mahāchetiya* (*passim*) from Skt. °*chaitya*; *achariya* (*passim*) from Skt. *āchārya*; *harisa* (F, line 1) from Skt. *harsha*; *tarisa* (F, line 1) from Skt. *tarsha*; *darisana* (F, line 1) from Skt. *darśana*; and *mahāsenāpatini* (*passim*) from Skt. °*patni*. Cf. Pischel, *Grammatik der Prakrit-Sprachen*, §135.

The *p* between vowels becomes *v*. Examples: *Avaranta* (F, line 1) from Skt. *Aparānta*; *kavaṇa* (*passim*) from Skt. *kripaṇa*; *uvāsikāya* (F, line 2) from Skt. *upāsikā*; *uvarivam[ā]tam*] (F, line 3) from Skt. *upari*°; *th[ā]vitam* (F, line 3) from Skt. *sthāpitam*; *Govaḡama* (F, line 2) from Skt. *Gōpagrāma* (?); *maṇṭava* (E, line 2) and *maṇḍava* (F, line 3) from Skt. *maṇḍapa*.

The *media* is changed into the *tenuis*, in *koṭh[ā]kārika*° (F, line 2) from Skt. *kōṣṭhāgārika*-; and *maṇṭava* (E, line 2) from Skt. *maṇḍapa*. But elsewhere *maṇḍava* (thrice in F). Cf. also *deya-dhama-parichāko* from Skt. °*parityāga*-, in the Allūru fragmentary inscription, line 14.

The *tenuis* has been changed into the *media* in *Pugiyāna[m]* (E, line 1), but elsewhere *Pūkiyānam* or *Pūkiyānam*, and *sughāya* (G, line 10) from Skt. *sukha*-. Cf. *nigūyasa* from Skt. *nikāya*- in the Allūru inscription. As regards *Pūkiya* and *Pūgiya*, it is, of course, possible that the latter is the more correct and original form. May it be connected with Skt. *pūya* = "betel-palm" ?

¹ G. Bühler, *Indische Palaeographie*, p. 44.

The initial *h* in some personal names appears to have been developed from *s*. Examples : *Haṃmasiri* (C 4, line 5) ; *Haṃmasiriṇikā* (C 2, lines 5-6 and 7 ; C 4, line 7) ; *Haghaṃna* (F, line 2). Also, *Ayira-haṃghāna* (C 1, line 11 ; C 2, line 10) from Skt. *Ārya-saṃghānām*. But *saṃghaṃ* (H, line 13) and *mahābhikṣu-sa[m]ghasa* (E, line 2).

We wish also to draw attention to the following forms : *ayira-* (C 1, line 11 ; C 2, line 10) from Skt. *ārya* ; *bhayā* for the more usual *bhāriyā* from Skt. *bhūryā* ; and *Chilāta* (F, line 1) from Skt. *Kirāta*.

LIST OF INSCRIPTIONS.

a. Inscriptions on the āyaka-pillars of the Mahāchetiya.¹

A. 2. East side, second pillar. One large and two small fragments. The large piece contains lines 1—7 (*sidham* to =*vachhalā ma-*), line 7 being incomplete. Besides, there is a gap on the right hand side by which several *aksharas* at the end of lines 2—4 and 6 are lost. One of the smaller fragments supplies the initial *aksharas* of lines 6—10, and the other, a few *aksharas* of lines 7—8. The inscription, when entire, must have consisted of 10 lines, 24½ inches long. It records the gift of a pillar by the *Mahātālavari* Chāṃtisiri (name lost), the sister of King Chāṃtamūla and the paternal aunt of King Siri-Vīrapurisadata. Date lost.

A. 3. East side, third pillar. Inscription in two pieces. One large piece contains the inscription almost complete except the middle portion of lines 1—2. This missing portion is supplied by the smaller fragment containing 17 *aksharas* of the first line. The inscription consists partly of 10 lines, 25 inches long. It records the donation of a pillar by Chāṃtisiri (*cf.* sub A. 2). Date, the 6th year of King Siri-Vīrapurisadata in last short line.

A. 4. East side, fourth pillar. Two large and one smaller fragment. The one large piece contains ll. 1—5, incomplete and partly obliterated. The other contains lines 5—11, *viz.*, the latter half of the inscription, almost complete, although partly indistinct. The small fragment supplies the initial *aksharas* of lines 1 to 3. The inscription must have consisted of 11 lines, measuring from 21—22½ inches in length. Donation of a pillar by Chāṃtisiri (*cf.* sub A. 2). Date as above sub A. 3 in last short line.

B. 1. South side, first pillar. One fragment, containing lines 1—6 in their full length, but with central portion completely obliterated. Length of lines 16 inches. Name of donor and date lost.

B. 2. South side, second pillar. Inscription complete in 7 lines, measuring 20 to 22 inches in length. Gift of a pillar by the *Mahātālavari* Aḍavi-Chāṃtisiri, the daughter of King Chāṃtamūla. Date as above.

B. 3. South side, third pillar. Complete in 10 lines, measuring 21 to 23½ inches in length. A few *aksharas* at the end of lines 5—9 missing. Donation of a pillar by Chāṃtisiriṇikā, evidently the same person as Chāṃtisiri (*cf.* sub A. 2). Date as above in last short line.

B. 4. South side, fourth pillar. Complete in 7 lines, 17½ to 22 inches. Gift of a stone pillar by the *Mahāsenāpatini* Chula-Chā[m]tisiriṇikā. Date as above in 6th and short 7th line.

B. 5. South side, fifth pillar. Complete in 7 lines, 20 to 22 inches. Gift of a pillar by *Mahādēvi* Rudradharabhaṭ[ā]rikā. Date as above in last short line.

¹ Besides the āyaka-pillar inscriptions enumerated here, twenty-three small fragments have been found which must have belonged to this class of inscriptions.

C. 1. West side, first pillar. Two pieces: the smaller piece, containing lines 1 to 6 (l. 1 complete, l. 2 with the first *akshara* missing, ll. 3—6 incomplete), fits wedge-like into the larger one, which consists of ll. 3 to 13, ll. 3 to 6 supplying the missing portions of the upper piece. The inscription, when complete, consisted of 13 lines, 21 to 23 inches long. Donation of a pillar by Chāmtisiri. Date as above.

C. 2. West side, second pillar. Two pieces. The larger piece contains ll. 1—6 complete, besides the initial and concluding portions of ll. 7—9. The smaller piece supplies the middle portions of these three lines and the remainder of the inscription, viz., ll. 10—12 entire. Twelve lines, 19½ to 22 inches long. Gift of a stone pillar by *Mahādēvi* Bapisiriṇikā, the daughter of Harṇmasiriṇikā and wife of King Siri-Virapurisadata. Date as above in ll. 11—12, the concluding line being a short one.

C. 3. West side, third pillar. Two pieces. The smaller fragment has 6 lines, viz., l. 1 complete, whereas considerable portions of ll. 2—5 are missing and only a few *aksharas* at the beginning of l. 6 remain. The larger fragment contains the missing parts of ll. 2—6 and, besides, ll. 7—13 entire. Thirteen lines, 20 to 22 inches long. Gift of a pillar by Chā[m]tisiri. Date as above in last short line.

C. 4. West side, fourth pillar. Complete in eight lines, 19 to 22 inches long. Gift of a pillar by *Mahādēvi* Chhaṭhisiri, the daughter of Harṇmasiri[ṇikā] and wife of King Siri-Virapurisadata. Date as above in concluding line.

C. 5. West side, fifth pillar. Complete in five lines, 19½ to 20½ inches in length. Gift of a stone pillar by the wife of Mahākāṇḍasiri. Date as above.

D. 2. North side, second pillar. One piece containing ll. 1—5 complete, the initial and concluding portions of ll. 6—7, the first six *aksharas* of line 8 and only one *akshara* opening line 9. The inscription must have recorded the gift of a pillar by Chāmtisiri. Date lost.

D. 3. North side, third pillar. Only a fragment containing ll. 1—2 almost complete, and besides, a few *aksharas* of line 3. Date lost.

D. 4. North side, fourth pillar. Complete in ten lines, 19½ to 21½ inches long. Gift of a pillar by Chā[m]tisiri. Date as above in last short line.

X. Original position unknown. Complete in nine lines, 24 to 25 inches in length. Donation of a pillar by Chāmtisiri. Date as above.

b. Chetiya-ghara inscriptions.

E. Inscription on floor of apsidal shrine, No. I, immediately to the east of the Mahāchetiya. Inscription complete in two lines, measuring 14 feet 5 inches. Average size of *aksharas* ½ to ⅔ inch. Inscription well preserved except first portion of the second line. It records the dedication of a *chetiya-ghara* or stone *maṇḍava* (Skt. *maṇḍapa*) provided with a cloister (*chatusāla*) at the foot of the Mahāchetiya by the *Mahātālavarī* Chāmtisiri, mentioned in several of the *āyaka*-pillar inscriptions, who here refers to King Siri-Virapurisadata as her son-in-law, for the benefit of the Masters of the Aparamahāvīnaseliya sect. Date, the eighteenth year of King Siri-Virapurisadata.

F. Inscription on floor of the apsidal shrine, No. II, on the mound Nāharāḷlabōḍu, consisting of three long lines, 18 feet 4 inches to 19 feet in length, and of a fourth short line of 1 foot 9 inches. Average size of *aksharas* ⅔ to ¾ inch. The inscription is fairly well preserved; here and there some *aksharas* have been lost. After a lengthy invocation of the Buddha it records the foundation of a *chetiya-ghara* and of various other religious edifices by an *uvāsikā* (Skt. *upāsikā*), named Bodhisiri, together with her relatives, for the benefit of the fraternities (*theriya*) of the Ceylonese monks who had converted a number of countries which are enumerated at great length. Date, the fourteenth year of King Māṭhariputa (=Siri-Virapurisadata?).

c. Detached pillar inscriptions.

G. Inscription on a stone pillar or stele decorated with carvings, at a distance of about two furlongs to the north-west of the Mahāchetiya. It consists of ten lines of writing. The inscribed surface shows three cracks and the right hand portion damaged. Some three or four *akṣaras* at the end of ll. 1—5 are lost. Lines 9 and 10 are partly obliterated. The lines, when complete, must have been 15 inches in length. The average size of the *akṣaras* is $\frac{1}{2}$ to $\frac{3}{4}$ inch. The lettering has become worn owing to exposure to the weather. The inscription records the foundation of a *vihāra* by *Mahādēvi* Bhaṭṭidēvā, who was the wife (?) of King Siri-Virapurisadatta and the mother of King Ehuvaḷa(?)—Chā[m]tamūla. The date in ll. 9—10 is no longer legible.

H. Inscription on a stone pillar or stele found at Koṭṭampalugu to the north of Nāgārjunikonda. It consists of fourteen lines of writing, measuring about 12 inches in length. The inscription is fairly well preserved, but here and there some *akṣaras* have become indistinct. The execution is fair, but less ornamented than in the earlier inscriptions. The size of the *akṣaras* is from $\frac{3}{8}$ to $\frac{1}{2}$ inch; they miss the long-drawn strokes of the earlier inscriptions and the lines are placed close together. The inscription records the foundation of a *vihāra* by *Mahādēvi* Koda[ba]ḷisiri, who was the daughter of King Siri-Virapurisadatta, sister of King Ehuvaḷa-Chā[m]tamūla, and wife of the Mahārāja of Vanavāsa. It is dated in the 11th year of King Ehuvaḷa-Chā[m]tamūla.

d. Inscriptions on sculptures.

J. Inscription along the lower edge of a frieze showing the adoration of the Wheel of the Law (first sermon at Benares) in the centre and an amatory couple or *mithuna* on both sides. These three scenes are separated and flanked by railings. The frieze is supported by a row of crouching lions. The inscription consists of two lines, measuring 38 and 16 inches in length. The execution is fair and the preservation, satisfactory. The average size of the *akṣaras* is $\frac{1}{2}$ inch. The inscription opens with an invocation of the Buddha and records the donation of a slab and of a coping stone at the Mahāchetiya by an individual of the name of Chhadakapavaticha and by his housewife Padumavāni together with their sons and daughters. No date.

K. Inscription along the lower edge of a long sculptured beam found on the mound Polugubōḍu. It consists of one line of writing, the beginning and concluding portions of which are almost entirely obliterated. The inscription, as far as preserved, measures nearly five feet in length. It records the donation of a slab (?) by a person whose name is lost, together with his sons, daughters, sons-in-law, grandsons, granddaughters, relatives and friends. The preserved portions contain no date.

TRANSCRIPTS AND TRANSLATIONS.

Āyaka-pillar inscription C 3.

The text of the *āyaka*-pillar inscription recording the donation of such a pillar by Chā[m]-tisiri occurs in nine redactions, namely, A 2, 3 and 4, B 3, C 1 and 3, D 2 and 4, and X, seven of which are complete and two (A 2 and D 2) are incomplete. In C 1 there is an addition at the end, whereas in X the invocation of the Buddha opening the document has been omitted. It will be sufficient to reproduce the text only once, as given in C 3, noting such *variae lectiones* as are found in the other redactions. The additional passage of C 1 will be given separately.

TRANSCRIPT.

(1. 1) Sidham namo¹ bhagavato devarāja-sakatasa supabudha-bodhino² savamñuno
(1. 2) sava-sat-ānukampakasa jita-rāga-dosa-mcha-vipamutasa mahāgaṇi-vasabha- (1. 3) [gaṇ]dha-
hathisa samma-saṃ[budh]asa dhātuvara-parigahitasa mah[ā]chete³ mahārajasa (1. 4) Virūpa-
khaṇḍa-Mahāsena-parigahitasa⁴ hiraṇa-koṭi⁵-go-satasahasā-hala-sa- (1. 5) tasaha[sa]-dāyisa
savathesu apatihata-saṃkapasa Vāsīthiputasa⁶ Ikhākusa (1. 6) Siri-Chātāmūlasa⁷ sodarā
bhagini raṇño Māḍhariputasa⁸ Siri-Virapurisadatasa (1. 7) pituchhā mahāsenāpatisa⁹
mahātavalavasa Vāsīdhiputasa¹⁰ Pūkiyānaṃ¹¹ Kaṇḍasiri[sa]¹² (1. 8) bhariyā samaṇa-
bam[h*]aṇa-kavaṇa-vanijaka¹³-dīn-ānugaha-velāmika¹⁴-dāna-paṭibhaga¹⁵-vo- (1. 9) chhimna¹⁶-
dhāra-padāyini sava-sādhū-vachhalā mahādānapatini¹⁷ mahātavalavari Khamdasāgarāmnaka-¹⁸
mātā (1. 10) Ch[ā]tisiri¹⁹ apano ubhaya-kulasa aticchhitam-anāgata-vaṭamānakānaṃ²⁰
parināmetunaṃ²¹ (1. 11) ubhaya-loka-hita-sukh-āvahathanāya²² atano cha nivāṇa-
saṃpati-saṃpādake (1. 12) sava-loka-hita-sukh-āvahathanāya²⁴ cha imaṃ khambham
patithapitaṃ ti (1. 13) Raṇño Siri-Virapurisadatasa sava 6 vā pa 6²⁴
diva 10

¹ Invocation of Buddha omitted in X.

² *supabudha-bodhino* up to *samma-sambudhasa* omitted in B 3, l. 1; C 1, l. 1; D 2, l. 1; D 4, l. 1.

³ *imamhi mahāchete* in A 4, l. 3; D 4, l. 1 (*mahāchete*); *imamhi mahāchete* in A 3, ll. 2-3; D 2, l. 1; *mahāchete* in A 2, l. 3.

⁴ *Virūpakhaṇḍa-Mahāsena-parigahitasa* omitted in D 2, l. 2. *Agīhot-Agīhoma-Vāḍapey-Asamedha-yijisa* after *-parigahitasa* in A 2, ll. 3-4; A 3, ll. 3-4; A 4, l. 4; *-parigahitasa* in B 3, l. 2; D 4, l. 2.

⁵ *hiraṇa-koṭi* in A 2, l. 4; A 3, l. 4; B 3, l. 3; D 4, l. 3.

⁶ *Vāsīthiputasa* in A 3, l. 5; A 4, l. 5; B 3, l. 4; X, l. 3; *Vāseṭhiputasa* in C 1, l. 4; *Vāsīthi* in D 2, l. 3; *Vāsīdhi* in D 4, l. 4.

⁷ *Chātāmūlasa* in A 2, l. 5; A 3, l. 5; A 4, l. 5; C 1, l. 5; D 4, l. 4; X, l. 3.

⁸ *Māḍhariputasa* omitted in A 3, l. 5; D 4, l. 5; *Māḍhariputasa* in A 4, l. 6; X, l. 3.

⁹ *senāpatisa* omitted in X, l. 4.

¹⁰ Read: *Vāsīthiputasa* with A 4, l. 6; B 3, l. 6; C 1, l. 6; X, l. 4. The reading is *Vāsīthiputasa* in A 2, l. 6; *Vāseṭhi* in D 2, l. 5; *Vāsīdhi* in D 4, l. 5.

¹¹ *Pūkiyānaṃ* in B 3, l. 6; X, l. 4.

¹² *Kaṇḍasiri* in A 4, l. 7; D 4, l. 6; X, l. 4. Omitted in A 3, l. 6.

¹³ *-vaṇija-* in A 3, l. 6; *-vaṇijaka-* in A 4, l. 7; B 3, l. 6; C 1, l. 7; D 2, l. 5; D 4, l. 6; X, l. 5.

¹⁴ *velāmika* in A 4, l. 7; *-velāmi-* in B 3, l. 7; D 2, l. 6.

¹⁵ Read: *paṭibhaga*, the reading of A 2, l. 7; A 4, ll. 7-8; B 3, l. 7; C 1, l. 7; D 2, l. 6; D 4, l. 6; X, l. 5.

¹⁶ *vochhina* in A 2, l. 7; A 3, l. 7; A 4, l. 8; B 3, l. 7; C 1, l. 7; D 4, l. 6; X, l. 5.

¹⁷ *mahādānapatini* omitted in B 3, l. 7; D 2, l. 6; D 4, l. 7.

¹⁸ *Khamdasāgarāmnaka-* in A 3, l. 7; A 4, l. 8; C 1, l. 8; X, l. 6. *Khada-* in D 2, l. 7; D 4, l. 7.

¹⁹ *Chātīsiri* in A 3, l. 7; A 4, l. 9; C 1, l. 8; X, l. 6. *Chātīsiri* in B 3, l. 8.

²⁰ *-vaṭamānake* in B 3, l. 8; D 4, l. 8; X, l. 7.

²¹ *parināmetuna* in A 3, l. 8; A 4, l. 9; *parināmetuna* in D 4, l. 8; *parināmetuna* (?) in X, l. 7; *apano ubhaya-kula-parināmetuna* in C 1, l. 8

²² *ubhaya-loka-sukha-nivāṭathanāya* in A 3, l. 8; A 4, l. 10; X, l. 7. Omitted in B 3, l. 9; C 1, l. 9; D 4, l. 8.

X, l. 8 has after *-saṃpādake* the following: *bhagavato samma-sambudhasa dhātu- (dhātu)vara-parigahitasa mahāchete* *imamhi*.

²³ *-sukha-nivāṭathanāya* in A 3, l. 9; A 4, l. 10 (?); D 4, l. 9. *Sava-loka-* omitted in B 3, l. 9.

²⁴ *vā pa 6* written under the line. In A 3, l. 10 and A 4, l. 11 these *aksharas* have been omitted.


C-3.

1. ...
2. ...
3. ...
4. ...
5. ...
6. ...
7. ...
8. ...
9. ...
10. ...
11. ...
12. ...


C-1.

1. ...
2. ...
3. ...
4. ...
5. ...
6. ...
7. ...
8. ...
9. ...
10. ...
11. ...
12. ...

B-1.



B-2.



TRANSLATION.

Adoration to the Lord, the Supreme Buddha, honoured by the Lord of the gods, the most compassionate towards all sentient beings, freed from lust, hatred and delusion which he has conquered by him, the bull and musk-elephant among great spiritual leaders, the Enlightened One, who is absorbed by the best of elements (*i.e.*, by Nirvāṇa). At the same time, the *Mahātūlavara* Chā[ti]tisiri (*who is*) the uterine sister of Mahārāja Vāsīṭhīputa the son of Śrī[ti]jamūla—absorbed by Mahāsena the lord of Virūpakhas, the giver of crores and hundred thousands of kine, and hundred thousands of ploughs (*of land*) unimpeded by the sea and the mountains, —(*she who is*) the paternal aunt of King Māḍharīputa Siri-Virapurisadata, the wife of the *Mahāśeṇāpati*, the *Mahātūlavara*, Vāsīṭhīputa Karīdasiri of (*the*) Pūliyas; and the mother of Khamīdasāgaratūnaka, she who, out of compassion for Śāmas, Bāhmins, and those that are miserable, poor and destitute, is wont to bestow on them an unrelenting and ceaseless flow¹ of Velānic gifts, she, the great mistress of munificence, loved by all the virtuous, having due regard for the past, future and present (*members*) of both the beings to which she belongs, for the attainment of welfare and happiness in both the worlds and in order to attain herself the bliss of Nirvāṇa and for the attainment of welfare and happiness of all the world, has erected this pillar. In the 6th year of (*the reign of*) King Siri-Virapurisadata, the 6th fortnight of the rainy season, the 10th day.

Additional Passage in C 1.²

TRANSCRIPT.

(l. 10) āchariyānaṃ Aparamahāvīnaś[e]liyāna[m] supariḡahitaṃ imaṃ mahācetiya-
navakamaṃ[m] (l. 11) Paṃḡagāma-vathavānaṃ Dīgha-Majjhima-pa[m]cha-mātuka-osaka³.
(l. 12) āchariyānaṃ āchariyānaṃ Ayira-haṃghāna[m] (l. 12) a[m]tevāsikena Dīgha-Majjhima-
nikkai-dharena bhajant-ānadena⁴ nithapitaṃ imaṃ navakamaṃ mahācetiyaṃ (l. 13) khambhā
cha thūpā tā tā rāṃṇo Siri-Virapurisadatasā sava 6 va pa 6 diva 10

TRANSLATION.

For the benefit of the Masters of the Aparamahāvīnaseliya sect this pious foundation of the Mahācetiya has been completed by the Reverend Ānanda, who knows the *Dīgha*- and the *Majjhima-nikāyas* by heart, (*who is*) a disciple of the Master of the Ayira-haṃgha (Skt. *Ārya-saṅgha*) who are resident in Paṃḡagāma and who are preachers and preceptors of the *Dīgha*, the *Majjhima-nikāya* and of the five *Mātukas*. This pious work, the Mahācetiya, was completed and the pillars were erected. In the 6th year of (*the reign of*) King Siri-Virapurisadata, the 6th fortnight of the rainy season, the 10th day.

Āyaka-pillar inscription B 1.

TRANSCRIPT.

(l. 1) Sidhaṃ mahārājasa....sena-pariḡahitasa Agiho-(l. 2) t-Āgīthoma-Vāja.....[hi]
rana koṭi-go-sata- (l. 3) sahasa-hala....savathesu apati- (l. 4) hata-sa[m]kapaśa V[ā]se.....

¹ My translation is based on the assumption that we must read *-dān-āpatihhāg-avochāna-*.

² *i.e.* the corresponding passage in line 8 of the *āyaka*-pillar inscription C 2, *infra*.

³ Read : *-desaka-* (C 2, l. 9).

⁴ Read : *bhaddant-ānadena* (C 2, l. 10).

Chātāmūlasa bhagini- (l. 5) ya mahātalava[rasa]...[si]risa bha[riyā]ya ma- (l. 6) hātala-variya...mah[ā]r[ā]jasa

[The inscription is too fragmentary to admit of translation. It, evidently, opens with the string of epithets eulogizing King Siri-Chā[m]tamūla. The donor, whose name is lost, was, perhaps, a daughter of Chā[m]tisiri.]

Āyaka-pillar inscription B 2.

TRANSCRIPT.

(l. 1) Sidham mahārajasa Asamedha-yājisa aneka-hiraṇṇa-koṭi-go-satasahasā-bala-sata- (l. 2) sahasa-padāyisa savathesu apatihata-saṃkapasa Vāsīthīputasa Ikhākusa (l. 3) Siri-Chā[m]tamūlasa duhutā raṇṇo Siri-Virapurisadatasa bhagini mahāsenāpatisa mahā- (l. 4) talavarasa mahādāṇḍanāyakasa Dhanakāṇaṃ Khamdavisākharāṇakasa bhayā mahātalavari (l. 5) Adavi-Chātīsiri apāno ubhaya-kulam parināme[tū]na atano cha ubhaya-loka-hita-sukh-āva-hathanāya (l. 6) bhagavato saṃma-sabudhasa² dhātuvara-parigahītasā Mahāchetiye imam khambham patidhapaṃta¹ ti (l. 7) raṇṇo Siri-Virapurisadatasa saṃva 6 vā pa 6 diva 10

TRANSLATION.

Success The *Mahātalavari* Adavi-Chātīsiri (*who is*) the daughter of the Mahārāja Vāsīthīputa Ikhāku Siri-Chā[m]tamūla, the offerer of Aśvamēdha, the giver of many crores of gold, hundred thousands of kine, and hundred thousands of ploughs (*of land*), of unimpeded purpose in all (*his*) aims; (*who is*) the sister of King Siri-Virapurisadata, (*and who is*) the wife of the *Mahāsenāpati*, the *Mahātalavara*, the *Mahādāṇḍanāyaka* Khamdavisākharāṇaka (*of the family*) of the Dhanakas, having due regard for both the houses to which she belongs and for the attainment by herself of welfare and happiness in both the worlds, has erected this pillar at the Mahāchetiya of the Lord, the supreme Buddha who is absorbed by the best of elements (*i.e.*, by Nirvāṇa). In the 6th year of (*the reign of*) King Siri-Virapurisadata, the 6th fortnight of the rainy season, the 10th day.

Āyaka-pillar inscription B 4.

TRANSCRIPT.

(l. 1) Sidham namo bhagavato devarāja-sakatasa supabudha-bo[dhino*] savamūno sava-sa[t-ā-](l. 2) nukaṇṇapakasa jita-rāga-dosa-moha-vipamutasa mahāgaṇi-vasabha-gaṇḍha-ha[thisa] (l. 3) saṃma-saṃbugasa² dhātuvara-parigahītasā mahācheti[ye] Kulahakāṇa-[m] bālīkā (l. 4) mahāsenāpatisa mahātalavarasa Vāsīthīputasa Hiraṇṇakāṇaṃ Khamdachalikireṇṇaṇakasa[sa] (l. 5) bhayā mahāsenāpatini Chula-Chātīsiriṇikā apāno ubhaya-loka-hita-sukha-ni- (l. 6) vāpathanāya imam sela-khambham patīṭhapitam ti raṇṇo Siri-Virapurisadatasa (l. 7) saṃva 6 vā pa 6 diva 10


TRANSLATION.

Success! Adoration to the Lord, the Supreme Buddha, honoured by the Lord of the gods, enlightened with perfect enlightenment, omniscient, compassionate towards all sentient beings, freed from lust, hatred and delusion conquered by him, the bull and musk-elephant among great spiritual leaders, absorbed by the best of elements (*i.e.*, Nirvāṇa). At the Mahāchetiya, the


¹Read : *patīṭhapitam*.


²Read : *sambudhasa*.


B-4.





B-5.





1.  1


2.  2

3.  3

4.  4

5.  5

6.  6

7.  7


8. 8


9. 9


10. 10


11. 11


12. 12


1.  1

2.  2

3.  3

4.  4

5.  5

6.  6

7. 7

8. 8

9. 9

10. 10

11. 11

12. 12

Mahāsenāpatini Chula-Chāṭisiriṇikā, (who is) a daughter of (the family of) the Kulahakas, and the wife of the *Mahāsenāpati*, the *Mahātalavara*, Vāsithīputa Kharṇdachalikireṇmaṇaka of (the family of) the Hiraṇṇakas, for the attainment by herself of welfare and happiness in both the worlds and of Nirvāṇa has erected this stone pillar. In the 6th year of (the reign of) King Siri-Virapurisadata, the 6th fortnight of the rainy season, the 10th day.

Āyaka-pillar inscription B 5.

TRANSCRIPT.

(l. 1) Sidham namo bhagavato devarāja-sakatasa supabudha-bodhino savamūno sava-sat-
[ānu-^{*}] (l. 2) kampakasa jita-rāga-dosa-moha-vipamutasa mahāgaṇi-vasabha-gaṇḍha-hadhisa¹
(l. 3) saṃma-sambudhasa dhātuvara-parigahitasa mahāchetiye Ujanikā² mahārabalikā³ (l. 4)
mahādevi Rudradharabhaṭ[ā]rikā imam sela-khaṃbham apano hita-sukha-nivāṇadhanāya⁴
patith[ā]pitam (l. 5) mahātalavarihi cha Pūkiyānam Chāṭisiriṇikāhi imasa mahāvihārassa
mahāchetiyaṃ⁵ (l. 6) samuthapiyamāne mahātalavariā ubhayitā dināri-māsakā satari-satam
100[+^{*}]70⁶ khaṃbho cha (l. 7) raṃṇo Siri-Virapurisadatasa saṃva 6 vā pa 6 diva 10

TRANSLATION.

Success ! Adoration to the Lord, etc. (see above, sub B 4). At the Mahāchetiya the Mahādēvi Rudradharabhaṭārikā, a Mahārāja's daughter from Ujjeni (Skt. Ujjayini) has erected this stone pillar for the attainment by herself of welfare and happiness and Nirvāṇa. And while the Mahāchetiya of this Great Vihāra was being raised by the ladies, the *Mahātalavaris*, Chāṭisiriṇikā of (the family of) the Pūkiyas, one hundred and seventy (100+70) *dināri-māsakas* and a pillar have been raised by the *Mahātalavari*.⁶ In the 6th year of (the reign of) King Siri-Virapurisadata, the 6th fortnight of the rainy season, the 10th day.

Āyaka-pillar inscription C 2.

TRANSCRIPT.

(l. 1) Sidham namo bhagavato devarāja-sakatasa saṃma-saṃma-sambudhasa⁷ dhātuvara-
(l. 2) parigahitasa⁸ Mahāchetiye mahārājasa Virūpakhapati-Mahāsena-parigahitasa (l. 3) Agihot-
Āgithogithoma⁹ Vājapey-Āsamedha-yājisa hiraṇa-koṭi-go-sata- (l. 4) sabasa-hala-satasahasā-
padāyisa savathesu apatihata-saṃkapasa (l. 5) Vāsithīputasa Ikhākusa Siri-Chātāmūlāsa
sodarāya bhaginiya Haṃma- (l. 6) sirimnikāya bālikā raṃṇo Siri-Virapurisadatasa bhayā
mahādevi Bapisiriṇikā (l. 7) apano mātaram Haṃmasiriṇikāṃ parinamatuna¹⁰ atane¹¹ cha
nivāṇa-saṃpati-saṃpādake (l. 8) imam sela-thaṃbham patithapitam achari[yā]nam Aparā-
mahāvīnaseliyānam superigahita[m^{*}] (l. 9) imam Mahāchetiya-navakamam Paṇṇagāma-
vathavānam Dīgha-Majhima-paṇḍa¹². m[ā]tuka-desa[ka-vā^{*}][chakānam] (l. 10) arayāna[m]¹³

¹ Read : *hathisa*.

² Read : *Ujenikā*.

³ Read : *mahārāja-bālikā*.

⁴ Read : *nivāṇathanāya*.

⁵ Read : *mahāchetiye*.

⁶ The meaning probably is that the Queen Rudradharabhaṭārikā, besides dedicating a pillar, contributed a sum of 170 *dināri-māsakas* towards the expenses incurred by Chāṭisiri for the building of the *stūpa*.

⁷ *saṃma*- has been written twice by mistake.

⁸ Perhaps *parigamhitasa*.

⁹ The two *akṣaras gi tho* have been written twice by mistake.

¹⁰ Read : *parināmetūna(m)*.

¹¹ Read : *atano*.

¹² Read : *paṇḍa* (cf. above, C 1, l. 11).

¹³ Read : *āchariyānam*.

Ayira-haghāna[m] amtevāsikena Dīgha-Manigaya¹-dharena bhadañit-Ānañdena (l. 11) niṭhapita[m] ima[m] navakama[m] mahāchetiya[m] khambhā cha ṭhapitā ti rañño Siri-Virapurisadatasa² (l. 12) sañva 6 vā pa 6 diva 10

TRANSLATION.

Success! Adoration to the Lord, the supreme Buddha, honoured by the Lord of the gods, absorbed by the best of elements. At the Mahāchetiya the Mahādevi Bapasirīṇikā (*who is*) the daughter of Hammasirīṇikā, the uterine sister of Mahārāja Vāsīṭhiputa Ikhāku Siri-Chāntamūla, etc., (see sub C 3) and (*who is*) the wife of King Siri-Virapurisadata, with due regard for her mother Hammasirīṇikā, and for the sake of attainment by herself of the bliss of Nirvāṇa, has erected this stone pillar. For the benefit of the Masters of the Aparamahāvīnasāliya sect has this pious foundation of the Mahāchetiya been accepted. This pious foundation, consisting of the Mahāchetiya, has been completed and the pillars have been set up by the Reverend Ānanda, who knows the *Dīgha*- and the *Majjhima*-(*nikāyas*) (?) by heart, (*who is*) a disciple of the Masters of the Ārya-saṅgha who are resident in Paṇṇagāma and who are preachers and preceptors of the *Dīgha* and the *Majjhima*-(*nikāyas*), and of the five *Mātukas*. In the 6th year of (*the reign of*) King Siri-Virapurisadata, the 6th fortnight of the rainy season, the 10th day.

Āyaka-pillar inscription C 4.

TRANSCRIPT.

(l. 1) Sidham namo bhagavato devārāja-sakatasa¹ sañma-saṃbudhasa dhātuvāra-parigamhitasa (l. 2) mahādetiyamhi² mahārājasa Virūpakhapati-Mahāsena-parigamhitasa Agihāta-³ (l. 3) Agiṭhoma-Vājapey-Āsamedha-vājisa hiraṇṇa-koti-go-satasahasasata-sata- (l. 4) sahasa-padāyisa savathesu apatihata-saṃkapasa Vāsīṭhiputasa Ikhākusa (l. 5) Siri-Chāntamūlasa sodarā-bhaginiya Hammasariya⁴ bālikā mahārājasa (l. 6) Māḍhariputasa Siri-Virapurisadatasa bhayā mahādevi Chhaṭhisiri apano (l. 7) mātaraṃ Hammasirīṇikā parināmetuna atanam⁵ cha nivāṇa-saṃpati-saṃpādake imam bhaṃkham⁶ (l. 8) paṇṭha-pitam mahārājasa Siri-Virapurisadatasa sava 6 vā pa 6 diva⁷ 10

TRANSLATION.

Success! Adoration to the Lord, etc., (see above, sub C 2) the Mahādevi Chhaṭhisiri (Skt. Shash-ṭhīrī), (*who is*) the daughter of Hammasiri, the uterine sister of Mahārāja Vāsīṭhiputa Ikhāku Siri-Chāntamūla, etc., (see above, sub C 3) and (*who is*) the wife of Mahārāja Māḍhariputa Siri-Virapurisadata, with due regard for her mother Hammasirīṇikā and for the sake of attainment by herself of the bliss of Nirvāṇa, has erected this pillar. In the 6th year of (*the reign of*) King Siri-Virapurisadata, the 6th fortnight of the rainy season, the 10th day.

Āyaka-pillar inscription C 5.

TRANSCRIPT.

(l. 1) Sidham namo bhagavato sañma-saṃbu[dha*]sa dhātuvāra-parigamhitasa Mahāchetiya- (l. 2) mahāsenaṇāpatisa mahātalavarasa Vāsīṭhiputasa Pūkiyānam Mahākāṇḍasirisa (l. 3)

¹ Read *Dīgha-Majjhima-nikāya-dharena* (cf. above, C 1, l. 12).

² Read: *Siri-Vira*

³ Read: *mahāchetiyaṃhi*.

⁴ Read: *Agihot-ā*.

⁵ Read: *siriyā*.

⁶ Read: *atano*.


⁷ Read: *khambhā*.

⁸ Read: *diva*.




PRAKRIT INSCRIPTIONS FROM A BUDDHIST SITE AT NAGARJUNIKONDA (III).



E. SECTION-1.



E. SECTION-2.



E. SECTION-3.



bhayā mahāsenāpatisa mahātalavarasa Viṇhusirisa mātā mahātalavari apano (l. 4) ubhaya-kulam parināmetu[na*] atano ubhaya-loka-hita-sukha-nivāṇathaya cha imam (l. 5) sela-khambham patithapitam mahārājasa Siri-Virapurisadatasa sativa 6 vā pa 6 diva 10

TRANSLATION.

Success! Adoration to the Lord, the Supreme Buddha, absorbed by the best of elements. At the Mahāchetiya the *Mahātalavari* (who is) the wife of the *Mahāsenāpati*, the *Mahātalavara* Vāsethiputa Mahākanḍasiri of (the family of) the Pūkiyas and (who is) the mother of the *Mahāsenāpati*, the *Mahātalavara* Viṇhusiri (Skt. Vishṇusri), with due regard to both the families to which she belongs, and for the sake of her own welfare and happiness in both the worlds and Nirvāṇa, has erected this stone pillar. In the 6th year of (the reign of) Mahārāja Siri-Virapurisadata, the 6th fortnight of the rainy season, the 10th day.

First Apsidal Temple inscription E.

TRANSCRIPT.

(l. 1) Sidham namo bhagavato Budhasa chetiya-ghara mahārājasa Virūpakhapati-Mahāsena-parigahitasa Agihot[ā]githoma-Vājapey-Āśamedha-yājisa aneka-hirana-koṭi-go-satasahas-hala-satasa[hasa*]-padāyisa savathesu apatihata-saṅkapasa Vāsethiputasa Ikhākulasa¹ Siri-Chātamūlasa sahodar[ā] - bhagini mahātalavarasa Vāsethiputasa Pugiyāna[m*] Khamḍasirisa bhariy[ā] mahātalavari Khamḍasāgararinnaga-m[ā]tā Chātisiri apano jāma[ā]tukasa raṇo M[ā]tbariputasa Ikh[ā]kunam Siri-Virapurisadatasa ayu-vaḍhanike vejayike (l. 2) apano cha ubhaya-[loka]-hita-sukha-[nivāṇathanāya sarima-sambudhasa dhā-]² tu-parigahitasa mahāchetiya-pādamūle³ pavajitānam nānā-desā-samanāgatānam sava-sādhūnam mahābhikhu-sa[m]ghasa apa[no] cha u-[bhaya-kulasa atichhita[m]-janāgata-vaṭamānake nikapenike cha parināmetunam Aparamahāvinaseliy[ā]nam parigabe sava-niyuta[m] chātusala-parigahitam⁴ sela-maṇṭava[m] patith[ā]pitam raṇo Siri-Virapurisadatasa samvachharam aṭhāra sam 10[+*]⁵ hemanta-pakham chhaṭham 6 divasam paṇchamam 5 sava-satānam hit[ā]ya sukhāya hotu ti

TRANSLATION.

Success! Adoration to the Lord Buddha. A *chetiya-ghara* (*chaitya-hall*). Chātisiri (who is) the uterine sister of Mahārāja Vāsethiputa Siri-Chātamūla of the house of Ikhāku, who is favoured (absorbed?) by Mahāsena, the lord of Virūpakhas, the offerer of Agnihōtra, Agnishtōma, Vājapēya and Āśvamēdha, the giver of many crores of gold, hundred thousands of kine, and hundred thousands of ploughs (of land) and who is of unimpeded purpose in all (his) aims, (who is) the wife of Vāsethiputa Khamḍasiri of (the family of) the Pugiyas and (who is) the mother of Khamḍasāgararinnaga, for the longevity and for the victory of her son-in-law, King Mātbariputa, Siri-Virapurisadata of the house of Ikhāku and for the attainment by herself of welfare and happiness in both the worlds and of Nirvāṇa, having due regard to the past, future and present bliss (?) of the great community of Buddhist monks consisting of all the holy men who have renounced the world and who have penetrated (?) into various countries, and of both the houses to which she herself belongs, has erected a stone shrine surrounded by a cloister and provided

¹ Probably *Ikhāku-kulasa*.

² The *aksharas* placed between square brackets are still partly traceable.

³ The *akshara* *hā* is written under the line.

⁴ Read: *chātusāla*.

with everything at the foot of the Mahāchetiya for the benefit of the Masters belonging to the sect of the Aparamahāvinaseliyas. In the eighteenth year, *anno* 18, of King Siri-Virapurisadata, in the sixth—6th—fortnight of winter, on the fifth—5th—day. May it be for the welfare and happiness of all sentient beings.

Second Apsidal Temple inscription F.

TRANSCRIPT.

(l. 1) Sidham namo bhagavato Ikhāku-rāja-pavara-risi-sata-pabhava-vaṃsa-sambhava-
deva-manusa-sava-sata-hita-sukha-maga-desikasa jita-kāma-kodha-bhaya-harisa-tarisa-moha-
dosa-sada(ā)pita¹. Māra-bala-dapa-māna-pasamana-karasa dasa-bala-maha(ā)balasa aṭha[m*]-
ga-maga-dhamachaka-pavata-kasa chaka-lakhṇa-sukumāra-sujāta-charaṇasa taruṇa-divasa-
kara-pabhasa sarada-sasi-soma-darisanasa sava-loka-chita-mahitasa Budhasa raṇṇo
M[āṭha]riputasa². . . . 10[+*]4 hemanta-pakham chhaṭham 6 divasaṃ teraṃ 10[+*]3. . . . ta [rā]-
jāchariyānam³ Kasmira-Gaṇdhāra-Chīna-Chilāta-Tosali-Avaramita-Vaṅga-Vanavāsi-Yava[na]-
Da[mila-Pa]lura⁴ Tāmbapaṇṇi-dīpa-pas[ā]dakānam theriyānam Tāmbapa[m]nakānam
suparigahe (l. 2) Siripavate Vijayapuriya-puva-disā-bhāge vihāre Chula-Dhammagiriyaṃ
chetiya-gharaṃ sapata-samtharaṃ sachetiyaṃ sava-niyutaṃ kāritaṃ uvāsikāya Bodhisiriya
apāno bhatuno Budhi[m]nakasa pituno cha se Govagāma-vathavasa Revata-gahapatisa
mātuya cha sa Budhamnikāya bhātunam cha se Chamdamukhanasa Karumbudhinasa
Haghamnasa bhaginiya cha Revatimnikāya bhātu-putānam cha Mahā-Chamdamukha-Chula-
Chamdamukhānam bhāgineyānam cha Mahā-Mūla-Chula-Mūlānam apāno cha ayakasa
Mūlavānīyasa ayikāya Budhavānikī[nāya] mātulaka⁵[sa cha] koṭh[ā]kārīkasa Bhadasa
Bodhisammasa Chamdasa Bodhikasa mahāmātukāya Bhadd[ā]ya Bodhiya cha apāno
pituno Budhi[vā]niyasa m[ātuya]. . . . (l. 3) bhātuno Mūlasa bhaginīnam Budhamnikāya
Mūlamnikāya Nāgabodhinikāya cha dhūtuya Viramnikāya putānam Nāgamnasa Viramnasa
cha sumnānam cha Bhadasiri-Misīnam evam-eva cha Kulaha-vihāre chetiya-gharaṃ Sihā-
vihāre bodhi-rukha-pāsādo Mahā-Dhammagiriyaṃ ovarako 1 mahāvi[hā*]re maṇḍava-
khaṃbho Devagiriyaṃ padhāna-sālā Puvasale taḷakam s[am]dā⁶ ma[m*]ḍavo cha Kamtakasele
mahāchetiyasa puva-dāre sela-maṇḍavo Hirumuthuve ovarakā tiṇṇi 3 Papilāyaṃ evarakā
sata 7 Puphagiriya[m] sela-maṇḍavo Dham⁷. . . . vihāre sela-ma[m]ḍavo etaṃ cha savam
uvarivamṇi⁸[taṃ. . . . sā]dhu-vagasa⁹ acharita¹⁰ hita-sukhāya thavitaṃ sava[sā] cha
lokasa imam navakammanam timhi navaka[m]mikehi kāritaṃ Chamdamukha-therena cha
(l. 4) Dhammanamdi-therena cha Nāga-therena cha sela-vaḍhākisa Vidhikasa kamman ti

¹ [I would read °moha-dosasa dapita-Māra°—Ed.]

² The akshara *tha* of *Māthariputasa* is partly preserved. After this word some five or six aksharas are lost. In the absence of any traces of i strokes, the missing word cannot have been *Siri-Purisdatsa*. In all probability it was *samvachcharam*, followed by a word expressing "fourteenth" (*chodam*?).

³ Perhaps *bhadanta-rāj-āchariyānam*?

⁴ The words which I read *Yavana-Damila-Palura* are not quite certain. The *Da* of *Damila* is still legible and the long-drawn top strokes of the remaining two aksharas have led me to the conjectural reading *mila*, the body of the akshara *m* being partly preserved. The *Pa* of *Palura* is conjectural.

⁵ The akshara *sa* of *mātulakasa* is conjectural. As the word is followed by several personal names in the genitive case, one would expect *mātulakānam*, but the akshara *ka* shows no trace of an ā-stroke.

⁶ Perhaps *sela-maṇḍa*?

⁷ Some ten aksharas are lost after *dham*.

⁸ The akshara *taṃ* is conjectural. Perhaps *tasa*.

⁹ The first akshara *sā* has been restored tentatively. The u-stroke of *dhu* is still faintly visible.

¹⁰ The aksharas which I read *acharita* (Skt. *atyanta*) are indistinct.

TRANSLATION.

Success! Adoration to the Lord Buddha, born of a race (*which is*) sprung from hundreds of sages and excellent kings of Ikṣāku's lineage; who has shown the road to welfare and happiness to gods and men and all beings, who has conquered and put down the pride and arrogance of Māra's hosts called lust, anger, fear, desire, thirst, delusion, and hatred; who, great of power, is possessed of the ten powers, who has set in motion the Wheel-of-the-Law (*pertaining to*) the Eight-fold Path, whose graceful and well-formed feet (*are marked with*) the sign of the Wheel, whose splendour is that of the newly risen sun, whose sight is lovely as that of the autumnal moon, and who is magnified by the thoughts of all the world. In the fourteenth—14th—(year) of King Mātharīputa, in the sixth—5th—fortnight of winter, on the thirteenth—13th—day. For the benefit of the masters and of the fraternities (*of monks*) of Taṃbapaṇṇa (Ceylon) who have converted Kashmīr, Gandhāra, China, Chīlāta (=Skt. Kirāta), Tosali, Avaramita (=Skt. Aparānta), Vaṅga, Vanavāsi, Yavana(?), Dāmila(?), Palura(?) and the Isle of Taṃbapaṇṇi (Ceylon). At Siripavata (=Skt. Śrīparvata) on the east side of Vijayapurī at the Convent on the Lesser Dhammagiri a *chaitya*-hall with a flooring of slabs, with a *chaitya* and provided with all the necessities, was caused to be made by the female lay-member Bodhisiri (Skt. Bōdhisiri) for the sake of her own husband Budhinnaka, and of his father, the householder Revata residing at Govagāma and of his mother Budhamnikā and of his brothers Chāṃdamukha, Karumbudhina (*and*) Haghamna and of (*his*) sister Revatinnikā and of (*his*) brother's sons Mahā-Chāṃdamukha (=Skt. Mahā-Chandramukha) and Chula-Chāṃdamukha (=Skt. Kshudra-Chandramukha) and of (*his*) sister's sons Mahā-Mūla and Chula-Mūla, and (*for the sake*) of her own grandfather Mūla-vāṇiya and of her grandmother Budhavāṇikinā and of her maternal uncle(s) (?), the treasurer¹ Bhada (=Skt. Bhadra), Bodhisamma (=Skt. Bōdhisarman), Chāṃda (=Skt. Chandra) (*and*) Bodhika, and of her maternal grandmother Bodhi and of her own father Budhivāṇiya and of her mother (?) of her brother Mūla, of her sisters Budhamnikā, Mūlamnikā, and Nāgabodhinikā, of her daughter Virāṇnikā, of her sons Nāgaṇṇa and Virāṇṇa and of her daughters-in-law Bhadasiri (=Skt. Bhadrāsiri) and Misi (=Skt. Mīsiri). And even thuswise a *chaitya*-hall at the Kulaha-vihāra, a shrine for the Bodhi-tree at the Sihala-vihāra one—1—cell at the Great Dhammagiri, a *maṇḍava*-pillar at the Mahāvihāra, a hall for religious practice at the Devagiri, a tank, verandah² and *maṇḍava* at Puvasea (=Skt. Pūrvaśaila), a stone *maṇḍava* at the eastern gate of the Great Chaitya at Kaṇṭakaśaila³ (=Skt. Kaṇṭakaśaila), three—3—cells at Hirumuṭhuva, seven—7—cells at Papilā, a stone *maṇḍava* at Puphagiri (=Skt. Pushpagiri), a stone *maṇḍava* at the vihāra. And all this above described has been dedicated for the endless welfare and happiness of the assembly of saints and for that of the whole world. This work was caused to be made by the three superintendents of works, the *thera* Chāṃdamukha, and the *thera* Dhammanandi and the *thera* Nāga. (*It is*) the work of the stone mason Vidhika.

Detached Pillar inscription G.

TRANSCRIPT.⁴

- (l. 1) [Si]dham namo bhagavato teloka-dhamma-dhurā-vahaea mahārāṇa[sa Virū-]
 (l. 2) [pa]kṣapati-Mahāsena-parigahitaṣa Agihot-Āgithoma-[Vājape-] (l. 3) y-Āsamedha-y-

¹ Koṭṭhākārika = Skt. kōṣṭhāgārika.

² If *aśadā* is the correct reading, it may perhaps be taken for another form of Pali *ālinda* "a verandah or terrace".

³ The vowel-mark of the fourth *śaila* has the appearance of an o-stroke, but this I believe is due to an error not unfrequent in these inscriptions.

⁴ The first half of the inscription has been restored with the aid of the corresponding passage in other inscriptions.

[ā]y(i)sa hiraṇṇa-koṭi-go-satasaha[sa-hala-ssta-] (l. 4) sahassa-padāi(yi)sa savathesu apatibata-saṅka[paśa]. (l. 5) [Vā]seṭhiputasa Ikhākunaṁ Siri-Chātamūlasa sun[hā]ya [mahārāja-] (l. 6) sa Mādha[ri]putasa¹ Ikhākunaṁ Siri-Virapurisadatasa bhayaya² ma-(l. 7)hārājasa Siri-E[huvu]la-]Chātamūlasa³ mātuya mahād[e]viya Bhaṭṭidevāya (l. 8).....[i]maṁ vihāro sava-jāta-niyuto⁴ achariy[ā]naṁ Bahusutiyānaṁ (l. 9) paṭiṭhā[pito]....i ra pu naṁ budhiṇa⁵....[saṁvachharaṭṭi]...[bitiyam] (l. 10) [gimha-pakhāṁ].....sughāya ti⁶

TRANSLATION.

Success! Adoration to the Lord, the Leader of the Law of the Three Worlds.—Mahādevī Bhaṭṭidevā(*who is*) the daughter-in-law of Mahārāja Vāseṭhiputa Siri-Chātamūla, of (*the house of*) the Ikhākus, etc. (see above, sub C 3); (*who is*) the wife of Mahārāja Mādhariputa Siri-Virapurisadata of the house of the Ikhākus; (*and who is*) the mother of Mahārāja Siri-Ehuvuḷa (?) Chātamūla, has erected.....this monastery provided with all essentials (?) for the Masters of the Bahusutīya sect.⁷

Detached Pillar inscription H.

TRANSCRIPT.

(l. 1) Sidham namo bhagavato samā-saṁ- (l. 2) budhasa mahārājasa Vāseṭhiputasa (l. 3) Ikhākunaṁ Siri-Ehuvuḷa-[Chāta]mūlasa sava 10[+*]1 (l. 4)....1 diva 7 mahārājasa Agihot-Āgidhema- Vājaveja⁸ (l. 5) Asamedha-yāvi(ji)sa [aneka-]hirāṇa-koṭi-go-satasahasā- (l. 6) hala-satasahasā-pad[ā]y[i]sa savathesu apatihata- (l. 7) saṅkapasa Vāseṭhiputasa Ikhākuna-[m] Siri-Ch[ā]tamūla[sa] (l. 8) nattiya mahārājasa Māthariputasa Siri-Virapurisa- (l. 9) datasa dhūtuya mahārājasa Vāseṭhiputasa Ikhākunaṁ (l. 10) Siri-Ehuvuḷa-Ch[ā]tamūla-[sa] bhaginiyā Vānavāsaka-mahārāja- (l. 11) mahādevi[ya] [Ko]da[ba]lisiriya imaṁ khaniyam vihāro cha (l. 12) achariyānaṁ Mahi[sā]sakānaṁ⁹ suparigahe chātudisaṁ (l. 13) sa[m]ghaṁ udisāya sava-sātānaṁ hita-sukh[ā]thaṁ thāpitaṁ achariye- (l. 14) na mahā-dhamma-kāthik[e]na Dhamma[gho]sa-¹⁰therena anuthitaṁ ti

TRANSLATION.

Success! Adoration to the Lord, the Supreme Buddha. In the 11th year of (*the reign of*) Mahārāja Vāseṭhiputa Siri-Ehuvuḷa-[Chāta]mūla of (*the house of*) the Ikhākus, the 1st (*fort-night of*...?), the 7th day. Mahādevī [Ko]da[ba]lisiri, (*who is*) the grand-daughter of Mahārāja Vāseṭhiputa, Siri-Chātamūla of (*the house of*) the Ikhākus, etc., (see above, C. 3); (*who is*) the daughter of Mahārāja Māthariputa Siri-Virapurisadata of (*the house of*) the Ikhākus; (*who is*) the sister of Mahārāja Vāseṭhiputa Siri-Ehuvuḷa-Chātamūla of (*the house of*) the Ikhākus; and (*who is*) the wife of the Mahārāja of Vānavāsaka has erected this pillar and monastery

¹ The second *akshara* may be either *ḍa* or *dha*.

² This mutilated word can hardly be anything but *bhayāya*.

³ The *aksharas* -huvuḷa are damaged owing to a crack, but *hu* is still legible.

⁴ Or should we read *sava-jīna-niyuto*? The *akshara* following *sava-* is certainly *jā*. In the other inscriptions we find *savaniyuto*.

⁵ [..... *Viraputtaṁ* *budhiṇa* . (proper name?) *raṇo* °—Ed.]

⁶ The date appears to have been followed by a benedictory formula such as *sava-loka-hita-sukhāya*.

⁷ Lines 9-10 seem to have contained a date, but are too much obliterated to allow of being deciphered.

⁸ Read *Agini-Āgidhoma-Vājaveja*.

⁹ The third syllable *sa* is still traceable.

¹⁰ The third *akshara* has become very faint. At first I felt inclined to read *Dhammayasa*, but the long horizontal base-stroke which is still clear rather suggests the letter *gha*.

G.



2 4 6 8 10 12 14

2 4 6 8 10 12 14

Handwritten text in a script, likely a form of Pāli or Sanskrit, arranged in two columns. The text is heavily obscured by noise and artifacts, making it largely illegible. The script appears to be a form of Pāli or Sanskrit, possibly from a Buddhist manuscript. The text is arranged in two columns, with the left column starting at line 2 and the right column starting at line 12. The text is written in a dark ink on a light background, with some characters appearing to be in a different script or dialect. The overall quality of the image is poor, with significant noise and artifacts throughout.

for the benefit of the Masters of the Mahi[sā]śaka sect, on behalf of the community of the Four Quarters, and for the sake of the welfare and happiness of all sentient beings. (*It has been* carried out by the Master, the great preacher of the Law, the *thera* Dhamma[gho]sa.

*Sculpture inscription J.*¹

TRANSCRIPT.

- (l. 1) Sidham namo bhagavato aga-pogalasa Budhasa Chhadakapavatic[e]na Paduma-
[vā]-niya gharaniya sagaya saputakānam Hagas[i]r[i]sa sagasa Nagatarasa cha sabhaja[sa]
(l. 2) saputikāna[m] cha deyadham[e] paṭo unisa cha mahācetiye paṭiḥ[ā]vito

TRANSLATION.

Success. Adoration to the Lord Buddha, the best of beings.

A meritorious gift (*consisting of*) a slab and a coping stone, has been dedicated at the Great Chaitya by Chhadakapavatica, Padumavāni his house-wife, together with their sons Hagasni and Nagatara with his wife and together with their daughters.

Fragmentary Sculpture inscription K.

TRANSCRIPT.

- (l. 1).....saputak[ā]na[m] Bha Dhamasa Padumasa cha [Bha]dasa Hughasa saput-
[i]k[ā]na[m] cha.....had[ā]ya Budh[ā]ya Padumāya M[isā]ya Chula-Budh-
[ā]ya N[ā]k[ā]ya cha saj[ā]m[ā]tuk[ā]na[m] san[ā]tuk[ā]na[m] sanat[i]na[m] cha sanādi-
m[i]ta-ba[m]dhavāna[m] cha deyadham[o] paṭa niba sapadaka.²....

TRANSLATION.

.....together with his³ sons Dhamā and Padumā, [Bha]da, Hughā and together with his daughters.....hadā, Budhā, Padumā, Mīsā, Chula-Budhā, and Nākā, together with his sons-in-law, together with his grandsons and granddaughters and together with his relatives, friends, and kinsmen, a meritorious gift (*consisting of*) a slab

Postscript.

Extract from a letter dated Oslo, 2nd October, 1928, from Prof. Sten Konow, Ph.D.

"In the first place I should like to draw your attention—perhaps unnecessarily—to the suffix *anaka* in *Viśākhaṇaka*, *Sāgaraṇaka*, formed from Viśākha, Sāgara, respectively. This same suffix is frequent in names from the Bombay Presidency; cf. Lüders, Nos. 985, 993, 1000, 1018, 1020, 1033 (Kaṇheri), 1000, 1001 (Kuṭā), 1088, 1091, 1097 (Kārli), 1109, 1111, (Bedsa), 1141 (Nāsik), 1171 (Junnar). It evidently belongs to a dialect with a Dravidian, perhaps Kanarese, substratum. The *h* for *s* also points to Kanarese. Moreover, some of the names seem to find their explanation in Kanarese. Thus *kanda* means 'child' in Kanarese, and *chali* 'cold.' *Chalikireṇmaṇaka* probably is *Chalikiraṇaka*='Moon.' It also strikes me that Kanarese *karrambu* means 'envy.' I have not access to a Telugu dictionary. But it seems to me that Kanarese is more likely. The other characteristics which can be gleaned from your quotations do not help us. They show that we have to do with a Standard Prakrit, related to Pali, which was, as you know, used over a large territory. The change of -p- to -v- is

¹ The transcript and translation of inscriptions J and K should be regarded as provisional.

² Perhaps *sapāduka-paṭa*. [Perhaps the reading is 'paṭāni be sapādūkāni', meaning two slabs with foot-prints.—Ed.]

³ His, her, or their, as the case may be.

general in most Prakrits and cannot be used for localizing the dialect. A similar language is also used in the Khāravela inscriptions. I would therefore be inclined to define the dialect of your inscriptions as follows: We are faced with a normalized semi-literary Prakrit, used by people whose home tongue was Dravidian, and probably Kanarese. If I am right, we should *a priori* be inclined to infer that the Ikkhākus had come to the Kistna country from the West. But all such conclusions are bound to be uncertain. *Khamda* is, as you say, probably = *Skanda*, and *Chānta* might be *Kshānta*, but might also have something to do with *Chāndaka*, the designation of some actors from Mathurā (Lüders, No. 85)."

Glossary.

- aga-pogala* (J, l. 1), Pali *agga-puggala* = Skt. *agrya-pudgala*, an epithet of Buddha.
- Agihot-Agiṭhoma-Vājaṭṭe-Āsamedha-yājisa* (passim), an epithet of Siri-Chāntamūla. Cf. *Aggiṭhoma-Vājaṭṭe-Āsamedha-yājī* in the Hirahadagalli copper-plate grant of the Pallava king Śivaskandavarman, *Ep. Ind.* Vol. I, pp. 2 f. Also, *dvir-Āsvamēdha-yājinaḥ* in the Śuṅga inscription from Ayōdhyā. *J.B.O.R.S.* Vol. X, pp. 202 f.
- a[chānta]* (F, l. 3), i.e., *achehanta* = Skt. *atyanta*.
- aṭṭhaṅga-maga-dhammachaka-pavataka* (F, l. 1), i.e., *aṭṭhaṅga-magga-dhammachakka-pavattaka* = Skt. *aṣṭāṅga-mārga-dharmachakra-pravartaka*, an epithet of Buddha.
- aṭṭhāra* (D, l. 2), "eighteenth."
- atichhūta*, i.e., *atichchhūta* (A 3, l. 8; A 4, l. 9, etc.), always followed by *anāgata-vaṭṭamānake* or *mānakānam*. Cf. Pali *atichchhāti* (Skt. *atī-richchhati*) which is only preserved in the expression *atichchhātīha bhante* "Please go on, Sir." The past participle *atichchhūta*, therefore, stands for the usual *atīta*.
- Aḍavi-Chāṭisiri* (B, 2, l. 5), a personal name. The second *akshara* is possibly *ḍa*.
- anuthūam* (H, l. 14). Cf. Pali *anuthūta* (=Skt. *anushūta*), past participle of *anuthūhāti*, meaning "carried out, effected."
- aneka-hiraṇya-koṭi-go-satasā[hasa]-hala-satasahasā-padāyī* (F, l. 1), i.e., *aneka-hiraṇya-koṭi-go-satasahasā-hala-satasahasā-ppadāyī*, epithet of Siri-Chāntamūla. Cf. *aneka-hiroga-koṭi-go-hala-satasahasā-ppadāyīno* in the Hirahadagalli grant, ll. 10-11, and *aneka-gō-hiraṇya-bhūmy-ādi-pradānaiḥ praviddha-dhājma-saichayasya* *mahārāja-Śrī-Skandavarmanṇaḥ* in the Pīkura grant of Śiṃhavarman, *Ep. Ind.* Vol. VIII, p. 161 ll. 5-6. Cf. also *ti-go-satasahasadēna* in Kārlē inscriptions, *Ep. Ind.* Vol. VII, p. 57, and *tri-go-satasahasradēna* in Nāsik inscriptions, *Ep. Ind.* Vol. VIII, p. 78.
- anūterāsika* (C 1, l. 12; C 2, l. 10), Pali *anūtesī*, *antevāsī* "a disciple."
- savathesu apatīhata-saṃkapa* = Skt. *sarvārthe . . . apratīhata-saṃkalpa*, epithet of Siri-Chāntamūla. Cf. *appatīhata-sāsaṇassa* in the Hirahadagalli grant, l. 10.
- Aparamahāvīnaseṭṭhiya* (C 1, l. 10; C 2, l. 8; E, l. 2), name of a Buddhist sect. See above, p. 10. The name presumably is identical with Pali *Aparaseṭṭhiya*, Skt. *Aparasāṭṭhiya*, a subdivision of the Theravāda. Cf. M. Walleiser, *Die Sekten des alten Buddhismus* p. 7; but cf. p. 21.
- ayaka* (F, l. 2), i.e., *ayyaka* = Skt. *āryaka*.
- ayikā* (F, l. 2), i.e., *ayyikā* = Skt. *āryikā*.
- ayira-haṅgha* (C 1, l. 11; C 2, l. 10) = Skt. *ārya-saṅgha*. Cf. *ayira, aīra* in Amarāvati inscriptions, Lüders, *List*, Nos. 1276 and 1280.
- ayū-vadhanike vejayike* (E, l. 1). Cf. *appaṇa kula-gottasa dham-āyū-bala-yaso-vadhanikā vija-ya-vejayike* "while he made (the gift) a means of the increase of the merits"

longevity, power and fame of (his) own family and race." (Bühler) in the Hira-
hadagalli grant of the Pallava king Śivaskandavarman, l. 9, *Ep. Ind.*, Vol. I,
p. 6; *amha-vejayike* [*dhām*]-*m-āyu-bala-vaddhamike* "for conferring on ourselves
victory (in war) and for increasing (our) merit, length of life, and power".
(Hultzsch) in the Mayidavōlu plates of Śivaskandavarman, *Ep. Ind.*, Vol. VI, p. 87;
amham āyu-bala-vaddhanīyam-kātūṇa "making (it) a means for increasing our
length of life and power." (Hultzsch) in the British Museum plate of Chārudēvi,
Ep. Ind., Vol. VIII, p. 146. The Sanskrit equivalent of the term is found
in the Chammak and Siwanī grants of Pravarasena II (*Gupta Inscriptions*,
pp. 238 and 246) and in the Uruvapalli grant (*Ind. Ant.*, Vol. V, p. 52). Cf.
also *chhatrapasa saputra-darasa ayu-bala-vardhis* in the Taxila plate of Patika (*Ep.*
Ind., Vol. IV, p. 56) and *J. R. A. S.* for 1924, p. 402.

ālindā (F, l. 3), perhaps Skt. *ālinda* m. "a terrace in front of the house-door," Pali
ālinda "a terrace or verandah outside a house." *Mahāvagga*, VI, 36, 4=
Vinaya Piṭakam (ed. Oldenberg) Vol. I, pp. 247 f.; *Chullavagga*, VI, 3, 5 and
14, 1=*Vin. Piṭ.*, Vol. II, pp. 153 and 169. The *ālinda* is not necessarily a
terrace or verandah outside a building, as is proved by *Mahāvamsa* XXXV,
3, *Tatheva Lohapāsāde Thūpārāmūposathavhaye kuchchhi-ājirāṇa kāresi kuchchhi*
ālindam eva cha "He made an inner courtyard and an inner verandah in the
Lohapāsāda." Cf. P. K. Acharya, *Dictionary of Hindu Architecture*, pp. 54 ff.,
and A. K. Coomaraswamy, *J.A.O.S.*, Vol. XLVIII, p. 252.

āchariya (C 1, ll. 10 and 11), written with short initial *a* in line 8 of inscription C 2
=Skt. *āchārya*, Pali *āchariya*, "a teacher."

Ananda (C. 1, l. 12; C 2, l. 10), i.e., *Ananda*, a personal name.

Ikkāku, i.e., *Ikkhāku*=Skt. *Ikshvāku*, Pali *Okkāka*, the legendary progenitor of the Solar
race.

Ikkhāku-rāja-pavara-risi-sata-pabhava-vamsa-sambhava (F, l. 1)=Skt. *Ikshvāku-rāja-pravara-rishi-*
sata-prabhava-vamsa-sambhava, an epithet of the Buddha.

udisāya (H, l. 13). Cf. Skt. *uddiśya*, Pali *uddissa* (absol. of *ud-ḍisati*) "to point out",
"on behalf of, on account of."

unisa (J, l. 2)=Skt. *uśhṇiṣa*, "a coping-stone." Frequently met with in Amarāvati
inscriptions. The word appears to designate not only the coping-stone which
forms the crowning member of the railing enclosing the *stūpa*, but also the
frieze running along the top of the sculptured facing of such a monument.
Cf. Acharya, *op. cit.*, pp. 99 f.

ubhaya-loka-hita-sukha-nivāṣathanāya (A 3, l. 8, etc., passim) and *ubhaya-loka-hita-sukh-ā-*
vahetkanāya (B 2, l. 5). Cf. Spence Hardy, *Eastern Monachism*, p. 229.

ubhayito (B 5, l. 6), i.e., *ubbhayita*=Skt. **ūrdhwayita* from *ubbha*=Skt. *ūrdhva*. Cf. Pischel,
Grammatik, § 300.

uvavimāṇi [*tan*] (F, l. 3)=Skt. *uparivarnikam*.

uvāsikā (F, l. 2)=Skt. *upāsikā*.

ovaraka (F, l. 3) "a cell"=Skt. **apavaraka*. Cf. Lüders, *List; Index an. opavarata*,
uyaraka, *uvavaraka*, *ovaraka*.

Kandamiri (A 2, l. 6, etc., passim), a personal name.

Karumbudhūz (F, l. 2), a personal name.

kavapa (A 3, l. 6; etc.)=Skt. *kṛpapa*, Pali *kappa*, "poor, miserable, wretched, a
beggar."

Kuṭabala (B 4, l. 3), name of a clan.

Kuṭaba-vihāra (F, l. 3), name of a monastery.

koṭhāgārika (F, l. 2)=Skt. *kōṣṭhāgārika*. "a treasurer, a superintendent of a royal store-house." Cf. *koṭhagala* in Sohgaure copper-plate inscription (Lüders, *List*, No. 937).

[Ko]ḍa[ba]ḷisiri (H, l. 11), a personal name.

khāṇiga (H, l. 12) "a pillar" (?). Cf. Pali *khāṇu*. Childers, *Pali Dictionary*, sub *Corrigenda*, p. 622, under *khāṇu*.

Khaṇḍa, i.e., *Khaṇḍa* (in personal names)=Skt. *Skanda*.

Khaṇḍa-chalikirāṇaka (B 4, l. 4), a personal name. Dr. Sten Konow suggests Kanarese *chalikiraṇaka*=moon, from Kanarese *chali*=cold.

Khaṇḍa-viśākha (B 2, l. 4)=Skt. *Skanda-viśākha*, a personal name.

Khaṇḍasāgara[m]ṇaka (A 3, l. 7, etc.) and *Khaṇḍasāgarāmṇaga* (E, l. 1)=Skt. *Skanda-sāgara*, a personal name.

khaṇḍha, i.e., *khambha* (passim), "a pillar," from Vedic *skambha*. Cf. Pischel, *Grammatik*, § 396. Also in *sela-khaṇḍha* (q.v.).

grihapati (F, l. 2)=Skt. *grihapati*.

charani (J, l. 1)=Skt. *grihṇī*.

chakra-lakṣaṇa-sukarmāra-sujātu-charaṇa (F, l. 1)=Skt. *chakra-lakṣaṇa*², an epithet of the Buddha.

Chāṇḍamukha (F, l. 3)=Skt. *Chandramukha*, a personal name.

Chāṇḍamukhana (F, l. 2); cf. Skt. *Chandramukha*, a personal name.

Chāṇḍamūla; see *Siri-Chāṇḍamūla*.

Chāṇḍisiri (A 3, l. 7, etc., passim) or *Chāṇḍisiriṇikā* (B 5, l. 5), a personal name.

chātudisa saṅgha (H, ll. 12-13)=Skt. *chāturdśaḥ saṅghaḥ*.

chātusala (E, l. 2), i.e., *chatussāla*, Skt. *chatuṣśāla*, Pali *chatussāla*, "a quadrangular building built round an inner courtyard, a cloister or quadrangle." Cf. *Mrichchha-katūkā* (ed. Stenzler) p. 46, l. 20; *viḥāraṃ sacatuṣśālam*; *Rājat.* III. 13; *Mahāvamsa* XV, 47 and 50; XXXV, 88; Nāsik Cave (No. 10) Inscription, L. 2, Ep. Ind., Vol. VIII, p. 78. Acharya, *op. cit.*, p. 193.

Chula-Chāṇḍamukha (F, l. 2)=Skt. *Kshudra-Chandramukha*, a personal name.

Chula-Chāṇḍisiriṇikā (B 4, l. 5), a personal name.

Chula-Buddhā (K)=Skt. *Kshudra-Buddhā*, a personal name.

Chula-Mūla (F, l. 2)=Skt. *Kshudra-Mūla*, a personal name.

chetiya-ghara (E, l. 1 and F, ll. 2 and 3)=Skt. *chaitya-griha*, "an apsidal temple or Chaitya-hall." The term seems to be employed synonymously with *sela-maṇḍava*. The word *chetiya-ghara* is frequently met with in inscriptions and applies equally to structural and rock-cut shrines. Cf. Lüders, *List, Index* and *Mahāvamsa* XXXI, 52.

chhaṭṭha (E, l. 2; F, l. 2), i.e., *chhaṭṭha* "sixth"=Skt. *shashṭha*.

chhaṭṭhi, i.e., *chhaṭṭhi*, in the personal name *Chhaṭṭhisiri* (C 4, l. 6).

Chhadakapavaticha (J, l. 1), a personal name (?) Cf. below under "Geographical Terms."

jām[ā]lukasa (E, l. 1)=Skt. *jāmātṛikasya*.

jua-kāma-kodha-bhaya-harisa-tarisa-moha-dosa-saḍ[ā]pita-Māra-bala-dapa-māna-pasamana-kara (F, l. 1)=Skt. *jūta-kāma-krōdha-bhaya-harsha-tarsha-mōha-dvēsha-śabdāpita-Māra-bala-darpa-praśamana-kara*, an epithet of the Buddha.

² [See footnote 1 on page 22, above.—Ed.]

jīta-rāga-dosa-moha-vipamuta (A 2, l. 2, etc.)=Skt. *jīta-rāga-dvēsha-mōha-vipramukta*, epithet of the Buddha. Rāga, dosa, moha, "lust, hatred, and delusion" are the three Aggis, Kūñchanas, or Akusala-mūlas symbolised in the centre of the "Wheel of Existence" by three animals: a dove or cock, a snake and a hog.

tarisa (E, l. 1)=Skt. *tarsha* "thirst."

taruṇa-divasakara-pabha (F, l. 1)=Skt. *ṛprabha*, an epithet of the Buddha.

talāka (F, l. 3)=Skt. *taḍāga*, "a tank or cistern."

tiṇi (F, l. 3), instr. *tiṃhi*, (F, l. 3) "three."

tera (F, l. 1) "thirteenth."

teloka-dhamma-dhurū-vaha (G, l. 1)=Skt. *trailōkya-dharma-dhurā vaha*, an epithet of the Buddha.

thambha in *sela-thambha* (C 2, l. 8)=Skt. *stambha*, Pali *thambha* "a pillar, a column, a stele."

thera, combined with personal names (F, ll. 3-4; H, l. 14)=Skt. *sthavira*, Pali *thera*, "a senior monk, an elder."

theriya (F, l. 1), derived from *thera*, adj. "belonging to *theras*," subst. "fraternity, community."

darisana (F, l. 1)=Skt. *darśana*, Pali *dassana*. Cf. Pischel, *Grammatik*, §135.

dasabala-mahābala (F, l. 1)=Skt. *daśabala-mahābala*, an epithet of the Buddha.

dināri-māsaka (B 5, l. 6); Skt. *dināra*, from Latin *denarius*, "an Indian coin struck in imitation of and called after the Roman Denarius" and Skt. *māsha(ka)*, "a certain weight and monetary value." *Manu* VIII, 135, 298, 392.

divasa (E, l. 2)=Skt. *divasa*. Elsewhere (C 2, l. 11) abbreviated as *diva*.

Dīgha-Majjhima-pa[n]cha-mātuka-desaka-vāchaka, and *Dīgha-Majjhima-nikāya-dhara* (C 1, ll. 11-12 and C 2, ll. 9-10); corrected reading. Cf. *Vinaya-dhara* and *Mahāvīnaya-dhara* in Amarāvati inscriptions. Burgess, *Amaravati Stupa*, p. 37, No. VIII, and p. 102, No. 25. The word *-dhara* in these compounds must have the same meaning as Arabic *ḥāfiẓ* "one who has the whole Qur'ān by heart."

duhutā (B, l. 3)=Skt. *duhitā* "a daughter", gen., instr. sing., *dhūtuya*, (F, l. 3; H, l. 9).

deva-manusa-sava-sata-hita-sukha-maga-desika (F, l. 1)=Skt. *dēva-manushya-sarva-sattva-hita-sukha-mārga-dēśika*, an epithet of the Buddha.

devarāja-sakata (A 2, l. 1, etc., passim)=Skt. *dēvarāja-sakṛita*, an epithet of the Buddha. *-desaka* (C 1, l. 11 "osaka"; C 2, l. 9 "desa") "a preacher".

Dhanaka (B 2, l. 4), a clan name.

Dhamma (K, l. 1)=Skt. *Dharma*, a personal name.

Dhamma[ghosa] (H, l. 14)=Skt. *Dharmaghōsha*, a personal name.

Dhammanandi (F, l. 4), i.e., *Dhammanandi*, a personal name.

dhātuvara-parigrahita (B 4, l. 3, etc., passim)=Skt. *dhātuvara-parigrihita* "absorbed by the best of elements (*dhātu*), i.e., by Nirvāṇa".¹

natu (K) in *sanatuka*, i.e., *sanattuka*=Skt. *sanaptrika*.

nattī (H, l. 8)=Skt. *naptrī*, "a grand-daughter".

¹ The above interpretation I owe to the courtesy of M. L. de la Vallée Poussin, who adds: "If the inscriptions belonged to the Mahāsāṃghikas, a conjectural explanation of *dhātuvara* as *Dharmadhātu* would not be excluded. The *Dharmadhātu* was sometimes a kind of Buddhist Brahman for the followers of the Mahāyāna."

[To me it does not appear to be impossible that the *Mahāśchetiya* has been specified in these inscriptions as 'protected by the corporeal remains of the Buddha' and that the genitive case is used here to discriminate this *stūpa* from others not similarly consecrated. Inscription E gives *dhātu-pari* only.—Ed.]

navakama and *navakamma* (C 1, l. 12; C 2, l. 11; F, l. 3)=Skt. *navakarma*, Pali *navakamma*, "a religious building dedicated by some lay-member to the Saṅgha". The procedure by which a superintendent of works (*navakammika*) is appointed by the chapter of *Bhikkhus* in order to supervise the construction of a *navakamma* is described in *Chullavagga* VI, 5=*Vinaya Piṭakam* (ed. Oldenberg), Vol. II, pp. 159 f. (*S. B. E.*, Vol. XX, pp. 189 ff.). "If the buildings were for the *Bhikkhus*, then a *Bhikkhu*, if for the *Bhikkhunīs*, then a *Bhikkhunī*, was appointed to superintend the works in order to ensure the buildings being in accordance with the rules of the Order as to size, form, and object of the various apartments". Cf. also *Sutta-vibhaṅga*, *Bhikkhunī-vibhaṅga* I, 1=*Vinaya Piṭakam*, Vol. IV, p. 211. The word *navakamma* frequently occurs in dedicatory inscriptions.

navakammika (F, l. 3) "a *Bhikkhu* or *Bhikkhunī* appointed by the Chapter as a superintendent of the building operations of a *navakamma*, (see preceding article). Cf. Lüders, *List*, Nos. 154, 773, 987 and 1250. A synonymous term is *kamm-ādhiṭṭhāyaka*, *Mahāvamsa*, XXX, 98.

Nākā (K)=Skt. *Nāgā*, a personal name.

Nāga (F, l. 4)=Skt. *Nāga*, a personal name.

Nāgātara (J, l. 1), a personal name.

Nāgamna (F, l. 3), a personal name.

Nīyabodhinikā (F, l. 3), a personal name.

nānā-dēsa-samanāgata (E, l. 2) "assembled (?) from various countries".

nīkapanika (E, l. 2), a word of uncertain meaning.

nīḥapita or *nīḥapita* (C 1, l. 12; C 2, l. 11), Pali *nīḥāpita*, past participle of *nīḥāpeti*, "to complete", *Mahāvamsa*, XXXI, 1, 2. Cf. Pali *nīḥita* completed, *thūpe anīḥite yeva*, *Mahāvamsa*, XXIX, 53; *thūpe anīḥitaṃ kammaṃ nīḥāpeti* *ibid.*, XXXII, 2.

nīrōḍha-sāmpatti-sāmpādake (A 3, l. 9, etc., passim)=Skt. *nīrōḍha-sāmpatti-sāmpādakē*, *pañcama* (E, l. 2) "fifth".

paṭa (J, l. 2 and K) "a slab." Frequently in Amarāvati inscriptions; see Lüders, *List*, *Index*. Also in compound *sapaṭa-samīhara* (F, l. 2), "with a floor of (stone) slabs".

paṭibhāga (A 2, ll. 6-7, etc., passim) in compound *samaṇa-baṃharaṇa*. The word corresponds with Skt. *pratibhāga*,¹ Pali *paṭibhāga*=counterpart, likeness. But the word wanted here is *apaṭibhāga*, Pali *appaṭibhāga* "unequalled, unparalleled, matchless."

paṭiḥapita (A 3, l. 9), i.e., *paṭiḥāpita*, Skt. *pratishṭhāpita* "erected, set up, dedicated"

Paduma (K)=Skt. *Padma*, a personal name.

Padumavāni (J, l. 1), a personal name.

Padumā (K)=Skt. *Padmā*, a personal name.

padhāna-sālā (F, l. 3)=Skt. *pradhāna-sālā*, "a hall for practising religious exercises", from Pali *padhāna* "exertion, energetic effort, striving, concentration of mind". Cf. *padhāna-maṃḍa* in Amarāvati inscriptions. Burgess, *Amarāvati Stūpa*, p. 105, No. 49; Lüders, *List*, No. 1230 and correction, p. 179.

parigaha (E, l. 2)=Skt. *parigraha*, Pali *pariggaha*, "grace, favour."

parigahita or *parigahita* in *dhātuvāra-parigahita* (q.v.) and *Vīrūpakhāpiti-Mahādhara-parigahita* (q.v.) The meaning of *parigahita* in these two compounds appears to be "absorbed by".

¹ [But Skt. *pratibhāga* means 'gift' or 'share' also.—Ed.]

² ["protected by"—Ed.]

parināmetuna[m] passim, *absolutivum* of *parināmeti*=Skt. *pariṇāmayati*, Pali *pariṇāmei* (caus. of *pariṇamati*) "to bend to, to change into, to turn to use for somebody, to apportion, to destine." *Mahādevi Bapisirīṇikā apāno mātaram Harimasirīṇikā parināmetuna* (C 2, l. 7) and *Mahādevi Chhaṭhisirī apāno mātaram Harimasirīṇikā parināmetuna* (C 4, l. 7). It is clear that *parināmetuna* is used here in the same sense as *purato katūnaṃ* in the Jaggayyapēṭa inscriptions: *apāno mātaram Nāgalinīm purato katūnaṃ* "having associated [with him] his mother Nāgalini" (Bühler). In the expression *apāno ubhaya-kulam parināmetuna* (B 2, l. 5; C 1, l. 8; C 5, l. 4) it is also used with the object in the accusative. Elsewhere we find *apāno ubhaya-kulasa atichhitam-anāgata-vaṭamānake* or *vaṭamānakānaṃ* in which the connection with the *absolutivum* *parināmetuna* is not clear. Cf. Buddhist Skt. *pariṇāmayati* (*Mahāvastu*, Vol. I, pp. 81 and 309).

pavajita (E, l. 1), i.e., *pavajita*=Skt. *pravrajita*, Pali *pabbajita*.

pas[ā]daka (E, l. 1)=Skt. *prasādaka*, Pali *pasādaka* "converting to the Buddhist faith".

pāsāda in *Bodhi-rukha-pāsāda* (F, l. 3) q.v.

pituchhā (A 2, l. 5, etc., passim)=Pali *pituchchhā*: "a father's sister, a paternal aunt". Cf. Pischel, *Grammatik*, § 148.

pituno (F, l. 2) gen. sing.=Skt. *pituh*.

puva-dāra (F, l. 3), i.e., *puva-dāra*=Skt. *pūrva-dāra* "the eastern gate or entrance". The word *dāra* is frequently met with in Amarāvati inscriptions. Cf. Lüders, *List*, *Index*, under *dāra*.

puva-diśā-bhāga (F, l. 2)=Skt. *pūrva-dśā-bhāga*.

Pūkiya, *Pukiya* (A 2, l. 6; C 3, l. 7; C 5, l. 2), *Pugiya* (E, l. 1), a clan name.

Bapisirīṇikā (C 2, l. 6), a personal name. Cf. Bapisirī in Lüders, *List*, No. 1213 (Amarāvati inscription) and names like Bappuka (*Ep. Ind.*, Vol. II, p. 282), Bappārya (*Gupta Inscr.*, p. 243), Bappasvāmin (*ibidem*, p. 105) and Bāppadōva (*ibidem*, p. 249), Bappikā (*Rājat.* VII, 1128).

Bahusutiya (G, l. 8)=Skt. *Bahusrutya*, Pali *Bahussutiya*, name of a Buddhist sect. It was a subdivision of the Gōkūlika sect which belonged to the Mahāsāṅghikas. Cf. M. Walleiser, *Die Sekten des alten Buddhismus*, pp. 6 and 21.

bālikā (B 4, l. 3; B 5, l. 3 *ex conjectura*; C 2, l. 6; C 4, l. 5).

Budhanīkā (F, l. 3), a personal name.

Budhanīkī[nā] (F, l. 2), a personal name.

Budhā (K), a personal name.

Budhinaka (F, l. 2), a personal name.

Budhi[vā]siya (F, l. 2), a personal name.

Bodhi (F, l. 2)=Skt. *Bodhi*, a personal name.

Bodhika (F, l. 2)=Skt. *Bodhika*, a personal name.

Bodhi-rukha-pāsāda (F, l. 3)=Skt. *Bodhi-riksha-prāsāda*, Pali *Bodhi-rukha-prāsāda*, "a shrine of the Bodhi-tree." G. Spence Hardy, *Eastern Monachism*, p. 212.

Bodhisammasa (F, l. 2)=Skt. *Bodhisammasa*, a personal name. Cf. Lüders, *List*, No. 1200.

Bodhisirī (F, l. 2)=Skt. *Bodhisirī*, a personal name.

Bhagini (A 3, l. 5, etc., passim, instr. sing. *bhaginiyā* (H, l. 10)=Skt. *bhaginī* "sister".

bhajanī-Anandena (C 1, l. 12) and *bhajanī-Anandena* (C 2, l. 10)=Skt. *bhājanī-Anandena* "by the Reverend Ānanda".

Bhāṭidevā (G, l. 7), a personal name.

bhatuno, gen. sing. (F, l. 2)=Skt. *bhātubh*.

Bhada (F, l. 2), i.e., *Bhadā*=Skt. *Bhadrā*, a personal name.

Bhadasiri (F, l. 3), i.e., *Bhaddasiri*=Skt. *Bhaddasī*, a personal name.

bharyā (A 2, l. 6, etc., passim) and *bharyā* (B 2, l. 4; B 4, l. 5)=Skt. *bhāryā*, Pali *bhāriyā*.

bhāgineya (F, l. 2)=Skt. *bhāginiya*, "a sister's son".

bhātano (F, l. 3) gen. sing.=Skt. *bhrātubh*; *bhātunam*, gen. plur.=Skt. *bhrātṛiṇām*.

bhātu-puta (F, l. 2)=Skt. *bhrātṛi-putra*, "a brother's son".

Majjhima-nikāya. see *Dīgha-Majjhima-nikāya*.

maṇḍava, *maṇḍava* (F, l. 3)=Skt. *maṇḍapa*.

Mahākāṁdasiri (C 5, l. 2), a personal name. Cf. *Kāṁdasiri*.

mahāgaṇi-rasabha-gaṇḍha-hathi (A 2, l. 2, etc., passim)=Skt. *mahāgaṇi-rṛishubha-gaṇḍha-hastin*, an epithet of the Buddha. For *mahāgaṇi* cf. *Mahāvamsa* XXIX, 30.

Mahā-Chandamukha (F, l. 2)=Skt. *Mahā-Chandramukha*, a personal name.

Mahāchetiya and *Mahāchetiya* (A 2, l. 3, etc., passim)=Skt. *Mahāchaitya*, "Great Chaitya," loc. sing. *Mahāchetiyamhi* (C 4, l. 2, ex conjectura).

mahātalarava (A 2, l. 6, etc., passim), a title of uncertain meaning, evidently denoting "a high dignitary or a feudal lord". See above, p. 6.

mahātalaravi (A 3, l. 7, etc., passim), "the wife of a *mahātalarava*".

mahādānāyaka (B 2, l. 4)=Skt. *mahādānāyaka* "a high, probably judicial, official". Cf. *J. R. A. S.*, 1924, p. 402.

mahādānapatini (A 3, l. 7, etc., passim)=Skt. **mahādānapatnī* "a mistress of munificence" an epithet of Chāṁtisiri. Cf. *mahādānapati* in Taxila plate inscription. *Ep. Ind.*, Vol. IX, p. 56.

mahādevī (B 5, l. 4; C 2, l. 6; G, l. 7; H, l. 11), a title borne by the consort of a ruling chief.

mahādhammakāthika (H, l. 14)=Skt. *mahādharma-kāthika* "a great preacher of the Law." Cf. Burgess, *Amaravati Stupa*, p. 94.

mahābhikkhu-saṅgha (E, l. 1), i.e., *mahābhikkhu-saṅgha*.

mahāmātukā (F, l. 2). Cf. Pali *mahāmātā* "a grandmother".

Mahā-Mūla (F, l. 2)=Skt. *Mahā-Mūla*, a personal name.

mahāvihāra (B 5, l. 5; F, l. 3).

mahāsenāpati (A 3, l. 7, etc., passim)=Skt. *mahāsēnāpati*, lit. "Commander-in-Chief" but here used as a title designating a feudal lord. According to the late Dr. Fleet it "denotes equal rank with Mahārāja and Mahāsāmanta." (*Gupta Inscriptions*, p. 15, n.). See above, p. 6.

mahāsenāputini (B 4, l. 5), Skt. **mahāsēnāpatnī* "the wife of a *mahāsenāpati*".

Mahī[sā]saka (G, l. 12), Skt. *Mahīśāsaka*, Pali *Mahimsāsaka*, name of a Buddhist sect. It was a subdivision of the Theravādins and appears to have flourished in the Āndhra country. Cf. M. Walleiser, *Die Sekten des alten Buddhismus*, pp. 7 and 22.

Māḍharīputa (A 2, l. 5, etc., passim) and *Māḍharīputa* (E, l. 1; F, l. 1; H, l. 8)=Skt. *Māḍharīputra*, metronymic of Siri-Virapurisadata.

mātā (A 3, l. 7, etc., passim) "mother", acc. sing. *mātaram* (C 2, l. 7; C 4, l. 7) instr. and gen. sing. *mātuya* (F, l. 2; G, l. 7).

mātuka, see *pañcha-mātuka*.

Misī (F, l. 3), i.e., *Missi*=Skt. *Misrī*, a personal name

- Mūla* (F, l. 3), a personal name.
- Mūlamnikā* (F, l. 3), a personal name.
- Mūlavāniya* (F, l. 2), a personal name.
- Rudradharabhaṭṭārikā* (B 5, l. 3)=Skt. *Rudradharabhaṭṭārikā*, a personal name of a queen, probably belonging to the ruling house of Ujjayinī. See above, p. 4.
- Revata* (F, l. 2), a personal name.
- Revatimnikā* (F, l. 2), a personal name.
- vaḍhāki* (F, l. 4)=Skt. *vardhaki*, Pali *vaḍḍhaki*, Hindi *barhai*, "a carpenter, builder, architect, mason." Cf. *vaḍhaki* in Karle inscription, Lüders, *List*, No. 1092 and *vaḍakin* in Sānchi inscription, *ibidem*, No. 495. In inscr. F, l. 4 the word occurs in the compound *sela-vaḍhāki*=Skt. *śaila-wardhaki*, "a stone-mason." Cf. Pali *uṭṭhaka-vaḍḍhaki* "a brick-mason," *Mahāvamsa* XXIX, 5, 30 and A. K. Coomaraswamy, *J. A. O. S.*, Vol. XLVIII, p. 272.
- vaṇija(ka)* (A 3, l. 6, etc., passim)=Buddhist Sanskrit *vanīyaka*, *vanīpaka* "a beggar, a mendicant." Examples: *Dēva na hy=ēsha Kunālō=ndhaku ēsha vanīpakah patnyā saha dēvasya yānāsālāyām=avasthitah*, *Divyāvadāna*, p. 414, l. 18; *Mahākāśyapō dīn-ānātha-kripana-vanīyak-ānukampī*, *Divy.*, p. 83, l. 19; *brāhmaṇaṇ vā śramaṇaṇ vā anyam v=āpi, vanīyakam*, *Mahāvastu*, Vol. I, p. 188, l. 14.
- vathava* (C 1, l. 11; F, l. 2), i.e., *vattavva*=Skt. *vāstavva* "residing at".
- vāchaka* (C 1, l. 11; C 2, l. 9, restored), "a preacher".
- Vāsīthiputa* (A 2, l. 3, etc., passim) and *Vāsethiputa* (G, l. 5; H, ll. 7 and 9), i.e., *Vāsīthiputta*=Skt. *Vāsīsthīputra*, metronymic of Siri-Chāntamūla, Kaṇḍasiri, Khamdachalikiremmaṇaka (?) (B 4, l. 4) and Siri-Ehuvala-Chāntamūla (H, l. 9).
- Vinhusiri* (C 5, l. 3)=Skt. *Vishṇuśrī*, a personal name. Cf. *Vinhukā* in Sānchi inscriptions, *Ep. Ind.*, Vol. II, p. 95.
- Vidhika* (F, l. 4), a personal name.
- Virūpakhapati-Mahāsena-parigahita* (A 2, l. 3, etc., passim)=Skt. *Virūpākshapati-Mahāsēna-parigrihīta*, an epithet of Siri-Chāntamūla. In the *Mulindapañhu*, pp. 6 ff., Mahāsēna figures as a *devaputta* who becomes incarnate in the sage Nāgasēna.
- viḥāra* (F, l. 2; G, l. 8; H, l. 11), "a monastery".
- Vīraṇna* (F, l. 3), a personal name.
- Vīra[m]nikā* (F, l. 3), a personal name.
- velāmi(ka)* (B 3, l. 7, etc., passim; once *vailāmika* A 4, l. 7) in compound *samaṇa-bamhaṇa*°. The word appears to be an adjective meaning, "belonging to Velāma." Buddha (*Jātaka*, Vol. I, p. 228; Cambridge translation, Vol. I, p. 101) refers to the time of Velāma when he (Buddha) "stirred up all India by giving the seven things of price, and in [his] largesse poured them forth as though [he] had made into one mighty stream the five great rivers." He then preached the *Velāmaka-Sutta* (*Velāmaka-Suttaṃ kathesi*) which is also mentioned in *Sumaṅgala-Vilāsini*, Vol. I, p. 234, l. 11. It would seem, that Velāma was a legendary personage renowned in Buddhist tradition for his munificence like Vessantara with whom his name is combined in *Vibhaṅgaṭṭha-kathā*, p. 414, l. 6. Mr. Helmer Smith has drawn my attention to a passage in *Āṅguttara-Nikāya*, Vol. IV, pp. 394-396 where the Buddha praises the liberality of a Brahmin Velāma with whom he identifies himself in a previous birth.
- vochhina*, i.e., *vochchhinna* (A 2, l. 7, etc., passim) in compound *samaṇa-bamhaṇa*°=Skt. *vyavachchhinna*, past participle of *vyavachchhinatti*, passive *vyavachchhidyaṭē*, Pali

- vochhijjate* "to be cut off". The word wanted here evidently is *avochhina*, Pali *abbochchhinna*, *abbhochchhinna* "not cut off, uninterrupted, continuous".
- samvachhara* (E, l. 2)=Skt. *saṃvatsara*, "a year". Elsewhere (A 3, l. 9, etc., passim) abbreviated as *saṃva*, or *saṃ* (E, l. 2).
- sata* (F, l. 3), i.e., *satta*,=Skt. *sapta*, "seven".
- satari-sataṃ* (B 5, l. 6), i.e., *sattari-sataṃ* "one hundred and seventy." Cf. Pischel, *Grammatik*, § 60.
- saṃthara* in *sapaṭa-saṃtharaṃ* (F, l. 2)=Skt. *saṃstara*, Pali *saṃthara*, *saṃthāra* "a layer, stratum, couch, flooring". Cf. *Mahāvamsa* XXX, 70.
- samaṇa-bamhaṇa-kavaṇa-vaṇija[ka]-dīn-ānugaha-velāmi[ka]-dāna-paṭibhāga-vochhina-dhāra-padāyini* (A 3, ll. 6-7, etc., passim)=Skt. *śramaṇa-brāhmaṇa-kṛpāṇa-vāṇiyaka-dīn-ānugriha-vailāmika-dān-āpratibhāg-āvyavachhinna-dhāra-pradāyini*, an epithet of Chāṃtisiri. Cf. above, under *kavaṇa*, *vaṇija(ka)*, *velāmi(ka)*, *paṭibhāga*, and *vochhina*.
- saṃma-saṃbuddha* (A 2, l. 1)=Skt. *samyak-saṃbuddha*, Pali *sammā-saṃbuddha* "perfectly enlightened, a universal Buddha".
- samuthapiyamāna* (B 5, l. 6)=Skt. *saṃutthāpyamāna*, present participle passive of *saṃutthāpayati*, Pali *saṃutthāpeti* "to found, originate".
- sarada-sasi-soma-darisana* (F, l. 1)=Skt. *śārada-śaśi-saumya-darśana*, an epithet of the Buddha.
- savaṃṇu*, gen. *savaṃṇuno* (A 2, l. 1, etc., passim)=Skt. *śarvaṇa*, Pali *sabbāṇṇu* "omniscient", an epithet of the Buddha.
- sava-niyuta* (E, l. 2; F, l. 2; cf. *sava-jāta(?)*-*niyuta* G, l. 8), i.e., *savva-niyutta*=Skt. *śarva-niyukta*.
- sava-loka-chita-mahita* (F, l. 1)=Skt. *śarva-lōka-chitta-mahita*, an epithet of the Buddha.
- sava-loka-hita-sukh-āvahathanāya* (C 1, l. 9; C 3, l. 12), cf. *ubhaya-loka-hita*.
- sava-sat-ānukampaka* (A 2, l. 1, etc., passim), i.e., *savva-satt-ānukampaka*=Skt. *śarva-sattv-ānukampaka*, an epithet of the Buddha.
- sava-sādhuvucchālā* (A 3, l. 7, etc., passim)=Skt. *śarva-sādhuvatsalā*, an epithet of Chāṃtisiri.
- [*sā*]dhu-vaga (F, l. 3), i.e., *sādhuvagga*=Skt. *sādhuvarga*.
- Siri-Ehuvala*-(*Ehuvala*)-*Chātāmūla* (G, l. 7, H, ll. 3 and 10), a personal name.
- Siri-Chātāmūla* (A 2, l. 5, etc., passim), a personal name. Sometimes *Chātāmūla*.
- Siri-Virapurisadatta* (A 2, l. 5, etc., passim) -*Vira*- (E, l. 2 and G, l. 6)=Skt. *Śrī-Vīrapurushadatta*, a personal name.
- suṃṇhā* (F, l. 3, G, l. 5)=Skt. *śuṇṣhā*, Pali *suṇṣā*, *suṇhā* "a daughter-in-law."
- supabuddha-bodhi* (B 5, l. 1)=Skt. *suprabuddha-bōdhi*, an epithet of the Buddha.
- suparigaha* (F, l. 1; H, l. 11)=Skt. *suparigraha*, "grace, acceptance".
- suparigahita* (C 1, l. 10; C 2, l. 8)=Skt. *suparigrihita*, Pali *supariggahita*, "well favoured, graced, i.e., accepted by."
- sela-khaṃbha* (B 4, l. 6; B 5, l. 4; C 2, l. 8; C 5, l. 5)=Skt. *śaila-skambha* "a stone pillar." Cf. above, under *khaṃbha*.
- sela-thaṃbha* (C 2, l. 8)=Skt. *śaila-stambha*, "a stone pillar." Cf. above, under *thaṃbha*.
- sela-maṃḍava* (E, l. 2) and *sela-maṃḍava* (F, l. 3)=Skt. *śaila-maṇḍapa*, "a stone shrine", *śela-vaḍhāki* (F, l. 4); see above, under *vaḍhāki*.
- sōdarā-bhagini* (A 2, l. 5, etc., passim) and once *sahodar[ā]-bhagini* (E, l. 2) "a sister born from the same womb"; gen. sing. *sodarāya bhaginiya* (C 2, l. 5).
- soṃma* (F, l. 1)=Skt. *saumya*, Pali *somma*,

Hagsiri (J, l. 1), a personal name. Cf. Lüders, *List*, No. 1284.

Haghamna (F, l. 2), from Skt. *saṅgha* (?), a personal name.

Haṅgha, i.e., *Haṅgha*, =Skt. *Saṅgha*, in personal names. Cf. Lüders, *List*, Nos. 1240, 1262, 1271, 1272, 1274, 1281.

Hammasirinikā (C 2, ll. 5 and 7; C 4, ll. 5 and 7) or *Hammasiri* (C 4, l. 5), a personal name.

harisa (F, l. 1) =Skt. *harsha*.

Hiraññaka, i.e., *Hiraññaka* (B 4, l. 4), a clan name.

hiraṇṇa-koṭi-go-satasahasā-hala-satasahasā-padāyi (A 2, l. 4, etc., passim); see *aneka-hiraṇṇa-koṭi*°.

Hugha (K, l. 1) =Skt. *Sukha* (?), a personal name.

hemanta-pakha (E, l. 2; F, l. 1) =Skt. *hēmanṭa-paksha*.

Geographical names.

Avaranta (F, l. 1), i.e., *Avaranta*, Skt. *Aparānta(ka)*, Pali *Aparanta(ka)*, a country of the Western coast of the Peninsula, corresponding to the Northern Konkan, the capital of which was *Sōpārā*, the ancient *Sūrpāraka*.¹ Aparanta is mentioned in Rock-Edict V of Aśoka in connection with the appointment of *dhamma-mahāmātas*, in Nāsik Cave III inscr. among the dominions of Gautamiputra Śātakarṇi (*Ep. Ind.*, Vol. VIII, p. 60) and in the Junāgaḍh rock-inscription of Rudradāman. It was converted by Yonaka-Dhammarakkhita, *Dīpav.* VIII, 7. *Mahāvamsa* XII, 4 and 34. Cf. also *Milinda*. p. 331, Lüders, *List*, Nos. 965, 1013 A[pa]rāntikā (?), 1123. Skt. *Aparāntaka*. Cf. *Raghu*. IV, 53.

¹ *Ujenikā* (B 5, l. 3, ex conjectura for “*Ujanikā*”), i.e., *Ujjenikā*, adj. from *Ujjeni*, Skt. *Ujjayinī*, Pali *Ujjeni*, Gr. Ὀζήνη (Ptolemy, VII, 1, 63), modern Ujjain, a famous town in Central India.

Kaṁṭakasela (F, l. 3, ex conjectura for “*Kaṁṭakasola*”), i.e., *Kaṁṭakasela*, Skt. *Kaṁṭa-kaśaila*, Gr. Κανταχοσσύλα ἐμπορίον (Ptolemy, VII, 1, 15) a town in Maisolia. See above, p. 8.

Kasmira (F, l. 1) Skt. *Kāsmīra*, Pali *Kasmira*, modern Kashmir, a country in the Western Himālaya. Converted by Majjhantika, *Dīpav.* VIII, *Mahāv.* XII.

Gaṁdhāra (F, l. 1), i.e., *Gandhāra*, Skt. Pali *Gandhāra*, the Trans-Indus country and the district of Taxila. Converted by Majjhantika, *Dīpav.* VIII, *Mahāv.* XII.

Govagāma (F, l. 2), Skt. *Gōpagrāma* (?). The ancient name of the town Goa on the West Coast is Govapurī, Skt. *Gōpakapurī*. (*Ep. Ind.*, Vol. II, p. 117. *Jour. Bombay Hist. Soc.*, Vol. I, pp. 220 f.), but here some other locality appears to be meant.

Chilāta (F, l. 1), Skt. *Kirāta*, Mahārāshṭrī *Chilāda*, *Chilāa*, Ardhamāgadhi *Chilāya*, Gr. Κιρράδαι (*Periplus*, § 62; Ptolemy, VII, 2, 2), Κιρραδία (Ptolemy, VII, 2, 16) and Τιλάδαι (Ptolemy, VII, 2, 15), an un-Aryan tribe frequently mentioned in Sanskrit literature. Cf. *Milinda*. pp. 327 and 331. (Read *Chilāta* instead of *Vilāta*).

China (F, l. 1, coupled with *Chilāta*), name of a country and its inhabitants.

Chula-Dhammagiri (F, l. 2), see *Dhammagiri*.

¹ Cf. Jarl Charpentier *J. R. A. S.*, 1927, pp. 111 sq. and *ibid.*, 1928, p. 410.

- Chhadakapavat[i]cha* (J, l. 1), perhaps an adjective from *Chhadakapavata*. Cf. [*Chhada*]-*kicha* "an inhabitant of Chhadaka" (?) Lüders, *List*, No. 1220 (Amarāvati).
- Tambapam̃ni-dīpa*, i.e., *Tambapam̃ni-dīpa* and adj. *Tam̃bapam̃naka* (F, l. 1), Skt. *Tāmaparṇa-dvīpa*, Gr. *Ταπροβάνη* (Ptolemy, VII, 4, 1), the Island of Ceylon.
- Tosali* (F, l. 1), a country and town on the coast of Kalinga, mentioned in the two separate Rock-Edicts of Dhauri and two copper-plate inscriptions from the Cuttack district (*Ep. Ind.*, Vols. IX, p. 286 and XV, p. 1); *Τωσάλη μητρόπολις* erroneously located by Ptolemy (VII, 2, 23) in Trans-Gangetic India. Perhaps identical with *Δωσάρα* (Ptolemy, VII, 1, 77) and *Δωσαρηγή* (*Periplus*, 47). Cf. above, p. 7.
- Damila* (F, l. 1, reading uncertain), Skt. *Draviḍa*, Pali *Damila*, the Tamil country and people on the coast of Coromandel.
- Deragiri* (F, l. 3), a hill (?), site of a *padhāna-sālā* founded by Bodhisiri.
- Dhammagiri* (*Mahā-* and *Chula-* in F, ll. 2 and 3), i.e., *Dhammagiri* Skt. *Dharmagiri*, a hill. The Chula-Dhammagiri was the site of a monastery, where Bodhisiri founded the *chetiya-ghara* or apsidal shrine mentioned in inscr. F. It appears, therefore, to be the ancient name of the hill now known as Naharāḷlabōḍu.
- Paṇṇagāma* (C 1, l. 11; C 2, l. 10), i.e., *Paṇṇagāma*, Skt. *Paṇnagrāma* (?), a village.
- Papilā* (F, l. 3), a locality.
- [*Pa*]lura (F, l. 1, first syllable restored), a town in Kalinga, identified with Dantapura (S. Lévi, *J. A.*, Vol. CCVI, 1925, pp. 46 ff.; *Ind. Ant.*, Vol. LV, pp. 94 ff.). Ptolemy mentions *Παλούρα πόλις ἐν Γαγγητικῷ κόλπῳ* (I, 5, 16) and *Πάλουρα πόλις* at the western-most mouth of the Ganges.
- Pupphagiri* (F, l. 3), i.e., *Pupphagiri*, Skt. *Pushpagiri* ("Flower Mountain"), a hill (?), site of a *sela-maṇḍava* or stone shrine founded by Bodhisiri.
- Puvaseḷa* (F, l. 3), i.e., *Puvaseḷa*, Skt. *Pūrvaśaila* ("Eastern Mountain"), a hill.
- Mahā-Dhammagiri* (F, l. 3), see *Dhammagiri*.
- Yava[na]* (F, l. 1), Skt. *Yavana*, Pali *Yona*, designation originally of the Greeks (Ionians), subsequently of other foreign nations. Converted by Mahārakkhita, *Dīpav.* VIII, 9, *Mahāv.* XII, 5 and 39-40. Cf. *Saka-Yavane* in *Milinda*. pp. 327 and 331.
- Vaṅga* (F, l. 3), i.e., *Vaṅga*, Skt. and Pali *Vaṅga*, modern Bengal.
- Vanavāsi* (F, l. 1) and *Vānavāsaka* (H, l. 10), Skt. and Pali *Vanavāsa*, Gr. *Βαναβάσι* (Ptolemy, VII, 1, 83), a country corresponding to North Kanara. The village of Banavāsi is situated in latitude 14° 33', longitude 75° 5' in the Shimoga district of the Mysore State. It lies close to the border of Mysore territory and North Kanara. Vanavāsa was converted to Buddhism by Rakkhita, *Mahāv.* XII, 4. Cf. also *Ep. Ind.*, Vol. III, p. 117. *Vikramāṇkadēvacharita* V, 23 (ed. Bühler), p. 34; *Mahāvamsa* XII, 31, XXIX, 42.
- Vijayapuri* (F, l. 2), a town (?) to the east of which the apsidal temple founded by Bodhisiri was situated. Cf. Lüders, *List*, No. 1285.
- Siriparvata* (F, l. 2), i.e., *Siriparvata*, Skt. *Śrīparvata*, a mountain, apparently the site of a *viḥāra* or monastery mentioned in connection with the apsidal temple founded by Bodhisiri. See above, p. 9.
- Sihāḷa* in *Sihāḷa-viḥāra* (F, l. 3), the Singhalese or Ceylonese Monastery, where Bodhisiri had founded a *Bodhi-rukkha-pāsāda* or "Shrine of the Bodhi-tree."
- Hirumūḥuva* (F, l. 3), a locality.

TWO ADDITIONAL INSCRIPTIONS FROM NAGARJUNIKONDA.

BY J. PH. VOGEL, PH.D.

After the above paper had been completed, Mr. Longhurst sent me estampages of two more inscriptions discovered by him in the course of his excavations at Nāgārjunikoṇḍa. Both are found incised on sculptures.

One of these inscriptions occurs on a 'footprint slab.' It consists of one line of writing and comprises twenty-three *aksharas*, the concluding letter being written below the line owing to want of space. The *aksharas* measure from $\frac{1}{2}$ to $1\frac{1}{4}$ inches in height. The lettering is distinct, except some of the vowel-marks. It will be observed that the inscription is crossed by a series of nine vertical lines which possibly have some connection with the footprint carved on the slab.

The inscription records the donation of a *patipadā*. It would follow that this word, corresponding to Sanskrit *pratipadā*, ought to indicate the object on which the inscription is engraved. The technical term, however, by which a footprint slab is indicated in the Amarāvātī inscriptions, is *paduka-paṭa* (i.e., *pāduka-patta*), or *pātuka*^o, *patuka* (i.e., *pāduka*).

The donor was Budhi (i.e., Buddhi), the sister of Moda, the Saka. If this interpretation is correct, the mention of a Saka or Scythian is a point of special interest. In this connection it should be noted that among the sculptures excavated by Mr. Longhurst at Nāgārjunikoṇḍa there are two showing a warrior in Scythian dress.

In the word *bakiniya* corresponding to Sanskrit *bhaginyāḥ* we note a disaspiration of the initial consonant and a hardening of the *media ga* into *ka*.

TRANSCRIPT.

Sid[dham] Sakasa Modasa bak[i]n[i]ya Budh[i]ya pat[i]padā deyadhama

TRANSLATION.

Success ! A *patipadā*, the pious gift of Budhi, the sister of Moda, the Scythian.

The second inscription occurs on a carved stone slab. It consists of only three *aksharas* which I read :

Dhamasa

meaning "Of Dhama". Whether this is the name of the donor or the mason, it is impossible to decide.

No. 2.—NALANDA STONE INSCRIPTION OF THE REIGN OF YASOVARMADEVA.

BY HIRANANDA SASTRI.

The inscription which forms the subject of this paper was excavated at Nālandā, the well-known ancient site of Magadha, by Mr. J. A. Page in the official year 1925-26.¹ It was found buried in the debris of the southern verandah of the old *vihāra*—now called Monastery I—which has yielded not only a large number of bronze or copper images of various kinds and the very valuable copper-plate inscription of Dēvapālādēva that has been published above,² but also the earliest remains so far discovered at Nālandā.

This interesting document is engraved on the top bed of a stone capital-bracket and covers a space of $17\frac{1}{2}$ inches by 11 inches. It consists of twenty-one lines of writing and, excepting

¹ See *A. S. R.*, 1925-26, pp. 131 & 158.

² Vol. XVII, plate between pp. 320 and 321.

for a crack at the middle, is fairly well-preserved. The execution is neat and calligraphic. The record is a *praśasti* drawn in florid **Sanskrit** and, but for the initial symbol and the words *apī cha* coming between the sixth and the seventh stanzas, is entirely in verse. The **characters**, in which it is written, belong to the **northern class of alphabets** and present a very marked development in contrast with those of the contemporary and even somewhat later inscriptions which have been found in Northern and Eastern India. They largely resemble the characters of the Aphaṣṭ stone inscription of Ādityasēna¹ and would, thereby, indicate that the development, we notice in them, must have taken place not later than the first half of the sixth century of the Christian era, i.e., the time to which this inscription belongs. Till now, the Gayā inscription of A.D. 588-89 was considered to be the earliest inscription to illustrate such forms. But the epigraph under publication is decidedly anterior to that record and, therefore, becomes the earliest known inscription to represent that development. The alphabet to which these characters belong may well be called acute-angled (Bühler)² or *Siddhamātrikā* (Berūnī)³ in preference to the term 'nail-headed' or '*kuṭīla*'. Dēvanāgarī is an outgrowth of this *lipi*. The present record uses the bipartite form of *ya* throughout, as does the Bōdh-Gayā inscription of Mahānāman.⁴ Nālandā is not far off from Bōdh-Gayā. This epigraph, therefore, will not countenance the supposition that the use of the bipartite *ya* in the Mahānāman inscription was "premature." The tripartite form of *ya* is found even in the Udaypur inscription of Aparājita,⁵ which belongs to the *Samvat* year 718 (=A.D. 661). It is to be met with not only in the inscriptional records named above, but also in the Horiuzi palm-leaf manuscripts of Japan which are believed to have existed in the second half of the 6th century (A.D.). To regard an inscription as late or early merely on the ground that it uses the bipartite or the tripartite form of *ya* would not, consequently, be quite accurate. The alphabet used in this inscription is, to a large extent, identical with the modern Dēvanāgarī or Nāgarī. The chief points of difference which it presents are these: The *ā-mātrā* is generally indicated by a sort of small wedge attached to the right of the top line, whereas in Nāgarī it is expressed by a full perpendicular stroke. In the case of *ṇā*, however, a somewhat different mode is adopted by slightly bending the right end and extending it upwards beyond the top towards the right side. The *ū-mātrā* is slightly different in shape, as, e.g., in *bhūrī*^o, l. 2. The *ē-mātrā* is marked in two different ways, sometimes in an elongated form of the Nāgarī symbol with a bend at about the middle, as in *dēhinām*, l. 1, and sometimes by a short curve appended to the left of the top line of the *akshara* to which it belongs, as in *°ārthinē*, l. 1, or in *karēṇa*, l. 21. Similarly, the *ai-mātrā* is expressed in two ways. In *°ś=ch=aisha*, occurring in the penultimate line, it is practically similar to the Nāgarī symbol, whereas in the majority of cases it is expressed by the hook-like mark attached to the left of the top line and the slanting *ē-mātrā*, as, e.g., in *°uchchaiḥ*, l. 21. The *ō-mātrā* is shown by the symbols of the *ā* and the *ē-mātrās* combined, see, for instance, *°mōkshāya* and *yō* in l. 1. The *au-mātrā* is also different, e.g., see *°gaura*^o in l. 6, or *°Sauddhōdanēr* in l. 9.

As to the initial vowels, only the *ā* and the *i* retain their comparatively earlier forms. The former keeps the hook attached to its leg as in *ādēsāt*^o, l. 12, and the latter, the two small circles placed above the reversed crescent, as in *īy* in l. 20.

In the case of consonants, the omission of the top line of the *sa*, the *ma* and the *ya* symbols is noteworthy. So, also, are the forms of the letters *bha*, *ha*, *gha* and *ja*. The symbol for *dha* is also dissimilar and still preserves the old form, as does the letter *tha*. The form of *r* in conjunction with a following consonant is also antique and noteworthy; e.g., see *sEndrair-yaḥ* in l. 1 or *°padārtha*^o in l. 2.

¹ C. I. I., Vol. III, No. 42, plate XXVIII.

² Indian Palaeography (Ind. Ant., Vol. XXXIII), p. 49.

³ Ibid. ⁴ C. I. I., Vol. III, plate XLI A.

⁵ Ep. Ind., Vol. IV, plate facing p. 30.

In respect of **orthography**, the points which call for remark are (1) the use throughout of *v* for *b*, e.g., in *vādhī*, ll. 15 and 17, or in *Vālāditya*, l. 19, and (2) the use of the *ṇ*-like symbol for the conjunct *ñ*, as in *sarvēśhāñ=janma*¹, l. 17.

The inscription contains two words of special lexical interest. One is *śāstā* which occurs in v. 14 and seems to be used in the sense of sword personified or command.¹ The other is *Tikina* which comes in the third stanza and must be a foreign title, as is shown below.

The inscription, as I have stated above, is a *prasasti* and its **object** is to record that **Mālāda, the son of the minister (mantrin) of Yaśovarmmadēva**, made certain gifts, specified herein, to the temple which **king Bālāditya** had erected at **Nālandā** in honour of the 'Son of Śuddhōdana', i.e., the Buddha. It consists of fifteen beautiful stanzas written in three different metres, namely, Śārdḍulavikrīḍitam, Vasantatilakā and Sragdharā and is a **Buddhist record**. Commencing with an invocation of the Buddha, it extols the great king Yaśovarmmadēva as the *Lōkapāla* i.e., guardian of the world, who had risen like the sun after dispelling the darkness in the form of the enemies and after placing his foot on the heads of all the kings though, unfortunately, it does not mention the dynasty to which he belonged or the country over which he ruled. It, then, introduces the donor Mālāda and describes him as the wise, magnanimous, benevolent and victorious son of Yaśovarmmadēva's minister, whom it calls the *Mārgapati* as well as *Udichīpati* and *pradīta-Tikina*, though it does not give his name or any other particulars about him. Mālāda is mentioned here as the brother of **Nirmmalā** (v. 11), son (*nandana*) of **Bandhumati** and scion of a noble family, whose name is not stated. Giving a vivid description of the magnificent temple which king Bālāditya had built at Nālandā like a column of victory constructed after conquering the world (vv. 4-10), the inscription specifies the benefactions which the donor made for that sanctuary, as well as, for the *bhikshus* or Buddhist monks. The gifts consisted of *ghee*, curds, a brilliant lamp, pure water mixed with fourfold fragrant objects (*chatur-jātaka*)² and refreshing like nectar, and a permanent endowment (*akshaya-nivṛ*), the nature of which has not been made quite clear. We are further informed that Mālāda distributed delicious food and scented water to the *bhikshus* and, purchasing a *lajana* and other things from the 'revered *Saṅgha*' gave them back to the monks, herein called *Śākyāmajas* (=the (*spiritual*) sons of the Buddha), excepting a *chīvarikā* (monk's robe) and *śradhā*³ up to and beyond *Narḍdarikā*. The afore-mentioned gifts Mālāda brought himself out of his great devotion for the Buddha when he was 'awakened' or enlightened by the illustrious monk **Pūrṇpēndrasēna** and gave them to the monks for the welfare of his parents as well as of other relations. At the close of the inscription we are told that the *kīrti* should be respected not only because of the fear of committing the five sins (*pañch-ānantarya*), which accrue from the infringement of such pious deeds, but, also, because of the fear of the sword¹ of king Bālāditya, the subduer of the enemy.

¹ See *Amarakōśa*, *Śabdakalpadrūma* and also Monier Williams' *Sanskrit-English Dictionary* under *Śāstri*. Or, does this word refer to an image of the Buddha (*Śāstā*) which might have been set up by Bālāditya in the temple he had built at Nālandā (see v. 6 of the text) ?

² The four fragrant articles are : (1) *Tvak*, i.e., *Bamboo māṇḍa*, (2) *Ēlā*, i.e., *Cardamom*, (3) *Patraka*, i.e., *Laurus Cassia* and (4) *Nāgakēśara*, or *Mesua Rozburghii*. Cf. *Rājanirghaṇṭa* and *Bhāvaprakāśa* quoted in the *Śabdakalpadrūma* :—

Tvag-ēlā-patrakais=tulyais=tri-sugandhi tri-jātakam |

Nāgakēśara-samyuktam chātūr-jātakam=uchyatē ||

³ The exact significance of this term is not clear. Possibly it meant some place for himself, if not his own country.

The last stanza tells us that the *praśasti* was composed by Śīlachandra and the celebrated *Karaṇika Svāmidatta* under the inviolable command of the *Saṅgha*.

The inscription is **not dated** but supplies sufficient data to fix the time to which it belongs. It was written when Bālāditya was ruling and when king Yaśōvarmmadēva was holding the reins of sovereignty. That the Bālāditya of this record must be identified with the homonymous chief whom Hiuen Tsiang eulogises as the subduer of Mihirakula and the founder of the grand temple at Nālandā need not be dilated upon. The inscription itself mentions him as the builder of a magnificent sanctuary at Nālandā. That it is silent about his subjugation of the well-known Hūṇa king of Sākala (the modern Siālkoṭ in the Panjāb) is either due to his having had very little to do in the matter, as has already been suggested by Vincent Smith,¹ or, perhaps, to the fact that this inscription came into existence before that event.² Bālāditya flourished *cir.* 530 after Christ. Accordingly, Yaśōvarmmadēva, his suzerain, must have ruled about the same age. So the question arises : Who was that suzerain ? He cannot be the homonymous ruler of Kanauj,³ who was routed by Muktāpīḍa Lalitāditya of Kashmir and is better known to history as the patron of Bhavabhūti, the eminent playwright, because he came a couple of centuries after this period. The Chandēl chief of the same name is also out of the question, for he belongs to a still later epoch, *i.e.*, the 10th century of the Christian era. I know of no other ruler of this name who could be identified with the overlord mentioned in this inscription. But a powerful ruler of the name of Yaśōdharma is known to have flourished at the time when Bālāditya reigned, *i.e.*, the period to which this document is assignable. According to the Mandasōr stone inscriptions,⁴ he was ruling in the Mālava year 589 (= A.D. 533-34), and was a mighty conqueror who governed the whole of Northern India from the Brahmaputra to the Western Ocean and erected two columns of victory with inscriptions commemorating his triumph over the foreign invaders. In view of the facts stated in all these records I am of the opinion that the Yaśōvarmmadēva of the Nālandā and the Yaśōdharma of the Mandasōr inscriptions are identical and that the late Dr. Fleet was perfectly right when he thought that the name of Yaśōdharma should be corrected into Yaśōvarma.⁵ It is true that names ending in *dharma* are not unknown, but the appellation as given in the document under publication looks more reasonable and more appropriate than the one which was read in the other epigraphs. Accordingly, I would suggest that we should call the sovereign ruler who was chiefly responsible for the breakdown of the power of the Hūṇas in India early in the 6th century of the Christian era by the name of Yaśōvarmmadēva as given in the present record. From the way this inscription introduces him and Bālāditya it is evident that he was the overlord of the latter. The suzerainty of Yaśōdharma is proven by the above-mentioned inscriptions. Bālāditya, in any case, could not have had two different overlords living side by side and having practically identical names.⁶ The chief interest of this inscription, therefore, lies in its enabling us to determine

¹ *Early History of India*, 4th edn., p. 386.

² It is not impossible, however, that Bālāditya fought Mihirakula—though under the supreme command of Yaśōvarmmadēva—and got the credit for ousting him (*i.e.*, Mihirakula).

³ The guess made in *A. S. R.* 1925-26, p. 131 was wrong.

⁴ *C. I. I.*, Vol. III, Nos. 34 & 35.

⁵ *Ibid.*, foot-note 2 on page 145.

⁶ *Janēndra* in the Mandasōr inscription (l. 4) does not necessarily mean a tribal ruler as Fleet seems to have imagined. The word should be taken as a synonym of *narēndra* in the general sense, *i.e.*, the king of 'men.' Besides, his mention before Vishṇuvardhana clearly shows his suzerainty. Prof. Dr. Vogel has kindly drawn my attention to the Yaśōvarmapura of the Ghōṣarāwā Buddhist inscription (*Ind. Ant.* Vol. XVII, pp. 307 ff.) which might have been designated after this monarch. The whereabouts of this place are not known. Sir Alexander Cunningham took it to be the town of Bihār which is not far off from Nālandā.

the real name of the subduer of the Hūṇas in Northern India, as stated above, though, unfortunately, it does not add anything to our knowledge of his ancestry or of his successors, whoever they were. That it lends an additional support to his claim for fame and that it proves for certain that what is stated about him in the above-mentioned epigraphs is not a mere 'oriental hyperbole' but rests on facts need not be emphasized.¹

Now comes the difficult problem of identifying the minister or *mantrin* who is spoken of as *Mārgapati*, *Udichīpati* and *pratīta-Tikīna* in this inscription. But for the reticence of the composers of the *prāśasti* on the nationality and other particulars including the name of this personage, one could have known something definite about him. *Mārgapati* literally means the guardian of road or roads, but from the similar expressions occurring in the chronicles of Kashmir one could take it to mean the guardian of the passes or the frontier. The *Mārgēśas* figure very prominently in the narratives of the later chronicles of the 'Happy Valley' as Sir Aurel Stein² has already pointed out. They were also known by other names like *Mārgapas*, *Adhvapas*, *Adhvēśas*, etc., and were generally referred to in the plural and in connection with some particular routes or passes across the mountains, like the *Muliks* of the Muhammadan times. Besides, they were the feudal chiefs who held hereditary charge of specific passes and were bound to furnish garrisons for the frontier posts on these passes in return for the revenue of certain lands assigned to them. In the inscription under notice, on the other hand, only one such 'guardian' is mentioned. He is spoken of in the singular number and is called the 'Lord of the North' and minister of Yaśovarmmadēva, the protector of the world. Apparently, he was the Chief of such Guardians of Passes whose official status must have been higher than that of the *Drāṅgēśas* or *Mārgēśas* of the Kashmir chronicles. What the *udichī* or north of this record connotes cannot be stated definitely but, possibly, it may not be wrong to take it in the sense of the North-West Frontier of India. This *Udichīpati* or the Lord of the North was, it would seem, the Chief of the Guardians of Passes in that region. This personage is further described as *pratīta-Tikīna* and the meaning of this epithet is to be determined. That *pratīta* (*prati* — *ita*) is a Sanskrit word signifying 'distinguished' or 'well-known' requires no proof. *Tikīna* is not a Sanskrit word at all. Dr. Sten Konow very kindly tells me that it "is evidently Turki *tigin*, *tegin*, *tāgin*. It means 'a prince of the blood', and is especially used about the son or the brother of the *Khān*. The Chinese render it as *t'o-k'in*. It was one of the words first recognised by Thomsen in the Orkhon Inscriptions" and we "find several instances of its use in Chavannes, *Documents sur les Tou-kiue (Tatars) Occidentaux*". The authors of the *prāśasti*, it would appear, were not aware of other particulars about this 'stranger' and therefore mentioned him by his rank or office only. The name of his son, the actual donor, was known and could not have been omitted. The inscription gives it as *Mālāda* which is also not Sanskrit—though a forced Sanskritic derivation may not be impossible.³ The other details given about the donor are that he was a scion of a stainless family and the delight, i.e., son, of Bandhumatī and brother of Nirmmalā. Bandhumatī and Nirmmalā might have been the proper names of the two ladies, his mother and his sister, or their epithets only. The former is known to be the name of several women. Both are undoubtedly Sanskritic and could have been applied to ladies of foreign descent also. *Mālāda* was, as is evidenced by this inscription, a devout Buddhist and might have been a proselyte. The offerings of a lamp, *ghee*, scented water, etc., which he brought to Nālandā out of his *bhakti* or devotion to 'the great son of Śuddhōdana', i.e., the Buddha, are like those which the Buddhists from Tibet and other Central

¹ Cf. J. J. Modi, *J. B. B. R. A. S.*, Vol. XXIV (1914-17), p. 595.

² Notes on the *Rājatarāṅgini*, Vol. I, p. 214; Vol. II, pp. 291 & 392.

³ However, it reminds me of *Malāda* of the *Mahābhārata* (Sabhā° XXXI, 9) and of the *Kāvyamīmāṃsā* (Gaek. Or. Series No. I, p. 93).

Asian countries are seen bringing to the images of the Buddha at Kasiā in the Gōrakhpur district or at Bōdh-Gayā and other sacred places even now.

The remaining persons spoken of in the *praśasti* are the monk **Pūrṇṇēndrasēna** and the two poets who composed it. Whether the former belonged to Nālandā itself or to some other locality is not definitely stated in the record but it does not look improbable that he was one of the great teachers of Nālandā itself. Of the two authors of the composition **Svāmidatta** is described as a *prathita-karaṇika*, i.e., a celebrated officer in charge of documents. No particulars are given about the joint author, namely, **Śilachandra**.

As to the identity of **Nālandā** no remarks are needed, for it is too well-known to require any. A few points about this locality, however, seem to be worth mentioning here. The first is its designation which is certainly Nālandā (ending in long vowel, i.e., ā) and not Nālandā (ending in short vowel, i.e., a) as is sometimes erroneously supposed to be.¹ The name ending in the long vowel not only occurs in this and other inscriptions but in literature also, both Buddhist as well as Jaina. I am not aware if the locality figures in Brahmanical literature at all. It goes back to the time of Mahāvīra, the twenty-fourth Jina, and of Gautama Buddha, i.e., at least five centuries before the birth of Christ. The Jaina accounts² would show that it was a very prosperous and sacred *bāhrikā* or suburb of Rājagriha where Mahāvīra spent fourteen *chāturmāsya*s. Early Buddhist literature³ also testifies to its pristine glory: But it looks curious that in neither of them it figures as a university or centre of learning. Possibly it grew as such later, i.e., about the period when the great pilgrim of China, namely, Hiuen Tsiang, came to study there. The description of the *chaityas* or *vihāras*, the *prāsādas* or *dēvālayas*, etc., as given in this interesting document, however, would show that the pilgrim's description of its splendour must have been based on facts.

¹ The name ending in the short vowel, i.e., a, is given in *C. I. I.*, Vol. III, p. 210, *Buddhist Records of the Western World*, pp. 167, etc., and *The Life of Nāgārjuna from Tibetan and Chinese Sources* by M. Walleiser (Reprint from *Asia Major*, Hirth Anniversary Volume, Leipzig, pp. 15, etc.).

² (1) See *Sūtrakṛtiāṅga*, 7th Lecture (Chapter on Nālandā), of the Second Book.

Teṇaṁ kileṇaṁ teṇaṁ samaṇaṁ Rāyagihe nāmaṁ nayare hotthā riddhipphita samiddhe vaṇṇaso jāva paḍirūve tassaṇaṁ Rāyagihassa nayaṇassa bahiyā uttara-puratthime diṭṭhā eṭṭhaṇaṁ Nālandānāmaṁ bahiriya hotthā apogabhavaṇassa yasannivittā jāva paḍirūvā || 1 ||

(2) *Kalpasūtra* of Bhadrabāhu (ed. H. Jacobi), Leipzig, 1879, p. 64, para. 122.

Rāyagiham nagaram Nālandam cha bāhriyam.

(3) The *Pārvadēśachaitya-paripāṭi* which was composed by Paṇḍita Harṇasasōma in V. S. 1565 and has lately been published in the *Yasōvijaya-Jainagranthamālā*, Bhāvanagara (Kathiawad) says :—

Nālandai pādai chanda-chaumāsa suṇijai
Hauḍa lokaprasiddha te Baḍagāma kahijai
Solaprasādatihām achchhai Jinabimbamijai.

(4) The *Sammēlakikharattīthamālā* is more explicit. It records :—

Bāhiri Nālando pāḍo
Suṇayo tassa punyapavāḍo
Vira chaudarahā chaumāsa
Hauḍa Baḍagāmma nivāsa
Bimhudehare ekaso pratimā navilahi i Bodhani gaṇimā.

* References to Buddhist works are several and I have dealt with them in the paper which I read before the All-India Oriental Conference at Lahore in 1928. (*Proceedings, Fifth Indian Oriental Conference*, Vol. I, pp. 386 ff.). Here I may allude to *Majjhima-Nikāya*, Vol. I, p. 377.

"Tāṁ kiṁ maññesi gaḥapati : Ayam Nālandā iddhā eh'eva phitā cha bahujanā ākinna-manussa ti."
"Evam bhanto, ayam Nālandā iddhā eh'eva phitā cha bahujanā ākinna-manussa ti."

ANANDA SASTRI.

As to the name *Narddarikā* occurring in this record, it might have been an ancient streamlet or a lake at Nālandā.

TEXT.¹

- Line 1 संभारुखिव(व)सनात्कृतमतिर्मोक्षाय यो देहिना कारुण्यात्सभं
शरोरमपि यो दत्वा तुतोषार्थिने [१*] सेन्द्रैर्यः स्वशिरःकिरोटमकरो-
वृष्टाङ्गि-
- „ 2 पद्मः सुरेस्तस्मै सर्वपदार्थतत्त्वविदुषे वु(वु)ञ्जाय नित्यं नमः ॥ [१^३ ॥*]
सर्वेषां मूर्ध्नि दत्वा पदमवनिभृतामुद्गतो भूरिधामा निस्त्रिंशंशुप्रतानप्रद-
लितनिखिलारातिघो-
- „ 3 सन्धकारः [१*] ख्यातो यो लोकपालः सकलवसुमतोपद्भिनीवो(वो)ध-
हेतुः श्रीमान्मास्त्रानिवोच्चैस्तपति दिशिदिशि श्रीयशोवर्मदेवः ॥ [२^४ ॥*]
तस्यासी परमप्रसादम-
- „ 4 हितः श्रीमान्तुदाराशयः पुत्रो मार्गपतेः प्रतोतति किनोदोचीपतेर्मन्त्रिणः [१*]
मालादो भुवि चन्दनोरिदमनो यो व(व)न्मुमत्यास्सुधीर्दीनाशपरिपूरणे-
- „ 5 कचतुरो धीरो विशुद्धान्वयः ॥ [३^३ ॥*] यासावूर्जितघैरिभूप्रविगलहानास्व(स्व)-
पानोन्नमन्माद्यद्भृङ्गकरोन्द्रकुम्भदलनप्राप्तश्रियाम्भूभुक्ताम् । नालन्दा ह-
- „ 6 सतीव सर्व्वनगरीः शुभ्राभ्रगौरस्फुरच्चैत्यांशुप्रकस्यैस्सदागमकलाविख्यातविद्व-
ज्जना ॥ [४^३ ॥*] यस्यामस्व(स्व)धरावलेहिशिखरश्रेणी वि-
- „ 7 हारावली मालेवोर्ध्वविराजिनो विरचिता धात्रा मनोज्ञा भुवः [१*]
जान्मारुतमयस्त्रजालखचितप्रासाददेवालयः सद्विद्याधरमङ्ग-
- „ 8 रम्यवसतिर्धत्ते सुमेरोः श्रियम् ॥ [५^३ ॥*] अत्रास[ञ्च]पराक्रमप्रणयिना जित्वा-
स्त्रिनाम्निद्विषो वा(वा)लादित्यमहानृपेण सकलभुक्ता च भूमण्डलम् [१*]
- „ 9 प्रासादः सुमहानयम्भगवतः शोभादनेरद्भुतः कैलासाभिभवच्छ्रेयः धवलो
मन्ये समुत्थापितः ॥ [६^३ ॥*] अपि च ॥ न्यकुर्व्वन्निन्दुकार्तिन्नुहिनगि-
- „ 10 रिशिरःश्रेणिशोभाच्चिरस्वन् शुभ्रामाकाशगङ्गान्तदनु मलिनयन्मूक्यव्यादि-
सिन्धून् । मन्ये जेतव्यशून्ये भुवन इह वृथा भ्रान्तिरित्याक-
- „ 11 लय्य भ्रान्त्वा क्षीणोमशेषाञ्चितविपुलयशस्तथ उच्चैस्स्थितो वा ॥ [७^४ ॥*]
अवादायि निवेद्यमान्यदधिमहीपस्तथा भासुरद्यातुर्जातक्रेणुमिश्रममल-

¹ From the excellent impressions supplied by Mr. J. A. Page.

• Symbol for *Om* or *Siddham*.

• Metre : Śārdūlavikrīḍitam.

Metre : Śraṅgharā.

- Line 12 न्तोयं सुधाशीतलं । साध्वी चाक्षयनीविका भगवते वु(बु)हाय शुद्धात्मने
मालादेन यथोक्तवंशयशसा तेनातिभक्त्या स्वयं ॥[८¹॥*] आदेशात्स्फीतशोल-
श्रुतधवलधि-
- „ 13 यो भिक्षुसङ्घस्य भूयो दत्तन्तेनैव सम्यग्ब(ग्ब)हुष्टदधिभिव्यञ्जनैर्यत्तर्म-
(म)चं । भिक्षुभ्यस्तच्चतुर्भ्यो [ब]हुसुरभि चतुर्जातकामोदि नित्यं तोयं स[न्ने]
विभक्तं पुनरपि
- „ 14 विमलं भिक्षुसङ्घाय दत्तम् ॥[९²॥*] तेनैवाङ्गतकर्मणा निजमिह क्रीत्वा-
[र्यं]सङ्गान्तिकान्मुक्ता चीवरिकां प्रदाय विधिना सामान्यमेकन्तथा ।
कालम्पेरयितुं सुखे-
- „ 15 न लयनन्दत्तं स्वदेशम्विना तेभ्यो नर्हरिकावधेः परतः शाक्यात्मजेभ्यः
पुनः ॥[१०³॥*] दानं यदेतदमलङ्गुणशालिभिक्षुपूर्णैन्द्रसेनवचनप्रतिवो(बो)-
धितेन । तेन प्रतीत-
- „ 16 यशसा भुवि निर्मलाया भ्रात्रा व्यधाय शरदिन्दुनिभाननायाः ॥[११³॥*]
पित्रोर्भ्रातुः कलत्रस्वसृसुतसुहृदान्तस्य धर्मैकधाम्नो दत्तं दानं यदेतत्सकल-
मतिरसेनायुरा-
- „ 17 रोम्यहेतोः । सर्वेषाञ्चभ्राजां भवभयजलधेः पारसन्तारणार्थं श्रीमत्सम्बो-
(म्बो)धिकल्पद्रुमविपुलफलप्राप्तये चातुमोदम् ॥[१२²॥*] चन्द्रो यावच्चकास्ति
स्फुरदुरुकिरणो लो-
- „ 18 कदीपश्च भास्वान् एषा यावच्च धात्रो सज्जलधिवलयो द्यौश्च दत्ताव-
काशा । यावच्चैते महान्तो भुवनभरधुराभारयन्तो महीध्रास्तावच्चन्द्राव-
दाता धवलयतु दिशाम्-
- „ 19 ऋलं कोर्त्तिरेषा ॥[१३²॥*] यो दानस्यास्य कश्चित्कृतजगदवधेरन्तरायं विद-
ध्यात्माच्चाद्विज्जामनस्यो जिन इह भगवानन्तरस्थः सदास्ते । वा(वा)लादित्येन
राज्ञा प्रदलितरि-
- „ 20 पुष्पा स्थापितश्चैष शास्ता पञ्चानन्त[र्यं]कर्तुर्मतिमतिविषमार्थमर्हीनः स
यायात् ॥[१४²॥*] इत्येवं शीलचन्द्रप्रथितकरणिकस्वामिदत्तावलङ्गणं संज्ञाज्ञां
मूर्ध्नि कृत्वा श्रुतलव-
- „ 21 विभवावप्यनालोच्य भारं । हृद्यामेतामुदारां त्वरितमकुरुतामप्रपञ्चां
प्रशस्तिं वाञ्छेतां किन्न पंगू शिखरितरुफलावासिमुच्चैः करेण ॥[१५²॥*]

¹ Metre: Sārdhūlavikrīḍitam.

² Metre: Sāggharā.

³ Metre: Vasaṭatīlakā.—The last akṣara of the first pīda should be treated as gū u.

TRANSLATION.

(Verse 1.) Continual salutation to the Buddha who made up his mind to emancipate living beings from the strong tangles of the world and who felt exceedingly delighted after giving (*his own*) body to the supplicant, whose foot-lotus is rubbed by the gods, including Indra, with the fishes (*engraved*) in the diadems on their heads and who is conversant with the real nature of all the categories.

(V. 2.) The illustrious, prosperous and highly glorious **Yasōvarmmadēva** has risen after placing his foot on the heads of all the kings and has completely removed the terrific darkness in the form of all of his foes by the diffusion of the rays of his sword. He is the celebrated protector of the world and the cause of the excitement of all the *Padminī* women of the earth. He shines above all in every quarter like the resplendent Sun, who has risen after spreading his rays on the tops of all the mountains and has torn asunder by the diffusion of severe rays the foe in the form of terrible darkness, who is the well-known protector of the world and cause of the blooming of all the lotuses of the earth.

(V. 3.) **Mālāda** was the illustrious and magnanimous son of the well-known **Tikina** (*i.e.*, **Tegin**), who was his (**Yasōvarmmadēva**'s) minister, the Guardian of the Frontier and Ruler of the North. He (**Mālāda**), the unrivalled and quick subduer of the enemies, fulfiller of the desires of the supplicants on the earth, resolute, of stainless family and the son (literally, gladdener) of **Bandhumatī**, was honoured by his (**Yasōvarmmadēva**'s) great favour.

(Vv. 4—6.) **Bālāditya**, the great king of irresistible valour, after having vanquished all the foes and enjoyed the entire earth, erected, as if with a view to see the **Kaiāsa** mountain surpassed, a great and extraordinary temple (*prāsāda*) of the illustrious son of **Suddhōdana** (*i.e.*, the Buddha) here at **Nālandā**. **Nālandā** had scholars, well-known for their (*knowledge of the*) sacred texts and arts, and (*was full of the*) heaps of the rays of the *chaitīyas* shining and bright like white clouds. She was (*consequently*) mocking, as it were, at all the cities of the kings who had acquired wealth by tearing asunder the temples of the great elephants surrounded by the shining black bees which were maddened by drinking the rut in the hostile lands. She had a row of *vihāras*, the line of whose tops touched the clouds. That (*row of vihāras*) was, so to say, the beautiful festoon of the earth, made by the Creator, which looked resplendent in going upwards. **Nālandā** had temples which were brilliant on account of the net-work of the rays of the various jewels set in them and was the pleasant abode of the learned and the virtuous *Saṅgha* and resembled **Sumēru**, the charming residence of the noble *Vidyādharas*.

And—

(V. 7.) (*The prāsāda*), after having gone round the earth and on finding, as it were, that it was a useless wandering when this world had no other structure to be conquered (surpassed), stands aloft, as if it were a column of the great fame it had won, scoffing at the lustre of the moon, disregarding the beauty of the rows of the summits of the Snow-mountain (**Himālaya**), soiling (*i.e.*, throwing into the shade) the white Ganges of the sky, and then turning dumb the streams of disputants.

(V. 8.) Here, **Mālāda** of the above-mentioned family and fame himself brought with great devotion for the pure Lord Buddha the pious permanent grant, pure water as cool as nectar and mixed with the powder of four fragrant objects, as well as, the shining lamp, the offerings of clarified butter and curds.

(V. 9.) Under the order of the community of friars of bright intellect, great piety and learning, he again distributed daily, in a fitting manner, rice with (*various*) preparations, curds and copious *ghee*, to the four monks¹. He again gave to the assembly of monks the pure and highly fragrant water, perfumed with the four² objects (scents) and distributed daily at the *sutras*.

¹ Does it mean "monks from the four quarters"?

² See above, p. 39, f. n. 2.

(V. 10.) He (Mālāda), whose deeds were wondrous, purchased (*everything of*) his own here (*at Nālandā*) from the revered *Saṅgha* and gave it back (*to the bhikshus*) according to rites, barring the monk's robe. He also gave away to the sons of the Śākya, *i.e.*, Buddhist monks, a common dwelling place (*wherein*) to spend time happily, up to and beyond Narddarikā, excepting a place for himself.¹

(V. 11.) This stainless gift has been made by him who is the brother of Nirmmalā² whose face resembled the autumnal moon. His fame is spread over the world and he has been awakened by the words of the monk Pūrṇendrasēna, who shines by his excellence.

(V. 12.) All this gift has been given with great devotion for the sake of the welfare and longevity of the parents, brother, wife, sister, son and friends of him (*i.e.*, Mālāda) who is the sole repository of virtue. May it be approved so that the living beings might cross the fearful ocean of the world and attain the great fruit of the Wishing Tree in the form of the sacred Enlightenment (*Bōdhi*).

(V. 13.) As long as the Moon shines and the Sun, the lamp of the world, with his lustrous and extensive rays (*sheds light*), as long as this earth together with the encompassing ocean endures and the sky, which gives space, lasts, and as long as these great mountains, bearing the yoke of the world, remain, so long let this *kīrti*, which is pure like the Moon, whiten the circle of (*all*) the quarters.

(V. 14.) Whoever interferes with this gift, which has to last as long as the world endures, will, void of virtue as he is, have the dire fate of one who commits the five sins—(*let him know*) that the Lord Jina (the Buddha) is here ever present within, occupying the adamant seat and that the great king Bālāditya has established this command (or the image of the Buddha).³

(V. 15.) Thus, Śilachandra and the well-known *Karaṇika* Svāmīdatta, having placed the order of the *Saṅgha* on their head, without considering the weight (*of responsibility*), composed at once this beautiful and sublime, though simple, *praśasti*, although the wealth of their knowledge is small, for, will not even the cripples⁴ wish to get the fruits from the tree on the mountain by raising (*their*) hand?

No. 3.—THREE TAMIL INSCRIPTIONS OF LALGUDI.

By K. V. SUBRAHMANYA AIYER, B.A., M.R.A.S., OOTACAMUND.

The three inscriptions which form the subject of this article are incised on the north wall of the Saptarishīśvara temple at **Lalgudi** in the Trichinopoly district. For the sake of convenience, I call them A, B and C. Inscription A is dated in the year opposite to the fourth (*i.e.*, the fifth year) of some king whose name is not given in it. It registers a gift of money made by the Pallava king Nandippōttaraiyar who fought the battle of **Tellāru** and gained victory in it, for burning a perpetual lamp in the temple of Mahādēva at Tiruttavatturāi in **Idaiyārru-nādu**. The amount was received by the members of the assembly of **Nallimaṅgalam** who bound themselves to bring to the temple and measure out daily (*one*) *nāḷi* of ghee.

¹ Does all this mean that Mālāda became a Buddhist monk for some time and again became a *grihastha* as the Burmese do even now-a-days?

² See above, page 41.

³ See foot-note 1 on page 39 above. The construction of this verse is not quite clear. Dr. Vogel thinks that the stanza might be referring to two images of the Buddha—the Buddha of the Vajrasana, being the Bōdhi image enshrined in the principal temple, and second, of the Teacher, perhaps an image of the Buddha shown in the act of teaching, which had been consecrated by Bālāditya.

⁴ The word *paṇḍu* is put in the dual number because the *praśasti* was composed by two authors.

Inscription B is dated on the day of Śadaiyam (Śatabhishaj) corresponding to a Tuesday in the month of Dhanuṣ falling in the ninth year opposite to the fourth (*i.e.* the thirteenth year) of the reign of king Mārañjaḍaiyaṇ. In the body of the record the king is called Pāṇḍyakulapati Varaguṇa-Mahārāya. The inscription states that the king gave 120 *kāṣu* to a certain Aṇḍaṇṭṭu-Vēlāṇ. This amount was finally received by the members of the assembly of Iḷamperuṅkāy-irukkai in Iḍaiyāṇṇu-nāḍu who bound themselves to supply towards interest, the capital remaining intact, one *uri* of ghee daily for burning a perpetual lamp in the temple. In case of default the assembly further agreed to pay a fine of 500 *kāṇam* (of gold). Inscription C is dated in the thirteenth year of the reign of the Chōḷa king Rājakēsarivarman. It states that the king's uterine sister Nāṅgai-Varaguṇa-Perumāṇār gave 30 *kalanju* of gold for a perpetual lamp to be burnt in the temple with one *uri* of ghee daily. The assembly of Maṇalkāl, a *brahmadēya* of Kālāra-kūṇṇam which was a subdivision of Vaḍagarai-Maḷa-nāḍu, received the amount given and sold a piece of land in exchange to the temple.

Before taking up the question of the date of these three inscriptions, I may point out straightway that they are written in the same hand and script and must consequently have been inscribed simultaneously. I may here add that there is another inscription in this very temple which is coeval with these records and is, apparently, written by the same hand though it refers itself to the Pallava king Nṛpatuṅavarman. It has already been published in the *South-Indian Inscriptions (Texts)*, Volume IV.¹ Inscriptions of the three kings mentioned in these records are also found in several other places. But they are all written in varying types of the Tamil script not resembling the one in which the three inscriptions under notice are incised. As these kings flourished at different periods, the records belonging to their respective reigns could not have been written in the same hand. Consequently, the Lalgudi inscriptions under examination, written as they are in the same hand, must be treated as later copies of older records made probably at the time when the temple where they are found was renovated or repaired. Palaeographically they can be assigned to the 10th century of the Christian era.

The inscription which I call C purports to belong to a ruler who is the latest among the kings mentioned in these three inscriptions. The princess referred to in it figures as the queen of Parāntaka Iḷaṅgōvēlār² in another inscription of Rājakēsarivarman which was found at Tillaisthānam in the district of Tanjore. She is also mentioned in a somewhat later record belonging to the third year of Parakēsarivarman.³ The Tillaisthānam inscription of Rājakēsarivarman, unlike the Lalgudi inscription, marks the *pulli* or *virāma* as do the Takkōlam and other inscriptions of Rājakēsarivarman, *i.e.*, Āditya I, and ought to be assigned to the same ruler. Two other epigraphs found at Tiruppalāttur⁴ refer to Teṇṇavaṇ Iḷaṅgōvēlār which is another name for Parāntaka Iḷaṅgōvēlār. They tell us that he was also called Maṇavan Pūḍiyār. One of them mentions his queen Kaṇṇalippirāṭṭiyār also. The name Pūḍiyār given to Iḷaṅgōvēlār and the mention of his queen would show that he is identical with the Koḍumbālūr chief Bhūti-Vikramakēsari who is reported in the Mūvarkōvil inscription to have married Kaṇṇali and Varaguṇā.⁵ From a Tiruchchendurai inscription we learn that he had a daughter named Pūdi-Ādicchapiḍāriyār who was the queen of Arikulakēsari, *i.e.*, Ariṇḍaya⁶ the son of the Chōḷa king Parāntaka I. I have shown

¹ See plate (VII) opposite to p. 173.

² *South-Indian Inscriptions*, Vol. III, No. 113.

³ *Ibid.* No. 127.

⁴ Nos. 258 and 273 of Appendix A to the *Annual Report on South-Indian Epigraphy* for 1903-04, and para. 90 of part II of the *Annual Report on South-Indian Epigraphy* for 1907-08.

⁵ *Annual Report on South-Indian Epigraphy* for 1907-08, para. 90 of Part II.

⁶ Nos. 316, 317 and 319 of Appendix A to the *Annual Report on South-Indian Epigraphy* for 1903-04.

elsewhere¹ that Āditya I must have ascended the throne in A.D. 871. Accordingly, the Lalgudi inscription, which also belongs to him, must be assigned to A.D. 883-4, for it is dated in the 13th year of his reign.

To settle the dates of the inscriptions A and B we have to consider the way in which they are dated. We find that they give some year opposite to the fourth. This mode of dating was adopted by the Pāṇḍya king Māraṇjadaiyan *alias* Varaguṇa-Mahārāja, as is evidenced by several inscriptions of his reign which have already been brought to light.² Consequently, these two records also should be ascribed to the same ruler.

We have now to establish the date of the accession of Teḷḷārreinda-Nandippōttavarman and of his contemporary Varaguṇa-Mahārāja I, who was the grandfather of Varaguṇavarman II and father of Śrīmāra Śrīvallabha Parachakrakōlāhala, the conqueror of Ceylon. The *Mahāvamsa* tells us that there was a Pāṇḍya invasion of Ceylon during the reign of Silāmēgha Sēna I (A.D. 846 to 866), in which the Pāṇḍya king came off completely victorious and took possession of the capital and carried away a large amount of booty, though he eventually restored the Sinhalese kingdom to its rightful king. The only early Pāṇḍya king who is known from the Siṅga-manūr plates to have invaded and conquered Ceylon is Śrīmāra. From the facts recorded in the *Mahāvamsa* it can be gathered that his reign covered the last 3 years of the rule of Dappula and probably commenced in the year 840 and ended in 862 A.D. when his eldest son Varaguṇavarman II succeeded him. Śrīmāra's predecessor, namely, Varaguṇa-Mahārāja I, must have reigned prior to 840 A.D. His latest regnal year so far known from inscriptions is the seventeenth and we can reasonably state that his rule over the Pāṇḍya country may have extended from 823 to 840 A.D. though it is not impossible that it might have commenced a few years earlier. The date of Varaguṇa I can approximately be ascertained from the chronology of the Pallava kings from Nandivarman Pallavamalla to Aparājita. The Vēlūrpālaiyam plates give us the genealogy of the latter Pallavas for three generations commencing from Nandivarman II Pallavamalla.³ They state that Pallavamalla's son was Dantivarman and that the latter's son was Nandivarman III. This information is supplemented by the Bāhūr plates which tell us that Dantivarman's son was Nandivarman III, who had for his queen the Rāshtrakūṭa princess Śaṅkhā, and that the latter's son was Nripatuṅga.⁴ It is to be noted that in these plates no mention is made of Kampavarman and the name Kampavarman was not borne by any one of the above mentioned kings. If Kampavarman was a lineal descendant of Nandivarman Pallavamalla, we might tentatively assume that he was another, and, perhaps, the younger son of Nandivarman III. The name Nandi-Kampēsvara given to the temple at Śōlapuram may have been called after Kampavarman, the son of Nandivarman.⁵ It may be pointed out here that both the palaeographical peculiarities of Kampavarman's epigraphs and the genealogy furnished by the Vēlūrpālaiyam as well as the Bāhūr plates do not admit of any place for him before Nripatuṅga. It will be shown presently that he cannot be made the immediate successor of Nripatuṅga. Therefore the only inference that could be drawn regarding Kampavarman is that he must have been a joint ruler with either Nripatuṅga or Aparājita

¹ *Ep. Ind.*, Vol. XIX, pp. 81 ff.

² See *Ep. Ind.*, Vol. IX, pp. 84 ff., and No. 13 of Appendix C of the *Annual Report on South-Indian Epigraphy* for 1907-08, Nos. 90 and 137 of Appendix B of the *Annual Report on South-Indian Epigraphy* for 1908-09, Nos. 358 and 364 of Appendix B of the *Annual Report on South-Indian Epigraphy* for 1907-08 and No. 84 of Appendix C of the *Annual Report on South-Indian Epigraphy* for 1909-10.

³ *South-Indian Inscriptions*, Vol. II, pp. 501 ff.

⁴ *Ep. Ind.*, Vol. XVIII, pp. 5 ff.

⁵ *Ibid.*, Vol. VII, p. 196. The name Kampavarman, just like Nripatuṅga, also suggests that he might have been so called after Kambha (Stambha), the eldest son of the Rāshtrakūṭa king Dhāravarsha Dhruva. In that case Nandivarman might have married a daughter of Kambha (or Stambha).

or with both.¹ Therefore, it is needless to take his reign into consideration to determine the period when the later Pallavas ruled. From the Āmbūr inscription dated in the 26th year of the reign of Nripatuṅga, we learn that the Gaṅga king Prithivīpati I was a subordinate of that Pallava king.² And since it is recorded in the Udayēndiram plates that this very Gaṅga king was an ally of the Pallava king Aparājita and fought under his standard and secured victory for him in the battle of Śrīpurambiyam against Varaguṇa (II),³ it might be said that Aparājita⁴ was the immediate successor of Nripatuṅga. That he was the last Pallava ruler of Kāñchī is known from the Tiruvālaṅgādu plates which report that the Chōla king Āditya I killed him and took possession of his kingdom.⁵ This event, we have reasons to believe, must have taken place before A.D. 891, for it is stated in an inscription at Tirumālpuram near Conjeeveram that the village of Śiriyārrūr in Maṇaiyil-nādu was granted as a *dēvadāna* and as a *brahmadēya* in the 21st year of Tonḍaimān-Ārrūr-tuṅjiṇa-uḍaiyār i.e., Āditya I⁶. If we allow at least two years for his settlement in the newly conquered country, it may be said that Āditya I killed Aparājita in about A.D. 888. The latest dates furnished by the stone inscriptions for Nandivarman Pallavamalla, Dantivarman, Nandivarman, the victor of Tellāru. i.e., Nandivarman III, Nripatuṅga and Aparājita are 65, 52, 22, 26 and 18, respectively. With the help of these, supplemented to a certain extent by the light of contemporary history, we shall try to settle the chronology of the later Pallava sovereigns. Keeping A.D. 888 as the last year of Aparājita and deducting from it 18, which is the highest regnal year known for him,⁷ we get A.D. 870 for his accession. This date must, therefore, be the year when his predecessor Nripatuṅga ceased to rule. Since the latest regnal year so far found for him is 26,⁸ we get A.D. 844 for his accession. It may be noted here that the initial year of Nripatuṅga's reign cannot be earlier than this date because in a record of his 18th year the Pāṇḍya king Varaguṇa-Mahārāja (II) figures as donor⁹ and we know for certain that that king's accession took place in A.D. 862.¹⁰ We have to take A.D. 844 as the last year of Nripatuṅga's father Nandivarman III, the victor of Tellāru. The latest regnal year found for him in the inscriptions mentioning the victory of Tellāru is 22.¹¹ But there is a possibility of his having reigned longer.¹² If he had a reign of 22 years, his accession would have to be placed in A.D. 822. This cannot be the case for, we learn from the Western-Gaṅga grants that the Rāshtrakūṭa king Gōvinda III and the Pallava king Nandivarman—both crowned kings themselves—fastened the fillet of royalty on the forehead of Śivamāra II Saigotṭa.¹³ The last year of Gōvinda

¹ In a Tamil inscription of Uttaramallūr of the time of Kampavarman dated in his 15th year whose text (No. 325) is published in the *S. I. I. (Texts)*, Vol. VI, the donor is Seyya-Aparājita, and he is called Perumāṇadigaḷ-adiyāṇ.

² *Ep. Ind.*, Vol. IV, p. 182.

³ *S. I. I.*, Vol. II, p. 334.

⁴ It is learnt from No. 350 of Vol. VI of *S. I. I. (Texts)*, that Aparājita bore the title Rājamārttāṇḍa.

⁵ *S. I. I.*, Vol. III, p. 419, v. 49. This statement is confirmed by a stone inscription found at Tillasthānam which styles Āditya I as "Rājakēsarivarman who extended his territory into Tonḍai-nādu" (*Ibid.*, p. 221, No. 89).

⁶ *Annual Report on Epigraphy* for 1907, Part II, paras. 29 and 30.

⁷ No. 435 of the Madras Epigraphical Collection for 1905.

⁸ *Ep. Ind.*, Vol. IV, p. 182.

⁹ No. 360 of the Madras Epigraphical collection for 1921.

¹⁰ No. 705 of the same collection for 1905.

¹¹ No. 180 of the same collection for 1907.

¹² In the numerous epigraphs dated simply in the reign of Nandivarman without the distinguishing epithets 'Pallavamalla' or 'Tellārrerinda' there must be some belonging to Nandivarman III, while the others may be of Pallavamalla.

¹³ *Ep. Ind.*, Vol. V, pp. 158 and 161.

III being A.D. 814¹ this event should have occurred before that date, say about A.D. 812. Accordingly, we have to take back the year of accession of Nandivarman III by ten years. Looking at the fact that Nandivarman Pallavamalla and his son Dantivarman had unusually long reigns, extending to 65 and 51 years,² it seems improbable that Nandivarman III, who succeeded Dantivarman, could have ruled long and, since the last year of his reign cannot be taken earlier than A.D. 844, it will be safe to assume that his rule lasted from A.D. 812 to 844. Deducting 51 from 812 and 65 from the balance we get the initial dates of Dantivarman and Nandivarman Pallavamalla. Their reigns should, therefore, have extended from A.D. 761 to 812 and A.D. 696 to 761. The chronology as worked out from these facts and others noted later on is shown below :—

Pāṇḍya kings.	Pallava kings.	Rāshtrakūṭas.	Western Gaṅgas.	Chōlas.
Māra-varman	Nandivarman II Pallavamalla			
Neḍuñjaḍaiyaṇ				
Rājasimha	Dantivarman	Gōvinda III	Śivamāra II	
Varaṅga I	Nandivarman III			
Śrīmāra	Nripataṅga	Amoghavarsha I	Prithvīpati I	
Varaṅga II	Aparājita			
				Āditya I

Since Nandivarman, the victor of Tellāru, figures as donor in the Lalgudi inscription A dated in the 5th year, evidently of the reign of Mārañjaḍaiyaṇ *alias* Varaṅga-Mahārāja I, that record cannot be placed earlier than A.D. 812 or later than A.D. 844 which are the initial and closing years of Nandivarman III. From this, it is clear that the date of accession of Varaṅga I cannot be taken to an earlier date than A.D. 807. We have already shown that it cannot be later than A.D. 823. In order to arrive at the actual year of accession of Varaṅga I, the astronomical details furnished in two inscriptions, which are both dated in 4+9th (*i.e.*, the 13th) year of Mārañjaḍaiyaṇ (*i.e.*, Varaṅga-Mahārāja I), may be considered here. One of them is the inscription B edited below and the other is from Tiruveḷḷarai.³ While the former gives the astronomical combination (a) **Dhanus, Tuesday and the nakṣatra Śatabhishaj**, the latter furnishes another set of combinations, *viz.*, (b) **Vṛiśchika, Monday and the nakṣatra Āśvinī** in the same year, *i.e.*, 13th. Between A.D. 800 and 852, though there are several years in which each set of combinations occurred separately, the following table gives such of those years only as con-

¹ *Ibid.*, Vol. III, p. 54.

² No. 666 of the Madras Epigraphical collection for 1922 and No. 262 of the same collection for 1924.

³ The details of date furnished in this record have been calculated by the late Mr. R. Sewell for Varaṅga I in *Ep. Ind.*, Vol. XI, p. 233. But as it is dated in the 9th year opposite to the fourth it is clearly a record of Varaṅga I.

tained both sets of details, the days corresponding to the combinations (a) and (b), the initial and fifth years of the king :—

No.	Year.	Equivalents of (a) and (b).	Initial year.	5th year.
1	814	(a) Tuesday, 19th Dec. (b) Monday, 30th Novr.	801 A.D. .	806 A.D.
2	817	(a) Tuesday, 15th Dec. (b) Monday, 26th Octr.	804 . .	809
3	824	(a) Tuesday, 29th Novr. (b) Monday, 7th Novr. f.d.n. 71	811 . .	816
4	831	(a) Tuesday, 12th Dec. f.d.n. 38 (b) Monday, 20th Novr. f.d.n. 01	818 . .	823
5	834	(a) Tuesday, 8th Dec. f.d.n. 56 (b) Monday, 16th Novr. f.d.n. 70	821 . .	826
6	841	(a) Tuesday, 22nd Novr. f.d.n. 23 (b) Monday, 31st Octr. f.d.n. 94	828 . .	833
7	851	(a) Tuesday, 1st Dec. (b) Monday, 9th Novr.	838 . .	843

Since the first two give the fifth year equivalents A.D. 806 and 809 they have to be rejected for the reason that Tellāṟṟeṟinda Nandivarman cannot figure in them. Similarly, Nos. 6 and 7 have to be abandoned because, according to them, the 17th year would work out to be A.D. 845 and 855, both of which are later than the lower limit fixed for Varaguna I. The only three that could be adopted are Nos. 3, 4 and 5 which would give us, for the king's succession, the years A.D. 811, 818 and 821. Even out of these, Nos. 4 and 5 may be given up as their adoption would narrow the possible longer range of reigns of both Varaguna I and Śrīmāra. It seems that the only probable date for Varaguna's accession is A.D. 811. This conclusion is not entirely without grounds. The internal evidence furnished in the Āṇamalai inscription, Madras Museum Plates and the Vēlvikuḍi grant shows that A.D. 770 must fall somewhere between the 3rd and 17th years of the reign of Parāntaka Neḍuñjaḍaiyaṇ to whose time they all belong¹. After Parāntaka and before Varaguna I, only a single king intervened, i.e., Rājasimha and his reign, as at present known, was an eventless one. Therefore, the period of forty-one years from A.D. 770 to A.D. 811 is more than sufficient to cover the rest of the reign of Parāntaka Neḍuñjaḍaiyaṇ from the time of the Āṇamalai record and the eventless rule of Rājasimha. For these reasons, therefore, adopting A.D. 811 as the date of accession of Varaguna I, we may assign A.D. 816 to inscription A and A.D. 824 to B.

Of the places mentioned in these inscriptions, many can be easily identified. Tiruttavatturai² must be Lalgudi itself because, the inscriptions are found there. Maṇakkāl³ is the homonymous village in the Trichinopoly district and Eḍayattimaṅgalam, not far from Lalgudi, might have been the principal place in Iḍaiyāṟṟu-nāḍu in which Tiruttavatturai is said to have been situated. I am not able to trace Nallimaṅgalam and Ilamperuṅgāy-irukkai. Tellāṟu, where Nandivarman gained a victory, is in the Wandiwash taluk of the North Arcot district.

¹ See *Ind. Ant.*, Vol. XXII, pp. 57 ff.; *Ep. Ind.*, Vol. XVII, pp. 291 ff.; and *Ep. Ind.*, Vol. VIII, pp. 317 ff.

² There is also a village, called Tiruttavatturaikkattalai in the Trichinopoly District.

³ A village of this name is in Uḍaiyārpālayam taluk, but this cannot be the one referred to in these inscriptions.



TEXT OF A.

- 1 Svasti śrī [!]* Yāṇḍu 4-vadiṇ edirām-āṇḍu Idaiyāṇṇu-nāṭṭu-tTiruttavatturāi-Māhādēvark 'ku' Teḷḷēṇṇu-ēṇṇu-veṇṇa Nandippōtta[r]ai-
- 2 yar kuḍutta paḷaṇ-kāṣu 60-du [!]* ivv-aṇṇu-padu kāsum i-nṇāṭṭu Nallimaṇḍalattu sabhaiyōm ivv-aṇṇu-padu kāsum(m) Tiruttavatturāi-Māhādēvar-
- 3 idai koṇḍu nārāya-nāḷiyāl niśadi nāḷi ney oru nondā-viḷakku śandir-ādittaval irav[um] pagalum eriya-kkoṇḍu-ṣeṇṇu aḷappōmā[nō]-
- 4 m[!]* Nallimaṇḍalattu sabhaiyōm Tiruttavatturāi-Mahē(hā)dēvarkku aḷavōmāyil muṭṭil muṭṭ-iraṭṭiyum mūlappaṭṭa paṇ-mahēśvara[rē]
- 5 sabhaiy-āgavum tanitt-āgavum nilaikkāḷam-uḷḷiṭṭa tān vēṇḍu kōviṇṇukku pukka
 2. iru-nūṇṇu-ppadiṇṇ-āṇṇu kāṇam daṇḍam-iḍa [v]e-
- 6 ṭṭinōm Nallimaṇḍalattu sabhaiyōm [!]* idu paṇ-māhēśvarar nārppatt-eṇṇāyiravarum
 ī(i)rakshai ||.

TRANSLATION.

Hail! Prosperity! In the year opposite to 4, Nandippōttaraiyar, who fought the battle of Teḷḷāru and gained victory (*in it*), gave 60 old *kāṣu* to (*the temple of*) Mahādēva at Tiruttavatturāi in Idaiyāṇṇu-nāḍu. Having received from the temple of the Mahādēva of Tiruttavatturāi these sixty *kāṣu*,³ we, (*the members of*) the assembly of Nallimaṇḍalam in this *nāḍu*, bound ourselves to take (*to the temple*) and measure out daily (*one*) *nāḷi* of ghee by the measure called *nārāya-nāḷi*, for burning one perpetual lamp as long as the sun and moon last. If we, (*the members of*) the assembly of Nallimaṇḍalam, fail (*in our undertaking*) and do not measure out (*the ghee*) to the temple of the Mahādēva of Tiruttavatturāi, all the Māhēśvaras attached to the central shrine⁴ shall levy on (*us, the members of*) the assembly, as a body or individually, a fine of two hundred and sixteen *kāṇam* and this shall be paid to the royal officers⁵ inclusive of the *nilaikkāḷam*⁶ whichever they desire. Thus we, (*the members of*) the assembly of Nallimaṇḍalam, had this (*edict*) incised. This (*charity*) shall be under the protection of all the Forty-Eight Thousand Māhēśvaras.

TEXT OF B.

- 1 Svasti śrī [!]* Kō-Māraṇḍaiyarkku yāṇḍu 4-vadiṇ edir 9-ām-āṇḍu Dhanu-nāyirru Śevvā[y*]-kkiḷamai peṇṇa Śadaiya(m)ttu [nāḷi]-
- 2 daiyāṇṇu-nāṭṭu Tiruttavatturāi-Māhādēvarkku¹ iravum pagalum śandir-ādittaval iraṇḍu no[nḍā-ttiru-viḷakku]
- 3 erippadāga kō-Māraṇḍaiyāṇḍa(ā)yīṇa Pāṇḍya-kulapati Varaguṇa-Māhārāyar²
 Aṇḍa-nāṭṭu-Vēḷāṇ [k]aiy[il-kkuḍutta pa]ḷa[n]-

¹ Read *Māhādēvarkku*.

² The symbols can be read as *vūḷa* (mistake for *vūḷa*) which with the preceding *pukka* becomes *pukkar-uḷa*.

³ The words 'ivv-aṇṇu-padu kāsum' are repeated twice in the record.

⁴ The words 'mūlappaṭṭa paṇ-māhēśvara' here used stand in the place of 'mūlappaṭṭuḍai paṇḍi-āḷḍarāy dēvakaṇṇi' occurring in other inscriptions. The body meant by the term appears to have been constituted into an assembly for managing the affairs of the temple and was called 'uṇṇāḷigai-vāriya' or 'uṇṇāḷigai-saḷḷai'.

⁵ 'Kō' literally means 'a king'.

⁶ *Nilai*=stationary and *kāḷam*=field or body. As such, the expression may mean 'a standing committee'.

⁷ Read *Māhārāyar*.

A AND B

1. 2. 3. 4. 5. 6. 7. 8. 9. 10. 11. 12. 13. 14. 15. 16. 17. 18. 19. 20. 21. 22. 23. 24. 25. 26. 27. 28. 29. 30. 31. 32. 33. 34. 35. 36. 37. 38. 39. 40. 41. 42. 43. 44. 45. 46. 47. 48. 49. 50. 51. 52. 53. 54. 55. 56. 57. 58. 59. 60. 61. 62. 63. 64. 65. 66. 67. 68. 69. 70. 71. 72. 73. 74. 75. 76. 77. 78. 79. 80. 81. 82. 83. 84. 85. 86. 87. 88. 89. 90. 91. 92. 93. 94. 95. 96. 97. 98. 99. 100. 101. 102. 103. 104. 105. 106. 107. 108. 109. 110. 111. 112. 113. 114. 115. 116. 117. 118. 119. 120. 121. 122. 123. 124. 125. 126. 127. 128. 129. 130. 131. 132. 133. 134. 135. 136. 137. 138. 139. 140. 141. 142. 143. 144. 145. 146. 147. 148. 149. 150. 151. 152. 153. 154. 155. 156. 157. 158. 159. 160. 161. 162. 163. 164. 165. 166. 167. 168. 169. 170. 171. 172. 173. 174. 175. 176. 177. 178. 179. 180. 181. 182. 183. 184. 185. 186. 187. 188. 189. 190. 191. 192. 193. 194. 195. 196. 197. 198. 199. 200. 201. 202. 203. 204. 205. 206. 207. 208. 209. 210. 211. 212. 213. 214. 215. 216. 217. 218. 219. 220. 221. 222. 223. 224. 225. 226. 227. 228. 229. 230. 231. 232. 233. 234. 235. 236. 237. 238. 239. 240. 241. 242. 243. 244. 245. 246. 247. 248. 249. 250. 251. 252. 253. 254. 255. 256. 257. 258. 259. 260. 261. 262. 263. 264. 265. 266. 267. 268. 269. 270. 271. 272. 273. 274. 275. 276. 277. 278. 279. 280. 281. 282. 283. 284. 285. 286. 287. 288. 289. 290. 291. 292. 293. 294. 295. 296. 297. 298. 299. 300. 301. 302. 303. 304. 305. 306. 307. 308. 309. 310. 311. 312. 313. 314. 315. 316. 317. 318. 319. 320. 321. 322. 323. 324. 325. 326. 327. 328. 329. 330. 331. 332. 333. 334. 335. 336. 337. 338. 339. 340. 341. 342. 343. 344. 345. 346. 347. 348. 349. 350. 351. 352. 353. 354. 355. 356. 357. 358. 359. 360. 361. 362. 363. 364. 365. 366. 367. 368. 369. 370. 371. 372. 373. 374. 375. 376. 377. 378. 379. 380. 381. 382. 383. 384. 385. 386. 387. 388. 389. 390. 391. 392. 393. 394. 395. 396. 397. 398. 399. 400. 401. 402. 403. 404. 405. 406. 407. 408. 409. 410. 411. 412. 413. 414. 415. 416. 417. 418. 419. 420. 421. 422. 423. 424. 425. 426. 427. 428. 429. 430. 431. 432. 433. 434. 435. 436. 437. 438. 439. 440. 441. 442. 443. 444. 445. 446. 447. 448. 449. 450. 451. 452. 453. 454. 455. 456. 457. 458. 459. 460. 461. 462. 463. 464. 465. 466. 467. 468. 469. 470. 471. 472. 473. 474. 475. 476. 477. 478. 479. 480. 481. 482. 483. 484. 485. 486. 487. 488. 489. 490. 491. 492. 493. 494. 495. 496. 497. 498. 499. 500. 501. 502. 503. 504. 505. 506. 507. 508. 509. 510. 511. 512. 513. 514. 515. 516. 517. 518. 519. 520. 521. 522. 523. 524. 525. 526. 527. 528. 529. 530. 531. 532. 533. 534. 535. 536. 537. 538. 539. 540. 541. 542. 543. 544. 545. 546. 547. 548. 549. 550. 551. 552. 553. 554. 555. 556. 557. 558. 559. 560. 561. 562. 563. 564. 565. 566. 567. 568. 569. 570. 571. 572. 573. 574. 575. 576. 577. 578. 579. 580. 581. 582. 583. 584. 585. 586. 587. 588. 589. 590. 591. 592. 593. 594. 595. 596. 597. 598. 599. 600. 601. 602. 603. 604. 605. 606. 607. 608. 609. 610. 611. 612. 613. 614. 615. 616. 617. 618. 619. 620. 621. 622. 623. 624. 625. 626. 627. 628. 629. 630. 631. 632. 633. 634. 635. 636. 637. 638. 639. 640. 641. 642. 643. 644. 645. 646. 647. 648. 649. 650. 651. 652. 653. 654. 655. 656. 657. 658. 659. 660. 661. 662. 663. 664. 665. 666. 667. 668. 669. 670. 671. 672. 673. 674. 675. 676. 677. 678. 679. 680. 681. 682. 683. 684. 685. 686. 687. 688. 689. 690. 691. 692. 693. 694. 695. 696. 697. 698. 699. 700. 701. 702. 703. 704. 705. 706. 707. 708. 709. 710. 711. 712. 713. 714. 715. 716. 717. 718. 719. 720. 721. 722. 723. 724. 725. 726. 727. 728. 729. 730. 731. 732. 733. 734. 735. 736. 737. 738. 739. 740. 741. 742. 743. 744. 745. 746. 747. 748. 749. 750. 751. 752. 753. 754. 755. 756. 757. 758. 759. 760. 761. 762. 763. 764. 765. 766. 767. 768. 769. 770. 771. 772. 773. 774. 775. 776. 777. 778. 779. 780. 781. 782. 783. 784. 785. 786. 787. 788. 789. 790. 791. 792. 793. 794. 795. 796. 797. 798. 799. 800. 801. 802. 803. 804. 805. 806. 807. 808. 809. 810. 811. 812. 813. 814. 815. 816. 817. 818. 819. 820. 821. 822. 823. 824. 825. 826. 827. 828. 829. 830. 831. 832. 833. 834. 835. 836

2
4
6
8
10
12
14
16
18

Handwritten text in Tamil script, likely a religious or philosophical manuscript. The text is arranged in approximately 18 horizontal lines. The script is dense and characteristic of traditional Tamil. Marginal numbers 2, 4, 6, 8, 10, 12, 14, 16, and 18 are visible on the left side of the page, corresponding to the lines of text. The text appears to be a continuous passage, possibly a commentary or a prayer.

- 4 kāsū 120 [*]nūrr-irupadu kāsūn(m) muda[l] ke[dā]m[ai]y poli[y-ū]tṭināl nīśadi
nā¹
- 5 aḷappōm-āyinōm ippaḍi oṭṭi i-kkāsū koṇḍō[m] Iḍaiyārru-nāṭṭu Iḷamperuṅkāy-
iruk[k]ai [sabhaiyō]-
- 6 m [*] i-nēy nīśadi iru-nāḷiyum muṭṭil muṭṭ-irattiyum mūlap[pa]ṭṭa pan-
māhēśvararē sabhaiy-āgavum tanitt-āgavum ni²
- 7 Iṭṭa tāṇ vēṇḍu kōviṇṇukku pukka 37³ aṇṇūgu kāṇam daṇḍam-iḍa oṭṭi-
kkuḍuttōm Tiruttavatturai-Mahādēvarkku [r*]

TRANSLATION.

Hail! Prosperity! In the 9th year opposite to the 4th year of (the reign of) king Māraṇjaḍaiyaṇ corresponding to the day of Śadaiyam, i.e., Satabhishaj (falling) on a Tuesday in the month of Dhanu, king Māraṇjaḍaiyaṇ alias Pāṇḍyakulapati Varagupa-Mahārāya gave into the hands of Aṇḍa-nāṭṭu-Vēḷāṇ 120 old kāsū for burning day and night, till the sun and the moon last, two perpetual lamps in the temple of the Mahādēva at Tiruttavatturai in Iḍaiyārru-nāḍu. As interest on these one hundred and twenty kāsū—the capital remaining un-affected—we bound ourselves to measure out daily [two nāḷi of ghee by the nārāya-nāḷi measure]. Thus agreeing, we, (the members of) the assembly of Iḷamperuṅkāy-irukkai in Iḍaiyārru-nāḍu, received these kāsū. If (any) default occurs in (giving) these two nāḷi of ghee daily, we agreed on behalf of the Mahādēva of Tiruttavatturai to pay, either in a body or individually, double the (quantity at) default and a fine of five hundred kāṇam (of gold) to the royal (officers) inclusive of [nīlakkāḷam] as the Māhēśvaras attached to the central shrine desire.

TEXT OF C.

- 1 Svasti śrī [r*] Kō-Rājakēsaripanma[r*]kku yāṇḍu 13-āvaḍu Iḍaiyārru-
nāṭṭu-tTiruttavatturai I-
- 2 śvara-baṭṭāra[kar]kku Śōlapperumāṇ-aḍigaḷ tiru-uḍappiraṇḍār Naṅgai-
Varagupa-perumāṇār śandir-ā-
- 3 dittavaṇ iravum pagalum eru noṇḍā-viḷakku nīśadi uriy ne[y]yāl⁴ erivadaṇk-
ku kuḍutta po[n]
- 4 30 muppadiṇ kaḷāṇju poṇṇum Vaḍakarai-Maḷa-nāṭṭu Kalāra-kku(kū)ṛrattu
mēl-kūrru pirama-
- 5 dēyam Maṇalkāl sabhaiyōm koṇḍu i-ppoṇ 30 kaḷāṇjuṇ-koṇḍu Tirut[ta]-
vatturai Perumāṇ-aḍigaḷukku tiruviḷakkiṇṇukku viṇṇu-kkuḍutta nilammāvaḍu⁵ Mē[r]-
ppulattu Maṇamutti-ttiḍalin-kīlai eṇgaḷ nāṅgu-mā-kkāṇiyum pōyum viṇṇu[ra]
nilattukku ellai Śirugavūr vēṭṭappērrin vaḍavāy mūṇru mā-kkāṇiyum pō-
[yu]-
- 9 m viṇṇu[ra] nilattukku ellai Śirugavūr ellai va[y*]kkālin-kkīlai⁶ iraṇḍu-
māvum
- 10 pōyum viṇṇu[ra] nilattukk-ellai nāṅgaḷē Talaivāyaṇukku kuḍutta ve-
ṭṭa[p]pērrin-kīlai arai-māvum āga-ttaḍi nāṅgiṇāl nilam araiyum u-
ṇṇilam oḷiviṇṇi i-ppoṇ 30 [ka*]ḷāṇjuṇ-koṇḍu i-ūilam pattu-chcheyum iraiy-
iliyāga viṇṇu vilaiy-āvaṇaṇ-cheyidu⁷ śo-

¹ This gap may be filled up with the words "rāya nāḷiyāl iru-nāḷi ney".

² The letters *laikkāḷam-u* are damaged.

³ The first *y* in *neyyāl* is corrected from *yī*.

⁴ Read *°kīlai*.

⁵ See note 2 on p. 52.

⁶ Read *nilammāvaḍu*.

⁷ Read *°cheydu*.

- 13 nnīr vet̥ti utpāda maṛṛum eppērppaṭṭa vet̥tiyum iraiyum echchōṛum vedi-
naiyum eppērppaṭṭadum-irādadāga viṛṛu vi-
14 lai-āvaṇaṇ-che[y*]du kuḍuttōm Tiruttavatturai-Mahādēvarkku Maṇaṛkāḷ sabhai-
yōm i-ñilattukku pugunda
15 kuttukkāl tirttu-kuḍuppōmānōm tirttu-[kkuḍōmāgil ku]ttukkāl pugunda(pugunda)-
pōdu muṛpaṭṭa panm[ā]-
16 hēśvararē nilaikkaḷam-uḷḷiṭṭa tān [vēṇḍu] kō[viṇu]kku -kkāṇam
sabhaiyaiy-āgavum tanitt-āgavum daṇ-
17 ḍam-iḍa oṭṭi i-ñilam pattu=chcheyum viṛṛu vilaiy-āvaṇam śeydu kuḍuttōm
Tiruttavatturai-[Ma]hādēvarkku Maṇa-
18 ṛkkāl sabhaiyōm [||*] idu pan-Māhēśvarar nārppatt-eṇṇāyiravarum rakshai ||| ||| |||

TRANSLATION.

Hail ! Prosperity ! In the 13th year of (the reign of) king Rājakēsarivarman, Naṅgai-Varaṇa-perumāṇār, the illustrious uterine sister of the Chōḷa king (*Śōlapperumāṇaḍigal*), gave 30 (*kaḷaṇḷu* of) gold for burning a perpetual lamp daily with (one) *uri* of ghee as long as the sun and the moon last, in the temple of *Īśvara-bhaṭṭāraka* at Tiruttavatturai. The (members of the) assembly of *Maṇaṛkāḷ*, a *brahmadēya* on the western portion of *Kalāra-kku(kū)ṛṛam* which was a sub-division of *Vaḍakarai-Maḷa-nāḍu* received these thirty *kaḷaṇḷu* of gold. The following are the lands which they sold for the 30 *kaḷaṇḷu* of gold to the temple of *Perumāṇaḍigal* at Tiruttavatturai for (burning) a sacred lamp :—

Four *mā* and (one) *kāṇi* of our land, situated to the east of the mound called *Maṇamutti-ttiḍal*; three *mā* and (one) *kāṇi* (of land) to the north of the *vet̥tappēru* in *Śīrugavūr* ; two *mā* of land to the east of the canal at the boundary of *Śīrugavūr* ; and half a *mā* (of land) to the east of the *vet̥tappēru* which we ourselves presented to *Talaivāyan*¹—in all, half a *vēli* comprised in four *taḍi*. Having received the 30 *kaḷaṇḷu* of gold, we, (the members of) *Maṇaṛkāḷ*, sold these ten *śey* of land, free from taxes, and drew up the sale-deed expressing therein that all kinds of *vet̥ti*, *irai*, *echchōru*, *vediṇai* and other (taxes) inclusive of *śennīrvet̥ti*, shall not be paid (on these lands), and conveyed the same to (the temple of) the *Mahādēva* at Tiruttavatturai. If there arises any trouble in respect of these lands, we bind ourselves to rectify the same. In case of our failure to rectify, we agree to pay, either as a body or individually, a fine of *kāṇam* of gold to the royal officers inclusive of the *nilaikkaḷam* as may be desired by the several *Māhēśvaras* existing at the time of default. Thus (agreeing), we, (the members of) the assembly of *Maṇaṛkāḷ*, sold the said ten *śey* of land, drew up the sale-deed and handed over (possession) to (the temple of) the *Mahādēva* at Tiruttavatturai. This (charity) shall be under the protection of all the *Māhēśvaras* (viz.) the Forty-Eight Thousand.

No. 4.—A SUNGA INSCRIPTION FROM AYODHYA.

By RAI BAHADUR DAYA RAM SAHNI, M.A.

This inscription was first brought to the notice of scholars by Babu Jagannath Das Ratnakara of Ayōdhyā. It is inscribed on a flat stone slab at the foot of the eastern entrance of the *Samādhi* of Bābā Sangat Bakhsh, which is reputed to have been built in the time of Nawāb Shujā'-ud-daula. This shrine with the connected buildings is situated in the western portion of a large walled enclosure known as Rānopāli, about a mile distant from the town of Ayōdhyā on the road leading to Fyzābād.

¹ May also mean 'for the head-slucce'.

The inscription consists of two lines. The first line appears to be complete, though it is difficult to say that the portion of the slab hidden under the sill of the doorframe does not contain one or more lines. Of the second line, the left hand portion is completely effaced, though some slight traces that have survived make it certain that the whole of this portion was originally inscribed. The characters are Brāhmī which show considerable resemblance with the inscriptions of the Northern Kshatrapas and some archaic votive inscriptions from Mathurā. The characteristics of this type are discussed in Bühler's *Indian Palaeography*¹ and these are the equalization of all the upper verticals except in *la*, the constant use of the *serif* and of the angular forms of *gha*, *ja*, *pa*, *pha*, *ma*, *la*, *sha* and *ha*. Another peculiarity of the Brāhmī script of this period is the slightly bent base line of the letter *na*. The inscription under discussion exhibits all these peculiarities in a marked degree and should be classed with those mentioned above. The document is written in correct Sanskrit and is thus one of the few early inscriptions recorded in that language. The only grammatical mistake noticed in it is the use of *Dharmarājñā* in place of *Dharmarājēna*.

The document has already been dealt with by several scholars, the first of whom was the discoverer, Babu Jagannath Das Ratnākara² himself. This article is written in Hindi and is accompanied by an inked impression of the inscription together with an improved hand-copy prepared by Mr. Ratnakara himself. Mahāmahōpādhyāya Pandit Gaurishankar Hirachand Ojha of the Rājputāna Museum, Ajmēr, dealt with the document in the same volume of the *Nāgarī-Prachārīnī Patrikā*,³ as well as in his report of that Museum for the year ending 31st March 1924, pp. 1-2. Mr. K. P. Jayaswal has devoted three articles to the subject.⁴ Other scholars, who have dealt with this inscription, are Mr. N. K. Bhattasali,⁵ Dr. A. Bannerji-Śāstri⁶ and Mr. N. G. Majumdar.⁷ The inscription has, however, not yet been dealt with in any of the official publications of the Archaeological Department and my object in editing it in this journal is to bring together the various views expressed by scholars on this important inscription and to record my own impressions of the same.

The inscription records the erection of a shrine or other memorial in honour of Phalgudēva, the father of the Dharmarāja Dhana(°dēva, °bhūti, etc.), Lord of Kōsala, son of Kauśikī, the sixth of the *Sēnāpati* Pushyamitra, who had performed the *Āśvamēdha* twice.

The inscription is important for more reasons than one. It is the first inscription on stone or metal yet discovered which mentions the name of Pushyamitra, the celebrated founder of the Śunga dynasty. Hitherto he was only known from literary sources, e.g., the *Divyāvadāna* (XXIX), Patañjali's *Mahābhāṣya* (III-2-123), where reference is made to a sacrifice performed by him, some of the *Purāṇas*, Kālidāsa's drama, the *Mālavikāgnimitra*, etc. The passages referring to the Śunga dynasty in the *Vishṇu* and the *Bhāgavata Purāṇas* are quoted in parallel columns in Pargiter's *The Purāṇa Text of the Dynasties of the Kali Age*, pp. 30-33. From the extract from the former we learn that the dynasty was founded by the General Pushyamitra after he had slain the last Maurya king Bṛhadratha. His son was Agnimitra, who was succeeded by Vasujyēṣṭha. The latter's son was Vasumitra and his son Andhraka. He was succeeded by Pulindaka and the

¹ *Ind. Ant.*, Vol. XXXIII, 1904, Appendix, p. 40.

² *Nāgarī-Prachārīnī-Patrikā*, Vol. V, pt. 1, pp. 99-104.

³ *Ibid.*, pp. 201, *seq.*

⁴ *Modern Review*, October 1924, pp. 430-32, *J. B. & O. R. S.*, 1924, Vol. X, pp. 202-208, and *ibid.*, Vol. XIII, pp. 247-49. [Here Mr. Jayaswal has given good facsimiles of this inscription.—Ed.]

⁵ *Modern Review*, February 1925, p. 202.

⁶ *Ibid.*, January 1925, pp. 59-60.

⁷ *Annals of the Bhandarkar Institute*, Vol. VII, pts. I and II, pp. 160-163.

latter by Yōmēgha. He was followed by Vajramitra. He was followed by Samābhāga. The latter's son was Dēvabhūmi.

Kālidāsa's drama mentions three of these kings, *i.e.*, the founder, his son Agnimitra and the latter's son Vasumitra and further informs us that Pushyamitra instituted a *Rājasūya* sacrifice and appointed Vasumitra as the guardian of the sacrificial horse, which in accordance with religious custom was to wander at will for a year and that the horse was seized by the cavalry of the Yavanas, whom Vasumitra successfully defeated and brought the horse back to his grandfather's sacrifice. The *Rājasūya* sacrifice was performed by universal monarchs and the sacrifice of this name mentioned in the drama of Kālidāsa may have been the one performed by Pushyamitra on the occasion of his coronation. The Ayōdhyā inscription, however, records the performance of two *Aśvamedha* sacrifices by Pushyamitra. It is at present not known what necessitated the institution of the second sacrifice by him. It is to the credit of Pushyamitra that he revived this sacrifice which had long been in abeyance owing to Aśōka's commandments prohibiting the immolation of animals even for sacrifices. Mr. Jayaswal¹ thinks that the *Aśvamedha* sacrifice mentioned in an inscription discovered at Nagari also referred to Pushyamitra. It is true that such an inscription was found by Dr. D. R. Bhandarkar when he was engaged in his excavations at Nagari.² It has, however, been found by Rai Bahadur Gaurishankar H. Ojha³ to be only a fragment of the Ghōsūṇḍī inscription and to supply the missing portion of the first line of that record. Thus restored, the epigraph shows that the son of Gajāyana and Pārāsari mentioned in it was one Sarvatāta, who had performed a horse-sacrifice, but makes no mention of Pushyamitra.

The Ayōdhyā inscription is also interesting as it establishes the fact that the correct name of the founder of the Śuṅga dynasty was Pushyamitra, not Pushpamitra as found in some of the Sanskrit works. Dr. Bühler had already been led to this conclusion⁴ by the form Pūsamitta which he found in certain Jaina Prakrit *gāthās*, but epigraphical evidence was wanting.

The interpretation of this short record is rendered difficult by the uncertainty about the exact significance of the words *Pushyamitrasya shashṭhēna* and I am afraid the difficulty will not be solved until another inscription of the Śuṅga dynasty containing the genealogy of these kings comes to light. I propose here to recapitulate what has been said by the previous writers before I record my views on the point. Pandit Ratnakara rendered these words as the sixth descendant, brother or son of Pushyamitra and as with the last alternative, Phalgudēva would become identical with Pushyamitra, he thought he could overcome the difficulty by supplying a word like *pūjyasya* between the words *pituh* and *Phalgudēvasya* and interpret the expression as "in honour of Phalgudēva, a teacher or deity of his father." Rai Bahadur Gaurishankar Hirachand Ojha favoured the meaning "sixth in descent from Pushyamitra," while Mr. Jayaswal preferred to interpret the expression as the sixth brother of Pushyamitra, making Phalgudēva the father of Pushyamitra. This view was endorsed by Dr. A. Banerji-Śāstri, who rejected "the descent theory" for the reason that if Dhana[dēva] was sixth in descent from Pushyamitra and evidently proud of it, his name would have ended with the word *mītra*. This, as Mr. N. K. Bhattasali⁵ has shown, is no real obstacle as the names of several of the kings of the Śuṅga dynasty as given in the *Purāṇas* and found on their coins have different endings. Dr. Śāstri also emphasises the fact that in the *Smṛitis* 'descent' is signified by the termination of the 5th case, not the 6th as

¹ *Modern Review*, October 1924, p. 432.

² *The Archaeological Remains and Excavations at Nagari* (Memoirs of the Arch. Surv. Ind. No. 4) p. 120.

³ *Annual Report, Archaeological Survey of India*, 1926-27, p. 204.

⁴ *Ind. Ant.*, Vol. II, p. 362.

⁵ *Modern Review*, January to June 1925, p. 202.

is the case in the expression under discussion. Mr. N. G. Majumdar has hunted up a parallel expression in verse 88 of the 16th *Sarga* of the *Raghuvaṃśa*. The expression in question is *pañchamaṃ Takshakasya*, which is interpreted by three commentators as meaning "grandson of grandson of Takshaka." Mr. Majumdar therefore sees no difficulty in interpreting *Pushyamitrasya shash-ṭhaḥ* as "sixth in descent from Pushyamitra." In his third article¹ on this inscription, however, Mr. Jayaswal points out that the example from the *Raghuvaṃśa* referred to above is actually interpreted by Mallinātha as meaning the fifth son of Takshaka. 'The sixth of Pushyamitra' in the Ayōdhyā inscription should therefore mean the sixth son of Pushyamitra. As, however, this interpretation would make Phalgudēva identical with Pushyamitra, he proposes to read *Dharmarājñā* in the 2nd line as *Dharmarājñī*, and to compound it with the following word *pituḥ*. He thus construes the record as meaning that Dhanadēva, the sixth son of Pushyamitra, erected a house in honour of Phalgudēva, the father of his lawful queen.

It will be seen from the above that the only parallel expression found by the ingenuity of Mr. Majumdar is capable of two divergent interpretations. As has been pointed out by Dr. Banerji-Śāstrī, the inscriptions so far known fail to throw light on the question and he is right in stating that the established custom in epigraphical records is either to name the generations in succession or not at all and that it is not usual to mention a distant stage by omitting the intervening ones. One such example I have indeed secured in verse 44 of the *Vaṃśāvalī* of the Chambā rājās,² where we find the words "Mēruvarman was the 10th from Jayastambha" after the nine intervening ancestors of Mēruvarman have been duly referred to in direct succession. Even here, however, the *vibhakti* employed is the fifth, not the sixth or possessive case. An example of this kind with the sixth case ending occurs in the *Raghuvaṃśa*, *Sarga* 6, verse 29 :—

त्वमेव कल्याणि तयोस्तृतीया

"Thou alone, fortunate lady, art fit to be their third."

Sunandā, the attendant of Indumatī, while narrating the achievements of the prince of the Aṅgas observes that the goddesses Śrī and Sarasvatī, though naturally hostile to each other, together reside in him in peace, thus indicating the propriety of her union with him. It will be observed that though the grammatical construction in this case is the same as in the doubtful expression being discussed, the sense of descent is out of the question. Whether more exact parallels both in form and sense will or will not be found in the vast field of Sanskrit literature, I am unable to say. It seems, however, exceedingly difficult to disregard clear palaeographic evidence and to group this record with the other known documents of the early Śunga period. I would, therefore, with Pandit Ratnakara, supply a word like *purushēṇa* after *shashṭhēṇa* and translate "by the sixth descendant of Pushyamitra". It will be seen from the facsimile that only the first portion of the name of the chief who had this inscription engraved is preserved. Previous writers have restored it as Dhanadēva and Mr. N. G. Majumdar identifies him with a chief of that name whose coins have been found round about Ayōdhyā. Be the name, however, what it may, the inscription has established beyond doubt the fact that Ayōdhyā formed part of the Śunga Empire as late as the date of the inscription, which, on palaeographic grounds must be assigned to about the 1st century A.D.

TEXT.

Line 1. *Kōsal-ādhipēna dvir-aśvamēdha-yājīnaḥ sēnāpatēḥ Pushyamitrasya śnashṭhēṇa*
Kauśikī-putrēṇa Dhana
 Line 2. *Dharmarājñā pituḥ Phalgudēvasya kētanam kārtaṃ*

¹ J. B. & O. R. S., Vol. XIII. pp. 247-49.

² Vogel, *Antiquities of Chamba State*, p. 85 :—

मेरुवर्मा जयसम्भादशमोऽभूत्.

[The chief point of interest in the inscription is the use of the genitive case in the expression *Pushyamitrasya shashthēna*. According to Pāṇini (तस्य पूरणे ङट्, नाम्नादसंख्यादेर्मट् and षट्कृतिकतिपयचतुरां युक्, *Ashṭādhyāyī*, V. ii. 48, 49 and 51), the suffix *ṇaṭ* (with the augments *maṭ* and *thuk*) is used in the sense of *pūraṇa*, i.e., येन संख्या संख्यान् पूर्यते संपद्यते स तस्याः पूरणः (*Kāśikā* on the *Ashṭādhyāyī*, V. ii. 48), 'that with which a number is completed'. So षष्ठः means षष्ठां पूरणः and पञ्चमः, पञ्चमां पूरणः, and so on. In other words, this suffix does not signify any order of descent or kinship and षष्ठेन of the inscription, taken by itself, would simply mean 'by the sixth.' The genitive case, however, would show the *sambandha* or relationship which this person had with Pushyamitra, for that is one of the chief functions of this *vibhakti*. To express 'order of descent' the ablative case should be employed, as a reference to the comments on अन्यारादितरते दिक्शब्दाश्चत्तरपदाजाहियुक्ते (*Ashṭādhyāyī*, II. iii. 29) would show. We generally say अयमस्मात् पूर्वः, अयमस्मादुत्तरः. This will be made clearer by the following quotation given in the *Śabdakalpādruma* under the word *sapinḍa* :—

“ पञ्चमात् सप्तमादूर्ध्वं मादृतः पितृतः क्रमात् ।

सपिण्डता निर्वर्तेत सर्ववर्णेष्वयं विधिः ॥ ” इत्युदाहृतचतुर्नारदवचनम् ॥

That *pañchamī* and not *shashthī* is generally used in such cases is further shown by the *Viṣṇu-Purāṇa* (*Amśa* III, *Adhyāya* X) and the *Garuḍa-Purāṇa* (*Adhyāya* LXV) as quoted in the *Śabdakalpādruma* under the word *vivāha*.

“ पञ्चमीं मातृपक्षाच्च पितृपक्षाच्च सप्तमीं ” and

“ पञ्चमात् सप्तमादूर्ध्वं मादृतः पितृतस्तथा ”

The *Yājñavalkya-Smṛiti*, *Āchār-ādhyāya*, (Trivandrum Sanskrit Series) would also support the said statement for it says :—

अरोगिणीं भ्रातृमतीमसमानवर्षिगोत्रजाम् ।

पञ्चमीं सप्तमीं चैव मादृतः पितृतस्तथा ॥ ५३॥

Therefore, if it was the order of descent which the author of the inscription had in view, he would have said *puṣyamitra* and not *puṣyamitray*. Consequently, it becomes evident that if any word is to be supplied, it should be *पुत्रेण* and not *पुत्रेण*. In consideration of these points, Mallinātha seems to be quite correct in taking *पञ्चमं तत्तकस्य* (*Raghu.*, XVI, 88) in the sense of 'the fifth son of Takshaka.' To get the meaning attributed to this passage by Chāritravardhana or by Dīnākaraṇḍa, we should expect the ablative case or the form *तत्तकात्* instead. We say *तस्य* but not *तस्मात्* पुत्रः, पौत्रः, प्रपौत्रो वा. Here, we should remember that the *Vāyu-Purāṇa* gives the reading *Pushyamitra-sūtās=ch=āshṭau* which strongly supports the interpretation of *षष्ठेन* as 'by the sixth son'. Besides, there is no inherent impossibility in the version given in this *Purāṇa* which would necessitate a summary rejection of it. Nor does it imply a sense which is wrong or impossible. Accordingly, the meaning 'by the sixth son of Pushyamitra' seems to be preferable.

As to the two new references given in this article one (*त्वमेव कल्याणि तयोस्तृतीया*) has no bearing whatsoever on the point under consideration. The other, which is a quotation from the *Vamśāvalī* of the rulers of Chambā, would only support the *prati-pakṣa* or the opposite view in that it uses *pañchamī* and not *shashthī* to express the order of descent of Mēruvarman.—Ed.]

No. 5.—PAHARPUR COPPER-PLATE GRANT OF THE [GUPTA] YEAR 159.

By K. N. DIKSHIT, M.A., CALCUTTA.

This **copper-plate** was found by me during the excavation of the great temple at **Pāhārpur** in the Badalgachi Thana of the Rājshāhi District in Bengal on the 29th November, 1927. It was recovered from the debris that had accumulated on the north-east side of the circumambulatory passage on the second terrace. From the circumstances of the discovery it was apparent that it could not have been originally buried or deposited under the floor of the passage, but was probably brought down from a higher level along with the bricks and mud. It is to be regretted that owing to the inadvertence of the labourer a hole has been made in the upper right hand corner of it and some letters in the three lines at the end of the first side and the first few lines of the second side have become obscure. The left hand margin has also been damaged at places, owing to which circumstance some of the letters written there have disappeared. The plate when dug out was covered with a thick coating of rust and verdigris but has subsequently been cleaned by chemical treatment and proves to have been fairly well preserved. It is rectangular¹ in shape, measures $7\frac{1}{4} \times 4\frac{1}{2}$ " and weighs 29 *tōlās*.

The **characters** in which the inscription under notice is written belong to the northern class of alphabets of the 5th century A.D. and closely resemble those of the grants 3 and 4 of the Dāmōdarpur² copper-plates of the time of Budhagupta. The formation of the medial *ā* by the addition of a stroke at the right lower end of the letters *ga*, *na*, *dha*, *ba*, *ra* and *śa* may be noted. The terminal *m* is written slightly below the top line as will be seen in *-ādhikaraṇam* (l. 1), *°chaturshṭayam* (l. 8), *Sam* (l. 20), and *phalam* (l. 24). The rare letter *ḍha* occurs in *āḍhavāpa* (l. 15). The forms of the conjunct letters *ksha* (as in *Dakṣiṇā*³ l. 1), *hma* (as in *Brāhma*⁴ ll. 3, 12 and 17) and *ñchchhya* (as in *apaviñchchhya* l. 20) are noteworthy. The numerical signs for 100, 50, 9, 7, 4 and 1 are to be found in ll. 19 to 21. The unusual form of 9 in l. 20, seems to be the prototype of the modern Bengali sign for that digit.

As regards **orthography**, the doubling of *k* before *ya* in *°dinārikkyā*⁵ (ll. 4 and 11), and before *r* in *°vikṛayō*⁶ (ll. 5 and 12), and *°kkramēṇ=ā*⁷ (ll. 5 and 17) requires notice. The consonants *k*, *n*, *d*, *m* and *y* are doubled after *r*, as in *°ārkkā*⁸ (l. 20), *°anuvārṇṇy=ā*⁹ (l. 3), *°nirddishṭā*¹⁰ (l. 18), *°sarmnā* (ll. 4 and 12), *°sarmmata* (l. 17), *°āryyā*¹¹ (l. 1), *°bhāryyā*¹² (ll. 4, 12 and 17), *°āchāryyā*¹³ (ll. 6 and 13) and in *dharmma*¹⁴ and *°dharmmēṇa* in lines 16 and 19. The *v* symbol is used for *b* in *°samudcya-vāhy-ā*¹⁵ (ll. 4 and 11) and *°vrahubhir*¹⁶ (l. 23).

The **language** of the inscription is Sanskrit. With the exception of the five imprecatory verses at the end, the whole record is in prose. The rules of *sandhi* have been very often violated, specially in respect of a *visarga* at the end of a word, as in *āyuktakaḥ āryyā*¹⁷ (l. 1), *°Gōhālūtaḥ arddha*¹⁸ (l. 9), *°vīrōdhaḥ guṇas*¹⁹ (l. 16), *kulyavāpa adhyarddhō*²⁰ (l. 19). *°Nātha-sarmmā etad*²¹ in ll. 4 and 12 is also wrong grammatically.

The document under examination registers the purchase of a fallow state land by a private individual for charitable purposes. The Dhānāidaha,²² the Dāmōdarpur,²³ the Farid-

¹ The left hand margin presents a broken appearance in the central portion. It is probable that, as in No. 3 of the Dāmōdarpur plates, there was a semi-circular projection at this place for attaching the seal.

² Above, Vol. XV, pp. 116 ff.

³ [See f.n. 5 on p. 61 below.—Ed.]

⁴ Above, Vol. XVII, pp. 345 ff.

⁵ Above, Vol. XV, pp. 113 ff.

pur¹ and the Ghugrāhāti² copper-plates also record similar transactions, the difference being that in the present case the rate at which one *kulyavāpa* of land was sold was 2 *dināras* whereas it was 3 in the case of the Dāmōdarpur grants and 4 in the case of the Faridpur ones. As Nos. 3 and 4 of the Dāmōdarpur plates are almost co-eval with the present plate, the difference in the rates mentioned in the two cases must be due to local causes. Probably the quality of the land available was inferior or there was an abundance of fallow land in the locality around Pāhārpur. It was, apparently, owing to such considerations that the 5 *drōṇavāpas* ($=\frac{5}{3}$ of a *kulyavāpa* approximately) were, as stated in No. 2 of the Dāmōdarpur plates, granted in lieu of a deposit of 2 *dināras*, when the rate was 3 *dināras* to a *kulyavāpa*³.

The grant under notice records that a Brāhmaṇa and his wife deposited 3 *dināras* or gold coins with the city council (*adhishṭhān-ādhiparāṇa*) to secure 1 *kulyavāpa* and 4 *drōṇavāpas* of land situated at 4 different villages all lying in the Dakṣiṇāmāsaka-*viḥi* and Nāgiraṭṭa-*maṇḍala* for the maintenance of worship with sandal, incense, flowers, lamps, etc., of the divine arhats at the *viḥāra* of Vaṭa-Gōhālī which was presided over by the disciples and the disciples of disciples of the Nigrantha preceptor (*Śramaṇ-āchārya*) Guhanandin, belonging to the Pāñcha-stūpa section (*nikāya*) of Benares. The donation of a Brāhmaṇa couple for the worship of Jinās, as recorded here, is noteworthy for it bespeaks of the religious toleration of the people of the period.

The Jaina *viḥāra* at Vaṭa-Gōhālī mentioned in this inscription, it would appear, must have stood at the original site of the present temple at Pāhārpur. The boundaries of the site are partly situated within the limits of the village of Gōālbbhiṭā to the north-west and the mound where the temple has been unearthed was pointed out to Dr. Buchanan Hamilton in 1807 as 'Gōālbbhiṭār Pāhār' (the eminence of Gōālbbhiṭā). The identification of Gōālbbhiṭā with the ancient Vaṭa-Gōhālī easily suggests itself as the stem Gōhālī is substantially identical with Gōāl. Few relics of the Jaina faith⁴ have come to light during the excavations at Pāhārpur, but numerous Brahmanical and Buddhist bas-reliefs and terra-cotta plaques, dating from the late Gupta times, have been discovered. In the ninth and the succeeding centuries of the Christian era, the Pāhārpur temple was known as the great Buddhist *viḥāra* of king Dharmapāla at Sōmapura, the latter place being recognised in the modern village of Ōmpur, a mile to the south of the mound.

Regarding the prevalence of Jainism in Bengal, the Chinese traveller Hiuen Tsiang, who visited the country of Puṇḍravardhana in the second quarter of the seventh century, records that⁵ "there are some 100 Dēva temples, where sectaries of different schools congregate. The naked Nirgranthas are the most numerous." This statement can now be corroborated by the evidence of the present document which speaks of a *viḥāra* presided over by a succession of Nigrantha monks, at least 150 years previous to the Chinese pilgrim's visit to the locality. In connection with the name Guhanandin it is worthy of note that the names of the Dīgambara Āchāryas of the third and fourth centuries of the Christian era, such as Yaśōnandin, Jayanandin, Kumāranandin, etc., as is shown by the lists, generally end in *nandin*. Puṇḍravardhana is mentioned as one of the seats of Jaina pontiffs, beginning with Gupti-Gupta or Viśākh-āchāryya, the disciple of Bhadrabāhu II and Guhanandin must have been one of them.

¹ *Ind. Ant.*, Vol. XXXIX, p. 193 and *J.A.S.B.*, N.S., Vol. VII, p. 475.

² Above, Vol. XVIII, p. 74.

³ [If the rate was 3 *dināras* to a *kulyavāpa*, the price of 5 *drōṇavāpas*, i.e., $\frac{5}{3}$ of a *kulyavāpa* must be 2 *dināras*.—Ed.]

⁴ [Does this fact support the author's view regarding the situation of the Jaina *viḥāra* at the site or suggest that the document under notice was brought from outside? Cf. his remark about the find in para. I, p. 59, above.—Ed.]

⁵ *Bal, Buddhist Records of the Western World*, Vol. II, p. 195.

The procedure followed in ancient Bengal¹ in respect of applications for the purchase and donation of land, as elaborated in the present case, is interesting. The intending donors approached the District Officer (*Āyuktaka*²) and the City Council (*Adhishṭhān-ādhikaraṇa*) headed by the venerable Mayor (*Nagara-śrēṣṭhīn*) and requested them for sale of land for charitable purposes at the prescribed rate. The Officer and the Council referred the case, in the first instance, to the committee of record-keepers consisting of one chief record-keeper and at least five other record-keepers.³ The latter after making necessary enquiries submitted their report with recommendation in favour of the transaction. The authorities thereupon realised the necessary amount from the applicants and intimated the elders and other householders belonging to the villages concerned to measure out the land and make it over to the applicants for the purpose in view.

The land measure adopted in this grant was based on the measures of grain as is the case in the Dāmōdarapur and other grants. The *kulyavāpa* denoted as much land as could be sown with a *kulya* measure of grain. A *kulya*, according to various ancient authorities, was equivalent to 8 *drōṇas*=32 *āḍhakas*=128 *prasthas*. Other land measures found in the present record are *drōṇavāpa* and *āḍhavāpa*.

The date of the grant as given in the inscription is Sam 159 Māgha di 7 and, apparently, refers to the Gupta era, which was in use in Bengal when the charter was issued. As such, it would fall in January 479, A.D. The mention of *Paramabhaṭṭāraka* in l. 16 can only be taken to refer to the reigning sovereign whose name is not mentioned. The Dāmōdarapur plates show that the kingdom of Budhagupta included the *bhukti* of Puṇḍravardhana at this period and it is not improbable that the unspecified reigning sovereign at the time of the issue of the copper-plate was Budhagupta.

Regarding the identification of the places mentioned in the plate, Puṇḍravardhana has been identified by General Cunningham⁴ with the extensive ruins known as 'Mahāsthān-gaṇh,' 8 miles north of the town of Bogra. Vata-Gōhālī, as stated above, may be the modern Gōālbhītā. I am unable to identify the other localities.

TEXT.⁵

Obverse.

- 1 Svasti [||*] Puṇḍra[varddha]nād=Āyuktakaḥ⁶ Āryya-nagara-śrēṣṭhī-purōgañ=ch=ādhiṣṭhān-ādhikaraṇam Dakṣiṇāmśaka-vithēya-Nāgiraṭṭa-
- 2 māṇḍalika-Palāsāṭṭa-pārsvika-Vaṭa-Gōhālī-Jambudēva-prāvēśya-Prishṭhima-pōttaka-Gōshā-ṭapuñjaka-Mūla-Nāgiraṭṭa-prāvēśya-
- 3 Nitva-Gōhālīshu Brāhmaṇ-ōttarān=Mahattar-ādi-kutumbinaḥ kuśalam-anuvarṇṇy-ānubōdhayanti [||*] Vijñāpayaty=asmān=Brāhmaṇa-Nātha-

¹ [It would be safer to say 'in this part of ancient Bengal' till it is proved by documentary evidence that this procedure was followed in the whole of ancient Bengal.—Ed.]

² [The Faridpur and the Dāmōdarapur grants mention more than one but less than five record-keepers. Faridpur grant No. 1 mentions only one record-keeper. Will it not be better to say 'the Committee which consisted of one chief record-keeper and very often other subordinate record-keepers'?—Ed.]

³ A. S. R., Vol. XV, pp. 104-117.

⁴ From the original plate.

⁵ [The plate correctly gives 'yuktakā āryya'. This reading would show that there were more *Āyuktakas* than two and that Nātha-śarmā and his wife Rāmi approached these *Āyuktakas* with their request for the land.—Ed.]

- 4 śarmmā ētad-bhāryyā Rāmī cha yushmākam=ih-ādhishtān-ādhikarāṇē
dvi-dinārikkyā-kulyavāpēna śāśvat-kāl-ōpabbhōgy-ākshaya-nivī-samudaya-vāhy¹-ā-
- 5 pratikara-khila-kshētra-vāstu-vikkrayō=nuvrittas=tad-arhatī=ānēn=aiva kkramēṇ=āvayōs=
sakāśād=dināra-trayam=upasaṅgrihy=āvayō[s*]=sva-puṇy-āpyā-
- 6 yanāya Vāṭa-Gōhālyām=av²=āsyān=Kāśika³-pañcha-stūpa-nikāyika⁴-nigrantha-Śramaṇ-
āchāryya-Guhanandi-śishya-prāśishy-ādhishtān-vihārē
- 7 Bhagavatām=Arhatām gandha-dhūpa-sumanō-dīp-ādy-arthan=tala-vāṭaka-nimittān=cha
a[ta*] ēva Vāṭa-Gōhālītō vāstu-drōṇavāpam=adhyarddhañ=Ja-
- 8 mbudēva-prāvēśya-Prishthima-pōttakē⁵ kshētraṁ drōṇavāpa-chatusṭayam Gōshā-
tapuñjād=drōṇavāpa-chatusṭayam Mūla-Nāgiraṭṭa-
- 9 prāvēśyā-Nitva-Gōhālitaḥ arddha-trika-drōṇavāpān=ity=ēvam=adhyarddham kshētra-
kulyavāpam⁶=akshaya-nivya dātum=i[ty=atra] yataḥ prathama-
- 10 Pustapāla-Divākaranandi-Pustapāla-Dhṛitvivishṇu-Virōchana-Rāmadāsa-Haridāsa-Śāśinandi-
shu prathamam⁷ [nā]m=avadhāraṇa⁸
- 11 y=āvadhṛitam asty=asmad-adhishtān-ādhikarāṇē dvi-dinārikkyā-kulyavāpēna śāśvat-
kāl-ōpabbhōgy-ākshaya-nivī-samu[daya-vā]hy⁹-āpratikara-
- 12 [khila*]-kshētra-vāstu-vikkrayō=nuvrittas=tad-yad=yushmām¹⁰=Brāhmaṇa-Nātha-śarmmā
ētad-bhāryyā Rāmī cha Palāśāṭṭa-pārśvika-Vāṭa-Gōhālīstha¹¹(?)-ya

Reverse.

- 13 ka-pañcha-stūpa-kula-nikāyika-āchāryya-nigrantha-Guhanandi-śishya-
prāśishy-ādhishtān-sad-vihārē Arhatām¹² gandha-[dhūp]-ādy-upayōgāya
- 14 [tala-v*]jāṭaka-nimittān=cha tatr=aiva Vāṭa-Gōhālyām vāstu-drōṇavāpam=adhyar-
ddham kshētrañ=Jambudēva-prāvēśya-Prishthima-pōttakē drōṇavāpa-chatusṭayam
- 15 Gōshātapuñjād=drōṇavāpa-chatusṭayam Mūla-Nāgiraṭṭa-prāvēśya-Nitva-Gōhālītō drō-
ṇavāpa-dvayam=ādhavā[pa-dva]y-ādhikam=ity=ēvam=a-

¹ Read 'bāhy-ā'.² Read 'av'.³ [Cf. *Navy-Āvakāśikāyām* of the Faridpur grants 2 and 3. *Ind. Ant.*, Vol. XXXIX, pp. 200 and 204.—Ed.]⁴ This expression is further characterised as *pañcha-stūpa-kula-nikāyika* in l. 13 of the text. The word *pañcha-nikāyika* is familiar to the students of Buddhism in the sense of 'one who knows the five Nikāyas'. In the present case, however, the word *stūpa* or *stūpa-kula* occurring between *pañcha* and *nikāyika* and its connection with a Jaina preceptor would seem to show that *Nikāya* must be taken here in the sense of a branch (*sākhā*) of the Jaina Āchāryas. *Pañcha-stūpa* may, in that case, be a place name from which a particular branch of the Jaina Āchāryas may have been known.⁵ † is redundant here.⁶ The engraver first wrote *drōṇavāpam*, but finding his mistake later, appears to have made an attempt at correction. The erased letters *drōṇa* are clearly visible below *kulya*.⁷ Some letters after this are lost.⁸ [The text of the Dāmōdarour plates would suggest that *avadhāraṇayā* was preceded by the names of the record-keepers which were put in the genitive plural.—Ed.]⁹ Read 'bāhy'.¹⁰ Read 'yushmām'.¹¹ [Compare the reading in l. 6 above.—Ed.]¹² Read *Arhatām*.

FIRST SIDE.

2 4 6 8 10 12

Handwritten text in Devanagari script, likely a copper plate grant. The text is arranged in horizontal lines, with some lines being longer than others. The script is a form of ancient Indian writing, specifically from the Gupta period. The text is written in a cursive style, with some characters being more stylized than others. The lines are numbered 2 through 12, indicating the sequence of the text. The text is written in a dark ink on a light-colored background.

ACTUAL SIZE.

SURVEY OF INDIA, CALCUTTA.

HIRANANDA SASTRI.

14 16 18 20 22 24

- 16 dhyarddham kshētra-kulyavāpam=prārtthayatē¹=tra na kaśchid=virōdhaḥ guṇas-
tu yat=parama-bhaṭṭāraka-pādānām=arth-ōpachayō dharinma-shaḍ-bhāg-āpyāya-
- 17 nañ=cha bhavati tad ēvañ-kriyatām=ity-anēn=āvadhāraṇā-kkramēṇ=ūsmād=Brā-
hmaṇa-Nātha-śarmmata ētad-bhāryyā-Rānīyās=cha dīnāra-tra-
- 18 yam-āyikṛity=aitābhyām vijñāpitaka-kram-ōpayōgāy=ōpari-nirddishṭa-grāma-Gōhālī-
kēshu tala-vāṭaka-vāstunā saha kshētram
- 19 kulyavāpa adhyarddhō=kshaya-nīvi-dharmmēṇa dattaḥ ku 1 drō 4 [*]
Tad=yushmābhiḥ sva-karmmaṇ-āvirōdhi-sthānē shaṭka-naḥ²air³-apa-
- 20 viñchchya⁴ dātavyō=kshaya-nīvi-dharmmēṇa cha śasvad=āchandr-ārka-tāraka-
kālam=anu-pālayitavya iti [*] Sam 100 50 9
- 21 Māgha di 7 [*] Uktañ=cha bhagavatā Vyāsēna [*] Sva-dattām para-
dattām vā yō harēta vasundharām [*]
- 22 sa viśṭhāyām krimir⁵=bhūtvā pitṛibhis-saha pachyatē [*] Shashṭi-varsha-
sahasrāṇi svarggē vasati bhūmidāḥ [*]
- 23 ākshēptā ch=ānumantā cha tāny=ēva narakē vasēt [*] Rājabhir=vvahu-
bhir⁶=dattā diyatē cha punaḥ punaḥ [*] yasya yasya
- 24 yadā bhūmi⁷ tasya tasya tadā phalam [*] Pūrvva-dattām dvijātibhyō
yatnād=raksha Yudhisṭhira [*] mahīm=mahimatām⁸ śrēṣṭha
- 25 dānāch=chhrēyō nupālanam [*] Vindhy ātavīshv=anambunshu⁹ śushka-kōṭara-
vāsina[ḥ *] kṛishn=āhinō¹⁰ hi jāyantē dēva-dāyam haranti yē [*]

Abstract of Contents.

Nātha-śarmma, a Brāhmaṇa and Rāmī, his wife, approach the District Officer¹⁰ and the City-Council headed by the Mayor (*Nagara-Śrēṣṭhī*) at Puṇḍravardhana with the request that in accordance with the procedure prevalent in the locality, they may be allowed to deposit three *dīnāras* in return for $1\frac{1}{2}$ *kulyavāpas* of land distributed among 4 different villages to be endowed in perpetuity for the maintenance of requisites of the worship of Arhats such as sandal, incense, flower,¹¹ lamps, etc., and for the construction of a resting place at the *vikāra* of the Jaina preceptor Guhanandī at Vaṭa-Gōhālī. The details of the lands required were:—Fields measuring 4, 4 and $2\frac{1}{2}$ *drōṇavāpas*, respectively, at the villages of Prishṭhima-pōttaka, Gōshāṭapuñjaka and Nīva-Gōhālī; home-stead land measuring $1\frac{1}{2}$ *drōṇavāpas* at Vaṭa-Gōhālī.

¹ [Read °prārtthayatē (°yētē).—Ed.]

² This expression can be compared with *ashtakā-navaka-nalābhyam* occurring in the Dāmōdarpur Plates. The present practice in parts of Bengal and Assam is to measure out the lands by *nilas* or reeds of a definite measurement in cubits, which differ in different localities. The *shatka*, *ashtaka* and *navaka* as referred to the *nilas* may therefore mean *nilas* of so many cubits (i.e., 6, 8 or 9).

³ [Dr. N. P. Chakravarti connects it with the Bengali word *hichhā* meaning to select or choose.—Ed.]

⁴ Read *krimir*.⁵ [But *krimir*, in is also allowed.—Ed.] ⁵ Read °bhakubhir.⁶ ⁶ Read *bhūmis*.

⁷ Read *matimatām*. [The reading *mahimatām* given in the plate is also correct.—Ed.]

⁸ Read *anambunshu*. [The plate correctly gives *anambunshu*.—Ed.] ⁹ Read =āhayā.

¹⁰ [See foot-note 5 on p. 61 above.—Ed.]

¹¹ The mention of flowers in the worship of the Arhats or Jinas indicates a point of difference between the practice of the old Nigrantha and the modern Digambara Jinas. The latter do not permit the use of flowers in as much as the insects likely to be present in the flowers may be destroyed thereby. The Svētāmbaras, however, have no objection to this practice.

The Council, in the first instance, consulted the Board of Record-Keepers presided over by Divākaranandin, who pointed out that there was no objection to the transaction, especially as, besides bringing some revenue to the treasury, it would entitle His Majesty to a sixth share of the religious merit accruing from the endowment. The Council, therefore, decided to accept the offer of the Brāhmaṇa couple and recorded the transfer of land.

The village elders of the respective villages at which the lands in question were situated, were then asked by the Council to mark out the boundaries of the lands thus granted and maintain them in perpetuity. The date was the 7th day of Māgha, in the [Gupta] year 159. The usual imprecatory verses follow.

No. 6.—KOTAVUMACHGI INSCRIPTION OF VIKRAMADITYA V.

By R. S. PANCHAMUKHI, M.A., OOTACAMUND.

Kōṭavumachgi is a village about 14 miles to the north-east of Gadag, the headquarters of the Gadag Taluk of the Dharwar District. The inscription, which is edited below, is engraved on a stone-tablet set up in front of the temple of Kalamēśvara which is standing there. The inscribed portion of the stone covers an area of 6' 2" by 1' 11" and is in a state of very good preservation. The inscription is neatly written in the **Kanarese script** of about the 11th century A.D. As regards **palaeography**, the chief points requiring notice are : (i) the lingual *ḍ* and *ḷ* are not clearly distinguished from the dental *d* ; compare for example *chhandav-aḷamkāra* (l. 25), *paṁneraḍu* (ll. 17, 29), *kūṇḍe* (l. 33), *paḍiyale* (l. 34), etc. ; (ii) the *u*-sign is indicated in three different ways, viz., (1) by a short hook at the bottom of the letter as in *Puligere* (l. 7), *paṁneraḍu* (ll. 17, 29), *ronḍu* (l. 36), etc., (2) by a mark with a downward bend by the side of the letter, as in *kuḍise kuḍe* (l. 13), *matṭar-aḷḍu* (ll. 18, 20), *kuruva-gey* (l. 28), etc., and (3) by a long right side stroke shooting from the bottom of the letter as in *Pushya śuddha* (l. 10), *nivēśanamgaḷu* (l. 46) ; (iii) the *e*-sign is given, sometimes, below the letter and resembles the *u*-sign, as in *Puligere* (l. 7) or in *belgoḍe* (l. 13). In one case it is represented by a horizontal stroke at the bottom of the letter, as in *Belvola* (l. 7) ; (iv) the final *m* is used in two places, i.e., in ll. 52 and 54 and is shaped like the secondary *ma*. Excepting the three imprecatory verses in Sanskrit, which come at the end, the record is written in **Kanarese prose** of the mediæval period. The words *ghaḷige* (l. 13) (which is a *tadbhava* of *ghaṭikā*) and *chhaṭṭa* (l. 24) (which is the *tadbhava* of *chhātra*) are of lexical interest ; so also, *kuruva-gey* (l. 28), *kūṇḍe* (l. 33), *paḍiyale* (l. 34) and *pārikhāya* (l. 41). In **orthography** the only point which requires mention here is the use of *r* and *ḷ* in place of *r* and *ḷ* as in *mūru* (l. 32) and *ḷu-kōṭi* (l. 48) respectively.

After *svasti*, the inscription opens with the usual prelude announcing that **Tribhuvana-malla Vikramādityadēva (V)** was reigning at the time and that **Belvola-Three Hundred** and **Puligere-Three Hundred** were administered by his subordinate *Daṇḍanāyaka Kēśavayya* whom it describes as ' the obtainer of the five great *śabdās*, the *Mahāsūmantādhipati*, the great and fierce commander-in-chief of armies and a favourite hero of his master ' (ll. 1-8). After giving the date (ll. 9-11) it records that *Daṇḍanāyaka Kēśavayya* granted, with the king's permission, the village **Ummachige** situated in **Nareyanagal-Twelve** to **Maunara Śrīdhara-Bhaṭṭa** of **Rōṇa** (ll. 9-13). The latter, in his turn, entrusted it to the 104 *Mahājanas* of the place specifying certain conditions to be observed by them. Lines 14-32 mention the income of certain estates under

different headings, namely, the maintenance of the temples and temple servants, the emoluments of *Bhaṭṭa* and *Akkariga*,¹ the stipends of students and the feeding of the *elḷkōṭi* ascetics.² Then follow the specifications of land and taxes levied on festive occasions such as *upanayana*, marriage, vedic sacrifices, *Bādube*,³ *Kārapuṇṇime* and *Dīpālige*, with a remark that they should be enjoyed by the *Ūroḍeya* (ll. 33-36). It further states (ll. 36-43) that fines on certain crimes it has specified, incomes derived from spoils, *daśavandha* (*daśabandha*) of escheat property of persons dying intestate and taxes on musical instruments such as *kāle* and *maddale* are to be utilised for repairs, etc., of the tank called *Dēyimgere* at Ummachige. Lines 43-46 contain the stipulation that the *Mahājanas* should protect the estates and maintain the gift even in adverse circumstances. The record was written by *Gōvinda-Bhaṭṭa* and engraved by *Chāvōja* (l. 54).

The inscription is dated the Śaka year 934, the 8th day of the bright half of the month Pushya, Paridhāvin *saṁvatsara*, Sunday and the Uttarāyana-saṁkrānti. These details do not appear to be quite regular. Except for the week day, the date corresponds, according to Swamikannu Pillai's *Ephemeris*, to Tuesday, 23rd December A.D. 1012.⁴

The inscription is important as it reveals the name of a new subordinate of Vikramāditya, viz., the *Mahāsāmantādhipati Kēsavayya* who was administering the two Six-Hundreds at the time of the grant. A record⁵ secured from Hosūr in the Gadag Taluk dated in A.D. 1029 refers to the *Mahāsāmantādhipati Kēsavarasa* in the passage "*Mahāsāmantādhipati mahāprachanḍa-daṇḍa-nāyakam śrīmat-Kēsavarasara tadagra-tanūjam* [||*] *Svasti samadhigata-paṁcha-mahāsabda mahā-sandhi-vigraha-ādhipati mahāprachanḍa-daṇḍanāyakam śrī-Vāvaṇarasara-ṇadarunūrumam* *nāluttam=ire* " as the father of *Vāvaṇarasa* who was then governing the two Six-Hundreds under Jayasimha, the younger brother and successor of Vikramāditya V. It is this *Vāvaṇarasa* who figures as a subordinate of Jayasimha II in the Hoṭṭūr inscription of Śaka 959 (A.D. 1037) and the Hulḡūr inscription of Śaka 960 (A.D. 1038).⁶ *Kēsavarasa* appears to have succeeded *Śōbhanarasa*⁷ in the administration of the two districts, sometime after A.D. 1004 when, according to a record⁸ of Yeliśirūr, the latter was still the governor. We know from the Nīlḡund inscription⁹ of Taila II dated in Śaka 904 that *Kannapa* was appointed as the governor of Beļvola-300 and Purigere-300 by Taila II and that he was succeeded by his brother

¹ *Akkariga* is made up of *Akkara* (Skt. *Akshara*) and *iga*, a *taddhita* termination indicating knowledge, according to the *Sūtra* तद्वैयचोते वा || 167 || of the *Karṇāṭaka-Bhāṣābhūṣaṇa* of Nāgavarma, p. 62 (Mysore Government edition). The word, therefore, means 'one who is well versed in (the science of) words.'

² *Elḷkōṭi* ascetics are probably the devotees of Śiva in the form of Mallāri who with an army of 'seven crores' destroyed the demons Malla and his brother. See for the story *Imp. Gaz.*, Vol. XVII, pp. 30-31.

³ *Bādube* is a Kanarese name for the new-moon day of Vaiśākha, *Kārapuṇṇime* for the full-moon day of Jyēṣṭha and *Dīpālige* for the new-moon day of Āśvina. For Kanarese names of all the full-moon days and new moon days of a year, see Dr. Fleet's note in *Ep. Ind.*, Vol. V, pp. 11 ff.

⁴ An inscription of Vikramāditya V bearing the Śaka date 93[5] is noticed in Appendix B (No. 722) of the *Madras Epigraphical Report* for 1923. But the reading of the last figure is doubtful. (see *ibid* p. 101). A record from Karaḍihalli in the Mysore State (*Ep. Carn.*, Vol. VII, Sk. 287) belonging to the same king is dated clearly Śaka 933, Paridhāvin, Pushya, Śu. 13, Monday (=Monday, the 29th December A.D. 1012) which may be regarded as his latest date known so far. The present inscription is thus six days earlier than the latest epigraph of Vikramāditya V.

⁵ No. 110 of the Bombay Karnatak collection for 1926-27.

⁶ See above Vol. XVI, pp. 75 ff. and pp. 332 ff. In the published text of the former record, the name appears to have been wrongly read as *Chāvānarasa*.

⁷ The relationship between *Śōbhanarasa* and *Kēsavarasa* is not disclosed by inscriptions.

⁸ No. 62 of the Bombay Karnatak collection for 1926-27.

⁹ *Ep. Ind.*, Vol. IV, pp. 206 ff.

Śōbhanarasa in the government of those provinces in about A.D. 982. It is likely that Taila II, after overthrowing the Gaṅga chief Pañchaladēva shortly after A.D. 975, invested Kannapa¹ with the governorship of the two districts as stated in the above record. Thus we get, after the downfall of the Gaṅgas, a succession of rulers of the Belvola and Purigere provinces in the 10th and 11th centuries of the Christian era, namely Kannapa, Śōbhanarasa, Kōśavarasa and Vāvaṇarasa.

From this inscription it can be gathered that Ummachige was a great educational centre in the beginning of the 11th century A.D. and maintained a college, with a free hostel attached to it, where instruction was imparted in several sciences. It allots a share of fifty *mattar* with one house-site to the *Bhaṭṭa* who could expound *Nyāsa* and *Prabhākara* and twenty-five *mattar* to the pupils studying those subjects, while twenty-five *mattar* and one house-site only are given to the *Akkariḡa* (man of letters) named Nāgadēsiga who could teach and compose works on mathematics, astronomy, prosody, poetics, etc., and was well versed in grammar. It is enjoined that this Nāgadēsiga should teach his pupils feeding them once a day and supplying them with a cloth every year. These two *vṛttis* are respectively called *bhaṭṭa-vṛtti* and *akkariga-vṛtti* in the record. It is interesting to note that the *Bhaṭṭa* and his pupils are the recipients of separate shares in the village whereas the *Akkariḡa*, who enjoys a lesser income, has also to feed and clothe his pupils. From this distinction in the two *vṛttis*, it is apparent that the curriculum of education was divided into two sections of which one was intended for specialisation in *śāstras* and the other meant for the general needs of a student. Among the subjects taught, *Nyāsa*² was, possibly, be a work on grammar; *Prabhākara* is a work of the Mīmāṃsā school of philosophy started by Prabhākara.

The record is interesting from another point of view also. It gives us a peep into the system of village administration in ancient times in Karnāṭaka. From the details of the grant given in ll. 14-41, it seems that the proper conduct of worship in temples, the imparting of education, the feeding of ascetics, the supply of water to the village people and the punishment of criminals were the chief items which claimed the immediate attention of the administrator. Regarding the last item, it is worthy of note that the inscription mentions a number of crimes taken cognisance of by the authorities and the penalties imposed in each case.³ They are: (1) for abusing one another (*baḡḡade*), 2 *paṇas*; (2) for assault (*baḡḡade*), 12 *paṇas*; (3) for drawing out the dagger (*surige-giḡade*), 3 *gadyāṇas*—a *māṇi*⁴ who ascends the processional *maṇḍapa* with weapons is excepted. (4) for stabbing (*iridaḡe*), 12 *gadyāṇas* and (5) for a bachelor (*māṇi*) committing adultery (*māṇi sūle-gēdaḡe*), 3 *gadyāṇas*. It is stated that the fines thus realised together with the spoils (*karavē*), one-tenth (*daśavaṇḡha*)⁵ of the ešcheat property (*aputrika-dravya*)⁶ and taxes on musical instruments must be utilised for the upkeep and repairs of the tank called Dēyimgere mentioned above. The Ūroḡeya, i.e., the village officer was authorised to change the amount

¹ Hebhal inscription of A.D. 975 mentions a certain Kannapayya as the *Pergade* of Bhujagabbarasi, the grandmother of the Gaṅga chief Mārasimha II. See *Ep. Ind.*, Vol. IV, pp. 350 ff.

² References to *Nyāsa* in Sanskrit literature show that it must be a grammatical work. See *Catalogus Catalogorum* by T. Aufrecht, p. 312 and *Ind. Ant.*, Vols. XLIV, p. 275 and XLV, p. 25 and Māgha, II, 122.

³ See *Historical Sketches of the Ancient Dekhan* by K. V. S. Aiyer, pp. 326 ff. and *T. A. S.*, Vol. III, pp. 191 ff.

⁴ *Māṇi* is a *brahmachārin* who does service in the temple. See *S. I. I.*, Vol. III, part iii, p. 227. In line 35, however, it is used in the sense of *upanyāyana*.

⁵ *Daśavaṇḡha* means a tenth part; it does not seem to have been used here in its technical sense of land or of revenue granted as a compensation for the construction, repairs, etc., of a tank, well or channel. See *Ind. Ant.*, Vol. XXX, p. 107, note 12 and page 267, note 2.

⁶ According to *Manusmṛiti*, IX 182, *aputrika-dravya* was the state property. In this case, however, it belonged to Śrīdhara-Bhaṭṭa who set apart one-tenth of it for the purpose specified.


[illegible]

28 28
28 28
30 30
32 32
34 34
36 36
38 38
40 40
42 42
44 44
46 46
48 48
50 50
52 52
54 54

of fines in respect of certain crimes according to the caste of the offender. This is in keeping with the laws laid down in the *Dharmaśāstra*.¹

Of the places mentioned in the inscription, **Rōṇa** is the modern Ron, the headquarters of the Ron Taluk in the Dharwar District. **Nareyaṁgal** which was the chief town of **Nareyaṁgal-12**, a sub-division in the **Beļvola-300** province, is the modern Naregal situated at a distance of 10 miles from Ron. **Ummachige** is evidently identical with Kōṭavumachgi where the record was found.

TEXT²

- 1  Svasti [*] Samasta-bhuvan-āśraya-Śrī-Prithvī-vallabha-mahārī-
- 2 jādhirāja-paramēśvara-paramabhaṭṭārakaṁ Satyāśraya-ku-
- 3 ḷa-tiḷakaṁ Chāḷukyābharanam śrīmat-Tribhuvanamalla-Vikra-
- 4 māḍityadēvara rājyam=uttarōttar-ābhivṛiddhige salutta-
- 5 m-ire [*] Samadhigata-paṁcha-mahāśabda mahāsāmantādhipati
- 6 mahā-prachaṇḍa-daṇḍanāyakam pati-mechche-gaṇḍaṁ śrīmad-Daṇḍanā-
- 7 yakaṁ Kēśavayyaṁgaḷ-Beļvola-mūnūgaṁ Puligere-mūnūruvaṁ su-
- 8 kha-saṁkathā-vinōdadin-āḷuttam-iḷdu [*] Śrīmat-Tribhuvanamalla-
- 9 dēvaram prā[r]tthisi Rōṇa Maunara Śrīdharabhaṭṭargge Śāka-varsha 934-
- neya
- 10 Paridhāvi-saṁvatsarada Pūshya śuddha aṣṭamī Ādityavāra vuttarā-
- 11 yaṇa saṁkrāntiyandu Nareyaṁgal=Panneraḍaḷagaṇa Ummachi-
- 12 [ge]yaṁ sarvavāhyamāntara-siddhiyāgi sarvvanamaśyav-aggrahāraṁ mā-
- 13 ḍi śāsanaṁ belgoḍe ghaḷige verasu paḍedu kuḍise kuḍe paḍed-āyū-
- 14 ran=ā-Śrīdharabhaṭṭar nūṇaḷvar=mmahājanake bharaṇaṁ-geydu tavagaṁ
- 15 mahājanakkaṁ prajegaṁ māḍida vyavastheyum³ dharmma-brayad=upabiyada
- 16 mānyada bhūmiya nivēśanada pramāṇamu[m=e]nt=ene Sōmēśvaradēvargge ma-
- 17 ttar=āru Bhāgiyabbēśvarakke mattar=ppanneraḍu eḷkōṭi-tapōdhanara
- 18 satrakke mattar=ppanneraḍu Āychagāvuṇḍana dēgulakke mattar=aydu maney=o-
- 19 ndu Ādityadēvargge mattar=aydu maney=ondu Beṭṭada-Bhagavatige
- 20 mattar=aydu maney=ondu Nārāyaṇadēvargge mattar=aydu maney=onda=
- 21 nt=ayvattu mattar=kkeyyuman=avaṇa nivēśanaṁgaḷuvaṁ Bendeyabhaṭṭārara
- saṁ-
- 22 tatiya brahmacharyyavulla naiśṭhika-tapōdhanar=āgiy=anubhavisuvar [*]
- 23 Mārakabbe-Bhaṭṭārige mattar=ppanneraḍu maney=ondu Nyāsaṁ Prabhākara-
- vuvaṁ
- 24 vakkhāṇisi guṇaśāsanadin=uṇba bhaṭṭa-vṛitti mattar=ayvattu maney=ondu
- chēhhaṭṭargge

¹ Compare *Manusmṛiti*, Chap. VIII, Vv. 267-268 and *Yājñavalkyaśmṛiti*, Chap. II, Vv. 220-224.

² From ink-impression.

³ The u-sign is indistinct and resembles the consonant y mark.

- 25 mattar=irppattaydu gaṇitam jōyisa-chchhanda-vaḷamkāravuvan=ābhaya.. veyuvam
ba.
- 26 reyalum bājisalum balla śabda-saṃskāravuḷlāta Nāgadēsīgargge nityasthitiy=o-
- 27 ndu poḷṭaḷ=āhāramum varishakk=ondu kappāḍavuvan=ikkiy=ōdisi guṇaśāsa-
- 28 nadin=āḷv=akkariga-vṛitti mattar=irppattaydu maney=ondu kuruva-gey=mattar=
ppanne-
- 29 raḍu maney=ondu gaḷamtige-gey=mattar=āru maney=ondu nāvida-gey=mattar=
em-
- 30 ṭu maney=ondu paṛekārgge mattar=ppannerāḍu maney=ondu guṇaśāsanadi-
- 31 n=āḷvara satrakke mattar=nnūru mane yeraḍ=antu dharmma-vrayakkam
vupabiyakkam
- 32 mattar=mūnūru Ūroḍeyargge mānyada key=mattar=innūru maneg-eṇḡa-
- 33 yyagala virppattaygay=niḷa[da] nivēsanam mūru¹ [śāśva]ta² sumkam gāṇa-veyilige
kūṇḍe mu-
- 34 ṭṭige paḍiyaḷe yajnadal=ondu gadyānam³ aydu paṇam madu-
veyal=era-
- 35 ḍu paṇam māṇiyal=ondu paṇam Bā[du]be Kāra-puṇami Dipāḷige mūru
parvvadoḷam
- 36 pratyēka vondu gadyāṇa imt=inituv=Ūroḍeyargge orbar=orbaram baydaḍe
daṇḍav=eraḍu
- 37 paṇam baḍidade pannerāḍu paṇam surige-giḷṭade mūru gadyāṇav=iṛidade
pannerāḍu gadyā-
- 38 nam jāti-bhēdav=aṛidu daṇḍavam viśēsham-māḷpa[r] māṇi sūḷe-gēdaḍe⁴
mūru gadyā-
- 39 nam prāyaschittam-golvandu mūru gadyānam māṇiy-āyudha berasu maṇḍa-
pa-
- 40 vēral=sallad=int-i-daṇḍadoḷam kava[r]ṭteyoḷav=aputrika-dravyada daśavandhodoḷam
puṭṭi-
- 41 da dravyamuvam kaḷe maddaḷeya paṇamum Dēyimgerege [[*] Idan=
upēkshisidātam
- 42 keṛeyan=ōḍeda pātakan=akkum pārīkhāyam modalāg=eḷla mūrggē . . ni-
- 43 vēsanam koṭṭa yikkuvavargge gāmuṇḍarggam kiḷjātiya mukkyarggam pra-
- 44 tyēkam maney=ond=āchandr-ārka-tārambaram mānyada satrada dharmma-
bra-
- 45 yad=upabiyad=ant=anitiv=eḍeya key=mattar=ainūruman=⁵alliy=alli-
- 46 ya nivēsanamgaḷuman=enitu dushkālav=ādaḍam mahājanam kōḍū-
- 47 qnvar=idakke tappidavar=Kurukshētradoḷam Vāraṇāśiyoḷam
- 48 eḷu-kōṭi Brāhmaṇaruvan=eḷu-kōṭi tapōdhanaruvan=eḷu-kōṭi

¹ The word *mūru* is written below the line.

² Read [śāśva]ta.

³ The writing here is completely effaced.

⁴ Read 'geydaḍe'.

⁵ Between *rai* and *nū* a superfluous letter which looks like *ḷu* is written and erased.

- 49 kavileyuvan=aḷida paṁcha-mahā-pātakan=akkum || Sāmānyō-
 50 yaṁ dharmma-sētumr(sētur)=nripāṇām kālē kālē pālanīyō bhavadbhiḥ |
 51 sarvvān=ētān=bhāginah pārtthivēndrān=bhūyō bhūyō yāchatē Rāmabhadraḥ ||
 52 Śva-dattām para-dattām vā yō harēta vasumdhārām [! *] shashṭi var-
 sha-sahasrāṇi viśṭāyām¹ jāva-
 53 tē krimiḥ || Bahubhir=vvasudhā bhuktā rājabhis=Sagar-ādibhiḥ [! *] yasya
 yasya yadā bhūmi-
 54 [s=ta]sya tasya tadā phalam || Gōvindabhaṭṭa[m] bareda Chāvōjam
 kaṇḍarisida maṅgaḷa mahā-śrī [! *]

Translation.

(Ll. 1-4) Hail ! While the reign of the glorious Tribhuvanamalla Vikramādityadēva, the refuge of the whole world, the lord of Fortune and Earth, the *Mahārājādhirāja*, the *Paramēśvara*, the *Paramabhaṭṭāraka*, the decoration of the race of Satyāśraya, an ornament of the Chālukyas, was increasing in prosperity,

(Ll. 5-8) while the chief of great feudatories, the august General who had attained the five *mahāśabdās*, a man of might causing pleasure to his master, the glorious *Daṇḍanāyaka Kēśavayya* was administering with enjoyment of pleasant conversation, the Belvola-Three Hundred and Puligeṇe-Three Hundred (*3 rovinces*),

(Ll. 8-13) (*Kēśavayya*), after requesting the glorious Tribhuvanamalladēva, made (*the village*) Ummachiḡe situated in Nareyaṁgal-Twelve into an *agrahāra* on *sarvanamasya* tenure along with full and complete rights of enjoyment of all the properties and obtaining it (*from him*) together with the royal charter, the white umbrella and *ghaḷige* (*i.e.*, an assembly hall)², caused it to be granted to Maunara Śrīdharabhaṭṭa of Rōṇa, on the eighth day of the bright half of Pushya, Sunday, the Uttarāyana-samkrānti, in the Śaka year 934 corresponding to the cyclic year Paridhāvi.

(Ll. 13-16) That Śrīdharabhaṭṭa, after thus getting it, entrusted the village to the hundred and four Mahājanas with the conditions of enjoyment by himself, the Mahājanas and the people (*of the village*) ; the extents of land and house-sites for meeting the expenses of charity, other auxiliary objects and for grants for services (*mānya*) are as follows :—

(Ll. 16-22) Six *mattar* to god Sōmēśvara, twelve *mattar* to (*the temple of*) Bhāgiyabbēśvara³; twelve *mattar* to the feeding house of *elkōḷi* ascetics ; five *mattar* and one house(-*site*) to Āychagā-vuṇḍa's temple ; five *mattar* and one house(-*site*) to Ādityadēva ; five *mattar* and one house(-*site*) to (*the goddess*) Beṭṭada-Bhagavati ; five *mattar* and one house(-*site*) to god Nārāyaṇa—these fifty *mattar* of land in all and the house-sites attached to them must be enjoyed by the bachelors of the family of Bendeyabhaṭṭā, following the course of the *naishṭhika*⁴ ascetics.

¹ Read *viśṭāyām*.

² See above Vols. XIII, p. 327n and XV, p. 93.

³ The temple was perhaps named after Bhāgalabbe, the mother of Vikramāditya V.

⁴ *Naishṭhika* is one who lives in the house of his preceptor as a *brahmachārin* throughout his life. He is described as follows in the *Garudapurāṇa* :—

नैष्ठिकी ब्रह्मचारी च ब्रह्मदाचार्यसन्निधौ । तदभावेऽस्य तनये परम्यां वैश्वामरिऽपि वा ॥

इमेन विधिना ईदं साधयेदिति द्वयः । ब्रह्मलीकमवाप्नोति न चेह आयते पुनः ॥

(Ll. 23-32) Twelve *mattar* and one house(-site) to the deity Mārakabbe Bhaṭāri, fifty *mattar* and one house(-site) towards *bhaṭṭa-vritti* to be enjoyed in return for performing the duties of expounding *Nyāsa* and *Prabhākara*, twenty-five *mattar* to the pupils, twenty-five *mattar* and one house(-site) as *akkariga-vritti* to Nāgadēsiga who was able to compose and expound (*the works on*) mathematics, astronomy, prosody, poetics and and who had a knowledge of sounds (*i.e.*, *Vyākaraṇa*), to be utilised for his daily requirements in virtue of his services of teaching his pupils, feeding them once a day and supplying (*them*) with a cloth every year; twelve *mattar* and one house(-site) for (*the supply of*) tender cocoanuts¹; six *mattar* and one house(-site) for (*the supply of*) vessels² for *abhishēka*; eight *mattar* of land and one house(-site) for barbers; twelve *mattar* and one house(-site) for drummers; (*one*) hundred *mattar* and two house(-sites) to the feeding-house of those that manage by *guṇaśāsana*.³ Thus in all three hundred *mattar* (*were set apart*) for charity and auxiliary expenses.

(Ll. 33-36) Two hundred *mattar* as *mānya* land and three house(-sites)—eight hands broad and twenty-five hands long each—to the *Uroḍeyya*. Moreover, the *Uroḍeyya* (*shall get these following*) taxes permanently :—a *kūṇḍe* for the open space of an oil-press; the reaper of a door-frame for every set of wooden materials (*for building purposes*)⁴; one *gadyāṇa* for a vedic sacrifice; five *paṇas* for, two *paṇas* for a marriage; one *paṇa* on the occasion of *upanayana*, one *gadyāṇa* severally on the three *pūrvas* of *Bālube*, *Kārapuṇiṇe* and *Dipīḷige*.

(Ll. 36-43) The incomes accruing from the following fines, *viz.*, two *paṇas* for abusing one another, twelve *paṇas* for beating; three *gadyāṇas* for drawing out the dagger, twelve *gadyāṇas* for stabbing—(*they*) may change (*the amount of*) fine considering the distinction of caste—three *gadyāṇas*, in case a bachelor commits adultery; three *gadyāṇas* on the occasion of purification ceremony—except when a *māṇi* gets up a processional *maṇḍapa* with weapons⁵; that obtained as spoils (*after a raid*), one-tenth (*daśavandha*) of the escheat property of persons dying intestate and the taxes on (*musical instruments*) *kāḷe* and *maddaḷe* (*the drum*); all these shall go to (*the tank called*) *Dēyīmgerē*. He who neglects this shall incur the sin of breaking the tank. A house-site including *pārikhāya*, etc., (*was set apart*). Those that keep a cowpen (*koṭṭa*), the *gāmuṇḍas* and the chief men of the low caste (*must get*) one house(-site) each.

(Ll. 43-46) The five hundred *mattar* (*of land*) and the respective sites (*attached to them*), (*granted*) as *mānya*, and for the purposes of feeding house, charity and auxiliary gifts, the *Mahājanas* shall protect and cause to be enjoyed as long as the moon, the sun and the stars (*exist*), however adverse the times may be.

(Ll. 46-48) Those that fail (*to carry this out*) shall incur the five great sins consequent upon the killing at Kurukshētra and Vāraṇāsi, of seven crores of Brahmins, seven crores of ascetics and seven crores of tawny cows.

(Ll. 48-53) Three imprecatory verses.

(L. 54) Gōvindabhaṭṭa wrote (*this*); and Chāvōja engraved. (*May there be*) fortune and great prosperity.

¹ *Kuruva* seems to stand for *kurubs* which means a tender cocoanut. (See Kittel's *Kanarese Dictionary*, p. 446.)

² The word used here is *gaṇantige* which is a *tadbhava* of the Sanskrit word *galantikā*. It means a small water-jar with a hole in the bottom from which the water drops upon a *līṅga*.

³ The exact significance of this word is not clear.

⁴ For the meaning of the word *muffu*, see Kittel's *Kanarese Dictionary*, p. 1263.

⁵ This parenthetical clause evidently provides an exception to the fine stated above for drawing out the sword.

No. 7.—THE HATHIGUMPHA INSCRIPTION OF KHARAVELA.

By K. P. JAYASWAL, Esq., M.A., BARRISTER AT-LAW, PATNA, AND PROFESSOR R. D. BANERJI¹,
M.A., BENARES HINDU UNIVERSITY.

This inscription is incised partly in front and partly on the roof of the **Hāthīgumphā**, an artificial cave, on the southern face of the **Udayagiri**, a low range of hills situated about three miles from Bhuvaneśvar in the Purī district of Orissa. It was noticed for the first time by Stirling in 1825² and was published by Prinsep from an eye-copy prepared by Kittoe in 1837.³ In 1877 Cunningham published a tracing in the first volume of the *Corpus Inscriptionum Indicarum*.⁴ In 1880 the late Raja Rajendra Lala Mitra published another version of this inscription.⁵ About this time a cast of this inscription was prepared and taken to the Indian Museum, Calcutta. The first reliable version of the record was issued from the able pen of the late Dr. Bhagvanlal Indraji in 1885.⁶ In 1895 and 1898 the late Dr. Bühler proposed certain corrections.⁷ The first inked impression was taken by the late Dr. T. Bloch in 1906 and sent to Prof. Kielhorn from whom it passed on to the late Dr. J. F. Fleet, who published two short notes proposing certain corrections in the reading of the 16th line.⁸ In the same year Prof. Lüders of Berlin published a summary of this inscription.⁹ In 1913 RDB¹⁰, examined portions of this record at the request of KPJ., and in 1917 he prepared two inked impressions at the request of the late Dr. V. A. Smith and KPJ.,¹⁰ one of which was published in the *Journal of the Bihar and Orissa Research Society*,¹¹ and the second sent to Dr. F. W. Thomas, the then editor of this journal. Soon after the publication of the text, KPJ. went to the cave and prepared a revised text of his readings from the rock itself and published the same in 1918 in the *Journal of the Bihar and Orissa Research Society*.¹² Sir Edward Gait, the then Lieutenant-Governor of Bihār and Orissa, who was greatly interested in the decipherment of the inscription, arranged a deputation of RDB., the then Superintendent of the Western Circle of the Archæological Survey of India, to go with KPJ. and in 1919, we both examined the entire inscription on the spot. In the meantime a cast of the inscription was prepared at the suggestion of KPJ. by the Government of Bihār and Orissa. The order of Sir Edward Gait in this respect was executed by the late Mr. H. Panday of the Archæological Survey Department who had accompanied KPJ. formerly and had become familiar with the inscription and the problems connected with it. This cast is now preserved in the Patna Museum. It is as successful a copy as the present condition of the original allowed it to be. Two impressions on paper were also taken for the Patna Museum. With the help of these materials the study was carried on by KPJ. at Patna. In 1924 both of us again went over the corrections. In 1927 KPJ. published the results of his further studies in the *Journal of the Bihar and Orissa Research Society* with new plates prepared

¹ [I am sorry to record here his sad and untimely death which took place at Calcutta on 23rd May 1930. Scholars of Mr. R. D. Banerji's type it is difficult to replace.—Ed.].

² *Asiatic Researches*, Vol. XV, pp. 313 ff.

³ *J. A. S. B.*, Vol. VI, pp. 1075-91, pl. LVIII.

⁴ Pp. 27 f., 98-101, 132 ff., pl. XVII.

⁵ *Antiquities of Orissa*, Vol. II, pp. 16 ff.

⁶ *Actes du Sixième Congrès International des Orientalistes*, pt. III, section 2, pp. 162-177.

⁷ *Indian Studies*, No. III, p. 13=*Origin of Indian Brāhma Alphabet*, pp. 13 f.

⁸ *J. R. A. S.*, 1910, pp. 242 ff. and 824.

⁹ *Ante*, Vol. X, App., pp. 160-61, No. 1345.

¹⁰ [Author's initials].

¹¹ Vol. III, pl. I.

¹² Vol. IV pp. 364 ff.

from the paper impressions preserved in the Patna Museum.¹ In 1928 some further notes were published by him in the same journal.² We have again conjointly examined the cast and the impressions and effected a few important improvements in the reading and explanation as offered below. Amongst notable contributions on the problems connected with the inscription, we refer to the articles by Dr. Sten Konow³ and Dr. F. W. Thomas.⁴ We have to thank our friend Prof. Anant Sadashiv Altekar for the help he has rendered to us in preparing the notes for this edition.

The Hāthīgumphā appears to have been a natural cavern which was later on converted into a temple or residence. The roof consists of a huge boulder, and the inscription begins on the southern face but is continued up to a place where the stone has become actually the roof of the cave. The last eight or nine lines occur on a sloping surface where it is difficult either to read or copy them. Both of us had to recline partly on our backs to read the portion from the rock. Below the inscription the walls of the natural cavern have been chiselled straight and at places are as beautifully polished as those of the Barābar caves. Near the floor there are sundry rock-cut partitions which do not appear to have been regular walls as they do not go up to the roof. In the dressed and polished portion of the side or the wall of the cave there are a number of later inscriptions (of about the 10th or the 11th century A.D.) many of which contain proper names which are not of any historical interest.⁵ They prove, however, that the cave was visited by pilgrims up to the 10th century and therefore it must have been considered some sort of a sacred shrine. It seems reasonable to expect that the great Jaina king Khāravela inscribed the record of his reign at a place which was holy in his eyes. Is it impossible that this is the place where Mahāvīra had preached the Jaina religion in Kālīṅga, because this inscription proves that the place was included in Kālīṅga at that time and there is a distinct reference to the preaching of Jainism in its 14th line? The bed of the cave is full of sand in front and unless it is excavated its original form cannot be determined. Three stone pillars have lately been put up in front of the cave, to protect the inscription from the effects of the weather, under the orders of Government. The Hāthīgumphā stands at right angles to the Svargapurī and Mañchapurī on its left and the Sarpa cave on its right. There are several small and large excavations on the top of the boulder which forms the roof of the cave. As a whole the entire record has been very carefully inscribed. In two places only letters have been left out. In l. 14 the letter *ya* in *arahaṇate* was left out and incised between ll. 14 and 15, its position in l. 14 being indicated by a *kākapada*. Two other letters *sa* and *ha* (?) are to be found in the interspaces immediately after *ya* but cannot be connected with any word in l. 14.

As regards **orthography** the inscription presents very few peculiarities. Ligatures are carefully avoided and the only instances where we meet with them are *Kaṇha-beṇṇā-* (l. 4), *Bamhaṇṇam* (l. 9) and *-vinīśrito* (l. 17). In the majority of cases the nasals are replaced by *anusvāra* excepting the places where they are used either as initials or medials. The initial forms are to be seen in *-ṇāvakehi* (l. 14) and *ṇaninam* (l. 15) and the medial forms in *°raṇṇi°* (l. 15) and in the ligature in *Kaṇha-beṇṇā-* (l. 4). The use of the cerebral nasal is erratic and in the majority of cases the dental has been used but the cerebral is rather rare and is to be met with in *samputa-* (l. 2) and *guṇa-* (l. 17) only. With the exception of two cases all the sibilants are dental. These two cases are the cerebral in *-deṣa-* (l. 11) and the palatal in *-vinīśrito*

¹ Vol. XIII, pp. 221 ff.

² *Acta Orientalia*, Vol. I, pp. 12 ff.

³ *Annual Report of the Archaeological Survey of India*, 1922-23, p. 130.

⁴ Vol. XIV, pp. 150 ff.

⁵ *J. R. A. S.*, 1922, pp. 83 f.

(l. 17). The writing seems to have been done by three different hands, and it is possibly on this account that the forms of the characters sometimes differ. The first part of the inscription was written on a carefully dressed surface but after the 4th and 5th lines the surface was undressed; and towards the end of all the lines after the 5th there are numerous chisel-marks which make the decipherment extremely difficult.

The language of the inscription is Prakrit. The use of *ra*, the affix *o* at the end of the nominatives of masculine stems ending in *a*, and the absence of palatal *śa* show that it is not Māgadhī or any eastern dialect of it. Throughout the inscription the dental has practically replaced all other sibilants. The doubling of consonants, even when necessary, has been omitted. The cerebralisation of dentals is also to be seen, as in *prajñāśāpanam* (l. 3). There is also an attempt to approach classical Sanskrit in certain cases, e.g., *Māhāmeghavāhanena* (l. 1) and *vaṁ-dūpayati* (l. 12), etc. Throughout the record the liquifaction of consonants is absent. This would indicate that the record was composed by a man from Western India who wrote in a literary dialect. It is quite possible that the record was composed by a Jaina monk from Gujārāt or the Mahārāshtra who might have been brought into Kalinga by King Khāravela for the purpose mentioned in l. 16. The language of the record is a very near approach to the canonical Pali. But, as in Jaina Śaurasēnī, *tha* in this dialect becomes *dha*, cf. *padhame* (l. 3), *radha*° (l. 4), *vitadha* (l. 5), *Goradhagiri*- (l. 7), *Madhuraṁ* (l. 8), *Bharadhavasa*- (l. 10), *Utarāpadha*- (l. 11), but not in all cases, cf. *Pithumḍa*- (l. 11). The extraordinary form *chavuthe* (l. 5) is a graphic form of *chavūthe*, but Prakrit *chaṇ* becomes *cho* in *Choyathī* (l. 16) which is a later Prakrit form of *chaturhashṭī*. So also Sanskrit *tvṛitam* becomes *turiyam* (l. 16) instead of *turiam*. Perhaps *turitam* was the intermediate form but the change of *ta* into *ya* instead of *a* is exceptional.¹

The characters of the inscription show great variety. Among the vowels, the initial forms of *a*, *ā*, *i*, *e*, *o* are to be found in it. The medial *ā* is denoted by a perfectly horizontal line in many cases as well as by a slanting stroke, as in *paṭhāpayati* (l. 4) and *-samuthāpitāhi* (l. 15). The medial form of the long *i* shows two diverging slanting strokes, in *-sarīra*- (l. 2) and two converging curved strokes in *kīḍitā* (l. 2). Among consonants two different forms of *kha* are noticeable, *Khāravele*° (l. 1) and *lekha*° (l. 2) in which the triangle at the bottom is either present or absent. Two different forms of *ga* are present, the angular Maurya form as in *nagarim* (l. 5), and the broad-backed Kushāna form, as in *Kalimḡ-ā*° (l. 1). Three forms of *gha* are clear:—(1) the Maurya form with a circular bottom, (2) the transitional form in which the only side of the curve has turned into a right angle, cf. *-oghāṭitam* (l. 6), and (3) the complete second century form in which, though the length of the left-hand side vertical is not reduced, the lower part of the letter consists of two right angles instead of a curve. Two different forms of *ta* are to be found: the Maurya, as in *hita*-, *-ti-vasa*- (l. 6) and the later, as in *°pateye* (l. 6). In the case of *da* also we find two forms: the Maurya, as in *pāmdarasa*- (l. 2) and the later, as in *°ḍāti* (l. 9). Three different forms can be distinguished in the case of *pa* and *ma*:—(1) the Maurya form, as in *paṭhāpayati* and *pachhima*- (l. 4); (2) the transitional form, as in *-patinā* (l. 1), *-kāṛāpanāhi* (l. 5), *maṭuka*- (l. 7), *Madhuraṁ* (l. 8), etc.; (3) the later form with angles fully developed in the place of curves as in *kapa-rukhe* (l. 9), *apayāto* (l. 8), *-samāja*° (l. 5), and *Satamam* (l. 7). It should be noted that the Kushāna form of *ma* is altogether wanting in this inscription. So also in the case of *ha* we find the Maurya form in *-sahasehi* and *haya*- (l. 4), the transitional form in *Mahārāja*° and *Māhāmeghavāhane*° (l. 1) and the angular form in *-vavahāra*- (l. 2). The general duct of the writing shows that the Hathigumpha inscription was inscribed at a time when the length of the verticals had not begun to decrease and the curves had just begun to become angularised. Therefore, this inscription

¹ [See f. ns. 11 & 12 on page 89 below.—Ed.]

belongs to the same period as the earliest inscription from Mathurā edited by Bühler¹, and it cannot be earlier than the beginning of the 2nd century B.C. or later than that of the 1st century B.C. For *na*, *ṇa* and other letters a reference is invited to the detailed palæographical analysis by RDB, elsewhere.²

There are two **symbols**, one over the other at the beginning, and one at the end of the record. At the beginning the first symbol looks like a crown. KPJ. identifies it with the *Vaddha-maṅgala*.³ The second is the *Svastika*. The last symbol is the Sacred Tree within a square enclosure or railing. There is an elaborate system of **spacing** in this record, the larger, corresponding to full stops. There is space before almost every proper name. The smaller spaces indicate clauses of a sentence.

It has been proved by repeated examinations of the rock that there is **no date** in a Maurya era in the 16th line of this inscription, as supposed by the late Bhagvanlal Indraji and ourselves formerly. The date will therefore depend upon synchronisms. The first of these synchronisms is with **Sātakarṇi**. It is now absolutely certain that the family name of the dynasty founded by Simuka is Sātavāhana and not Sātakarṇi.⁴ The Nānāghāṭ inscriptions supply the label *Rāyā Simuka-Sātavāhana* for the statue of Simuka. There were more kings than one of the name of Sātakarṇi, and the first king of that name is called Siri Sātakarṇi both on his coins and in the label on his statue at Nānāghāṭ. Subsequent Sātakarṇis with whose names we meet in epigraphical records added their metronymics to distinguish themselves from their predecessors, e.g., Gautamīputra Sātakarṇi, Vāsishṭhīputra Śiva-Śrī Sātakarṇi and Gautamīputra Śrī Yajña Sātakarṇi. It is therefore evident that this record refers to a Sātakarṇi who was a contemporary king in the Western regions. The name is not to be taken as a reference to an unidentified dynastic title. And the only king of this dynasty who can safely be ascribed to the period when Khāravela was ruling is Śrī Sātakarṇi, the husband of Nāyanikā, and not Gautamīputra or Śiva-Śrī or Śrī Yajña. About Gautamīputra Sātakarṇi it is to be observed that the long record in cave No. 3 in the Pāṇḍulēnā group does not mention the king or the country of Kālīṅga, and thereby proves that Kālīṅga or Orissa was not included in his conquests and, very probably also, that he did not come in close contact with Khāravela or any other king of Kālīṅga, though the Amarāvati and China inscriptions of Pulumāvi and Śrī Yajña prove definitely that the whole of Kālīṅga had passed under their dominion.⁵ The other kings of the name of Sātakarṇi are excluded as being, *inter alia*, too late to be Khāravela's contemporaries. According to the Purāṇic lists Sātakarṇi II comes 36 years after Sātakarṇi I. RDB. has proved that the dissentient view about the Hāthīgumphā inscription being later than the Nānāghāṭ records is untenable.⁶ Therefore the Sātakarṇi of the Hāthīgumphā inscription must be Sātakarṇi I. The statement in l. 6 about Khāravela's subjugation of the **Rāṭhikas** and **Bhojakas** shows that up to the 4th year of the reign of Khāravela they existed as separate states, as in the time of Aśōka, but subsequently these states must have been swallowed up by the Sātavāhanas. Therefore, Khāravela's conflict with Sātakarṇi must have taken place

¹ *Ante*, Vol. II, p. 198.

² *Memoirs*, A. S. B., Vol. X, pp. 133 ff.

³ *J. B. O. R. S.*, Vol. III, p. 429.

⁴ KPJ. put it forward in 1914 in his *Brahmin Empire*, and the view has been confirmed by the discovery of the last record of the family-name, clearly. *Ante*, Vol. XIV, p. 153. *Sātavāhana* as the family-name is fully borne out by literature. [See *J. B. O. R. S.*, Vol. XVI, pp. 258 ff. on Sātavāhana history.—K. P. J.]

⁵ *Ante*, Vol. X, App. Nos. 1248 and 1340.

⁶ *Memoirs*, A. S. B., Vol. X, p. 145. [See also *J. B. O. R. S.*, XVI, pp. 258 ff.—K. P. J.]

before the formation of the Sātavāhana empire covering the whole of Marāṭhī-speaking (e.g., Barhādī, Khāndeśī, Northern Marāṭhī and Koṅkaṇī) area.

The reference in the 6th line to the canal from *Tanasuliya-vāta*, which was excavated in the year 103 of King Nanda, will fix the upper limit of Khāravela's time, like the reference to **Muriya-kāla** (the time of Muriya in l. 16). Chālukya Vikramāditya VI in the Yeḍarāve inscription is said to have established his Chālukya era after abolishing the eras of Vikramāditya, Nanda and Śaka. "Having said 'Why should the glory of the Kings Vikramāditya and Nanda be a hindrance any longer?', he, with a loudly uttered command, abolished that (*era*) which has the name of Śaka, and made that (*era*) which has the Chālukya counting".¹ Again, we have the definite datum that Alberuni found in use in his time an era with the initial year 458 B.C., which goes back to the time of the first Nanda king (Nanda Vardhana).² The year 103 of the Nanda era would correspond to 355 B.C. when the Tanasuliya canal, which Khāravela extended to the capital in the 5th year of his reign, was originally excavated. If we take this Nanda to be the last Nanda, Khāravela would be referring to (325 B.C.—103=) c. 222 B.C. and not to any later year. But we have something more definite in the next datum, namely, the contemporaneity with **Bahasatimitra**. In line 12 Khāravela reaches the **Sugamgiya** palace, i.e., the famous Maurya palace at Pāṭaliputra mentioned in the *Mudrārākṣha*.³ Bahasatimitra is expressly called the King of Magadha. Now we know from coins that Bahasatimitra and Agnimitra issued coins of the same type. This much we may take as certain that the time of Bahasatimitra, whosoever he may be, is the first half of the 2nd century B.C.⁴ Āshāḍhasēna, who belonged to the royal family of Adhichchhatrā, describes himself as the maternal uncle of King Bahasatimitra in the Pabhosā inscription,⁵ and Āshāḍhasēna dates his record in the 10th year of Odraka,⁶ whom KPJ. has identified with a king of the Śuṅga dynasty. Bahasatimitra's coins have been found at Kosam (Kauśāmbī)⁷ which was a state on the borders of Magadha. The characters of the coins agree with those of the Hāthīgumpha inscription.⁸ As Bahasatimitra does not occur in the list of the Mauryan kings and as his connection with the family of Odraka is indicated by the Pabhosā record, we are justified in taking him as one of the early Śuṅgas before Odraka, the fifth king of the line. In other words, Khāravela's contemporary Bahasatimitra would belong to a period between 188 B.C. and c. 125 B.C. It is true that we do not find the name of Brihaspatimitra in the Śuṅga list. But we have the explanation given in the *Purāṇas* themselves. It is reported there that Pushyamitra made others rule; the *Vāyu* says that he made his 8 sons rule equally, i.e., with equal powers.⁹ We know that Agnimitra ruled at Vidiśā with a separate court of his own. Probably the 6th son was ruling in Kōsala as the Śuṅga inscription at Ayōdhyā would suggest.¹⁰ It is significant that Pushyamitra is not called king in this record, but his title *Sēnāpati* is there just as it is in Kālidāsa's *Mālavikāgnimitra*. Similarly the dating on the Bhārhut gate "in the reign of the Śuṅgas" confirms the Purāṇic datum that several sons ruled at the same time (*in different parts*) under Pushyamitra. The *Vāyu-Purāṇa* places in the imperial list (*of Magadha*) the sons of Agnimitra, and not Agnimitra himself, after Pushyamitra. As

¹ *Bom. Gaz.*, Vol. I, Pt. ii, p. 477.

² *J. B. O. R. S.*, Vol. XIII, pp. 237, 241; Sachau, Vol. II, pp. 5 to 7.

³ Act III.

⁴ *Cambridge History of India*, Vol. I, p. 525.

⁵ *Ante*, Vol. II, p. 242.

⁶ *Ibid.* For *Udraka* as a proper name compare *Divyāvadāna*, p. 392.

⁷ *Ante*, p. 243 n. 17.

⁸ V. A. Smith, *Catalogue of Coins in the Indian Museum, Calcutta*, Vol. I, p. 155.

⁹ *J. B. O. R. S.*, Vol. X, p. 202, Vol. XIII, pp. 247 and 248.

¹⁰ *J. B. O. R. S.*, Vol. XIII, pp. 247, 248 and p. 57 above.

Bṛhaspatimitra is not in the royal list of Magadha between Agnimitra's sons and Odraka, we shall be justified in taking him to a period before Agnimitra's sons succeeded to the Magadha throne, i.e., to the time of Pushyamitra himself.¹

The most important contribution of the Hāthīgumphā inscription is the synchronism of Khāravela with the Indo-Greek king Demetrios. This important discovery was made in November 1919,² and it was settled that after the phrase *Yavana-rāja* comes the name Dimita... . Beyond this name not a single succeeding word of the sentence can be read. Demetrios, son of Euthydemus I, is generally well-known as the conqueror of India. It is mentioned in a verse of Chaucer quoted nearly half a century ago by Cunningham. Strabo refers to the fact that the kingdom of Bactria had expanded in a remarkable way beyond its original limits and that the kings responsible for its enlargement were Demetrios and Menander.³ Beyond this nothing could be said about the Indian conquests of Demetrios before the discovery of the king's name in the Hāthīgumphā record. Justin calls him the king of the Indians. He was probably driven out of Bactria by a rival king named Eukratides and had to settle down in Afghānistān and India. The surest indication of his dominion over some part of India is the use of the Kharōṣṭhī script on some of his copper coins with the use of the title *Aparajita*.⁴ Unfortunately we do not know the exact date of Demetrios except through synchronisms. He conducted negotiations between his father Euthydemus I and Antiochus III of Syria and married the latter's daughter. Therefore he must have been a young man towards the close of the third century B.C. His Indian campaigns appear to have been undertaken when he had come to the throne in mature age, and his coins show that he was between 30 and 35 when his reign began.⁵ Numismatists distinguish two Demetrioses, taking Demetrios II to be the son of Demetrios I.⁶ It would be absurd to say that the Indian conquests of the first dynasty of the Bactro-Greek kings were made by Demetrios II. The Indian campaigns of Demetrios and his advance at Pāṭaliputra are distinctly described in *Yuga-Purāṇa* of the *Gārgī-saṃhitā*. The historical text of the work has been recently collected from different MSS. by KPJ.⁷ Section 5 contains the account of the Greek invasion of Pāṭaliputra and a battle at that place. It is stated that after conquering Sākēta, Mathurā and Pañchāla the Greeks reached Kusumadhvaja, and at Pushpapura, i.e., Pāṭaliputra, there was a great battle fought on the mud-embedded western ramparts with engines (ballistae or catapultae), and the outlying districts became full of disorder. Further on (section 7) there is a mention of Demetrios as *Dharmamita* where it is distinctly stated that his officers would oppress the people. Finally it is stated that intoxicated with fighting the Greeks would not stay in the Middle Country and that there would be a furious civil war among themselves in their own country. This statement is corroborated by the Greek accounts of the great civil war in Bactria and Afghānistān between Demetrios and his successors and Eucratides

¹ The objection of Prof. Rapson (*Cambridge History of India*, Vol. I, p. 537, note) that there is an interval of 25 years between Pushyamitra and Odraka, and therefore Āshādhaseṇa, the maternal uncle of Bahasatimitra, cannot be connected with Bahasatimitra of Pabhosa has not much force in a country where people marry more than one wife at the same time and where maternal uncles are often found to be much younger than their nephews.

² It was announced by Sir Edward Gait in his presidential address to the Bihār and Orissa Research Society in 1920 (*J. B. O. R. S.*, Vol. VI, p. 5). The late Rao Bahadur H. Krishna Sastri did not notice this discovery even in 1922-23. Cf. *Annual Report of the Archaeological Survey of India*, 1922-23, p. 130.

³ *Cambridge History of India*, Vol. I, pp. 444-45.

⁴ *Catalogue of the Coins in the Punjab Museum, Lahore*, Vol. I, p. 14, No. 29.

⁵ *Cambridge History of India*, Vol. I, Plate III. 3.

⁶ *Ibid.*, p. 451.

⁷ *J. B. O. R. S.*, Vol. XIV, pp. 397-421 and Vol. XV, pp. 129-133.

and the kings of the dynasty founded by him. Therefore his mention in the Hāthigumphā inscription proves definitely that Khāravela must have flourished in the first half of the 2nd century B.C.

The compilation (*upādayati*) of the **Aṅgas** is described in line 16 as the crowning act of glory of Khāravela. This was undertaken and completed in the 13th year. Learned Jainas from all over India were assembled in a conference (*saṅghayanam*), evidently on the Kumārī Hill of sacred associations, and they put together once more the scattered or lost sacred texts of Jainism. The Jaina tradition asserts that in the reign of Chandragupta Maurya a Jaina conference was held at Pāṭaliputra after the 12 years' famine was over but that no agreement could be reached as to the restoration of the texts. Khāravela's wide conquests from the Pāṇḍya country up to the North-Western Frontiers and from the Marāṭhā country up to Magadha and his consequent political influence made it possible for him to have the texts recompiled. That the term '*Aṅga*' denotes the Jaina canonical *Aṅgas* is proved by the adjective 'consisting of 64' (*choṣaṭhi*), which is a very difficult and mysterious expression. The Jaina tradition says that 64 letters make up the Jaina sacred literature. The Jainas at present give a mystic interpretation, *vide* Mr. J. L. Jaini in his *Introduction to the Jīva-Khaṇḍa* of the *Gōmmatasāra* at p. 12. He says :—"The knowledge of Śruti, Śruti-Jñāna, may be of things which are contained in the *Aṅgas* (Limbs or sacred books of the Jainas) or of things outside the *Aṅgas*. There are 64 simple letters of the alphabet. Of these 33 are consonants, 27 vowels and 4 auxiliary (which help in the formation of compound letters). The total number of possible combinations of these 64 simple letters into compounds of 2, 3, 4, or more up to 64 letters is : $2^{64}-1=1,84,46,74,40,73,70,95,51,615$.

"These are the letters (simple and compound) of Śruti in its entirety. This number being divided by 16,348,307,888, which is the number of letters in a central foot (*madhyamapāda*) of the Paramāgama (Sacred Jaina Literature), gives us the number of padas of the *Aṅgas* as 11,283, 58,005. The remainder 80,108,175 gives us the letters of that part of Śruti which is not contained in the *Aṅgas*. This part is divided into 14 Prakīrṇakas".

In our opinion the Jainas had an alphabet of 64 letters several of which were not actual letters but symbols.

One school of the Jainas maintains that only 11 *Aṅgas* were recovered after the loss. If we read "*Aṅga-satika-turiyaṃ*" instead of "*Aṅga satika(m) turiyaṃ*" we may get the meaning that the re-compiled *Aṅgas* were in two groups, *Satika* = *saptika*, group of seven texts, and *Turiya* = *turiya*, a group of four texts. In any case the Jaina tradition about the loss and the recovery of the texts stands confirmed, and here we find another instance of the faithfulness of the Jaina tradition. The monks honoured at the Kumārī Hill in the 13th year were Śvētāmbaras as they were given pieces of China-cloth (silk) (*china-vatāni* = *china-vastrāṇi*)¹ and white robes (*vāsa-sitāni*). Khāravela, by his religious enterprise, was emulating Chandragupta and Aśoka. But posterity has completely forgotten him.

Fortunately the majority of the names of places mentioned in this record can be identified. **Kalīṅganagarī** is the ancient capital. Kalīṅga, a city which has now disappeared, lay close to Kalīṅgapāṭanam, a place on the Bay of Bengal in the Ganjām district of the Madras Presidency. **Kaṇha-berinā** is Kṛishṇa-verṇā² of the Rāshṭrakūṭa period and the modern Kṛishṇā. **Musikā-nagaram** was probably a city on the river Mūsī in its upper reaches near Gōlkoṇḍa-Hyderābād³

¹ On the occurrence of *China* in the *Arthashastra* and its connection with *Shina* the Gilgit tribe see '*Hindu Polity*,' I, 212; cf. Grierson, *Linguistic Survey of India*, Vol. X, pt. 4, p. 5n.

² [The *Kaṇṇapenna* or *Kaṇṇabanna* of Pāli literature.—Ed.]

³ The confluence of the *Mūsī* and the *Kṛishṇā* is mentioned in a copper-plate, *ante*, Vol. VI, p. 209. [Muziris on the Malabar coast is suggested as a possible alternative—R. D. B.]

As to the peoples mentioned in the inscription the **Rāṭhikas** are probably the **Mahārāṭhis** or the people of northern Mahārāshṭra, *i.e.*, the inhabitants of the modern districts of East Khāndesh, Nāsik, Ahmadnagar, Poona and the northern *taluks* of Sholāpur; the **Bhojakas** are likely the same as Mahābhōjas, *i.e.*, the inhabitants of the Marāṭhi-speaking districts of the Central Provinces and Berār.

The **Tanasuliya** or **Tanasuliya-vāṭa** cannot be identified by us. **Vajiraghara** remained under the same name till the 12th century A.D. when it is mentioned by Kulōttuṅga Chōla I or the Chālukya-Chōla Rājendra Chōla II, as **Vayirāgara** in the Tiruvorriyūr Ādhipuriśvara temple inscription of the second year. It states that Rājakēsarivarman *alias* Rājendra Chōla II captured elephants at this place and defeated the king of Dhārā at Chakrakōṭṭa. In the Pāṇḍava-Perumāḷ temple at Conjeeveram another Tamiḷ inscription of the 5th year of the same king, who is called Rājakēsarivarman *alias* Kulōttuṅga Chōla I, informs us that the king's victories at Vayirāgara and Chakrakōṭṭa were gained while he was the heir-apparent, *i.e.*, before 8th October 1070 A.D. Chakrakōṭṭa has been correctly identified by Rai Bahadur Hiralal with Chakra-Kotyā in the Bastar State of the Central Provinces. It is therefore certain that this Vayirāgara is the same as modern Wairagaḍh in the Chanda district of the same province. Kielhorn restored the name *Vayirāgara* as *Vajrākara*.¹ The form *Vajiraghara* in this record shows that the original form was *Vajra-grīha* or *Vajra-gaḍha* in Prakrit which came to be written as Vayirāgarām in Tamiḷ. Both Chakra-Kotyā and Wairagaḍh are on the road from Central Kāliṅga to Southern Mālwā. **Goradhagiri** is no doubt the ancient name of the Barābar Hills in the Gayā district, as proved by Mr. V. H. Jackson, I.E.S., the late principal of the Patna College who, along with Mr. Russell, discovered the inscriptions on boulders near the top, giving the name correctly as *Gōrathagiri*.² Mr. Jackson also described immense fortifications on the hill top.³ The place was an important outpost on the western flank of the ancient capital of Magadha, Girivraja or Rājagriha or Rājagaha. It is mentioned in the *Mahābhārata* where the route of Bhīma and Kṛishṇa to Girivraja is described.⁴ Rājagriha or Rājagaha, the ancient capital of Magadha, still exists as Rājgir, famous as a Jaina Tīrtha and for its hot springs, in the Bihār sub-division of the Patna district of Bihār and Orissa.⁵ **Madhura** is undoubtedly the northern Mathurā in the United Provinces. **Bharadhavasa** (Skt. *Bhārutaravasha*) means the plains of Northern India. **Pithumḍa** is Ptolemy's *Pitundra*, a city which no longer exists, but which was an important port even in the first century A.D.⁶ **Tamira** or **Tramira** is equal to *Draṇiḍa* or *Dramiḍa*, *i.e.*, the *Tamiḷagam* or the Tamiḷ speaking districts of the Madras Presidency known as *Damirike* to classical writers. **Utarāpadha** is Sanskrit *Uttarāpatha* which included our North-Western Frontier Province. **Magadha** is south-western Bihār consisting of the modern districts of Patna, Gayā and the north-western Hazāribāgh, while **Aṅga** consisted of the portions of the districts of Bhāgalpur and Monghyr which lie to the south of the Ganges, adjoining Magadha. The **Paṇḍa-Rāja** of this inscription refers to the kings of the southern extremity of the Indian Peninsula from Madura to Cape Comorin.

We edit the inscription from the rock, the cast in the Patna Museum and from impressions taken by us as well as by the Curator of the Patna Museum.

¹ *Ante*, Vol. VII, App. pp. 124-25, Nos. 756, 761. See also note 4 on p. 124.

² *J. B. O. R. S.*, Vol. I, p. 159.

³ *Ibid.*, Vol. III, p. 469.

⁴ *Ibid.*, Vol. I, pp. 160 and 161.

⁵ For the antiquities of Rājgir see Marshall's account in the *Annual Report of the Archaeological Survey of India*, 1905-06, Part II, pp. 86 ff.

⁶ *J. B. O. R. S.*, Vol. XIV, p. 151.

TEXT.¹

- 1 [Two symbols] Namo Ar[i]bhamtānam[*] Nāmo sava-Silhānam[*] Aire la³ Ma
hārājena **Māhāmeghavāhanena**⁴ **Cheti-rāja**-vasa⁵-vadhanena pasatha-subha
lakhanena chaturamta-luṭhita-guṇ-opahitena **Kaliṅg-ādhipatinā**⁶ siri-Khāra-
veiena
- 2 paṇḍarasa-vasāni siri-kaḍāra-sarira⁷vatā kiṭitā kumāra-kiṭikā[*] Tato
lekha⁸-rūpa⁹-gaṇanā¹⁰-vavahāra¹¹-vidhi¹²-visāradena sava-vijāvadātēna nava-vasāni
Yovaraja[m]¹³ pasāsita[m] [*] Saṃpūṇa-chatu-vīsati-vaso tadāni vadhamāna¹⁴.
sesayo **Ven-ābhivijayo**¹⁵ tatiye
- 3 **Kaliṅga**¹⁶-**rāja**-va[m]se purisa-yuge Māhārāj-ābhisechanam¹⁷ pūpunūti[*] Abhi-
sita-mato cha padhame¹⁸ vase[*] vāta-vihita-gopura-pākīra-nivesanam paṭi-
samkhārayati[*] **Kaliṅga**¹⁹-**nagari**-Khibīra-isi-tāla²⁰-taḷga-pāḍiyo²¹ cha bam-
dhāpayati[*] sav-uyāna-pa[ti]samthapanam cha
- 4 kārayati panatīsāhi sata-sahasēhi Pakatiyo cha ramjaya²² [*] Dutiye cha
vase achitayitā **Sātakaṇṇim**²³ pachhima-disam haya-gaja nata-radha-bahulam
damḍam pathāpavati[*] **Kaṇha-berṇā**²⁴-gatāya cha senāya vīṇasitaṃ
M[ū]sika-nagaram²⁵ [*] Tatiye puna vase
- 5 gaṇḍhava-veda-budho dapa-nata-gīta-vādita-saṇḍaṃsanāhi usava-samāja-kārā-
panāhi cha kiḷāpayati nagariṃ [*] Tathā chavuthe vase **Vijādhara-**
ādhivāsam ahata-puṇam Kaliṅga-puṇa²⁶-rāja-[nivesitaṃ]
vitadha-ma[ku]ṭṭa-sabilama[dh]ite cha nikhita-chhata-
- 6 bhiṃgūre hita-ratana-sāpateye sava-**Raṭhika-Bhojake**²⁷ pāde vaṇḍāpavati[*]
Paṇchame cha dāni vase **Narṇḍa-rāja**²⁸-ti-vasa-sata-oghāṭitaṃ **Tanasuliya-**
vātā paṇḍim Nagaram pavesa[ya]ti [*] So bhisito cha Rāja-s²⁹.
[u]ya[m] saṇḍasayamto sava-kara-vaṇam
- 7 anugaha-anekāni sata-sahasāni visajati Poram Jānapadam[*] Sātamam cha
vasam pasāsato **Vajiraghara-vati**-ghusita-gharini sa matuka-pada-puṇna . .
[ku]ma [*] Aṭhame cha vase mahatā sen[ā]
Goradhagirim
- 8 ghātāpayitā **Rājagaham** upapīḍāpayati[*] Etin[ā] cha kaṇṇapadāna-sa[m]-
nādena³⁰ samb[i]ṭa-sena-vāhane vipamu³¹[m]chitu **Madhuram** apayāto **Ya-**
vana-rāj[ā] **D[i]mī[ta]**³² yachhati palava . .
- 9 kapa-rukhe haya-gaja-radha-saha-yaṇte sava-ghar-āvāsa-parivasane agiṇathiyā³³
sava-gahanam cha kārayitum Baṃhaṇānam jātim parihāram dadāti[*]
Arahato [va ?] [gi]ya[to]
- 10 . . . k.i. māna[ti]rāja-saṇnivāsam **Mahāvijayam** pāsādam kārayati aṭha-
tisāya sata-sahasēhi[*] Dasame cha vase damḍa-saṇḍhī-sā[ma]-mayo **Bha-**
radhava-sa-pathānam mah[i]-jayanam kārāpayati
p[ā]jyātānam cha man[i]-ratnāni upalabhate
- 11 [mamdam] cha **Ava**³⁴-**rāja**-nivesitaṃ **Pithumdam**³⁵ gadabha-namgalena kāsā-
yati janasa dabhāvanam(a) cha terasa vasa-satikam ābhi[m]dati T[r]amira³⁶.
desha-saṃghātam [*] Bārasame cha vase hasa ke [saha]-
sehi vitāsayati **Utarāpadha-rājāno**

(a) [The reading seems to be janapada-bhāvanam.—Ed.]

- 12 M[a]gadhānam cha vipulam bhayam janeto hathi Sugamgiya[m] pāya-
yati [*] M[āga]dha[m]³⁶ cha rājānam Baha[sa]timitam³⁷ pāde vamdā-
payati[*] **Namda-rāja**-nītam cha **Kā[li]mga-Jinam**³⁸ samnive[sa]
[gaha]-rata[nā]na[m] paḍihārehi³⁹ **Amga-Magadha**⁴⁰-vasum cha neyāti[*]
13 katu[m] jaṭhara-l[i]khila barāni siharāni nivesayati sata-
visikanam⁴¹ [pa]rihārehi[*] Abhutam=achhāriyam cha hathi-nivā[sa]-pari-
saram⁴² haya-hathī-ratanā-[mānikam] **Pamḍa**⁴³-rājā [ch=edāni anekāni]
m[u]ta-maṇi-ratanāni āharāpayati idha sa t[a].
14 sino vasikaroti[*] Terasame cha vase supavata-
vijaya-chaka-**Kumārī-pavate** arahayate pa-khiṇa-sam[si]⁴⁴tehi **kāya-nisīdiyāya**
yāpa-ñāvakehi⁴⁵ rāja-bhitini china-vatāni vās[ā]-s[i]tāni⁴⁶ [*] pūj-ānurata-
uvās[aga-**Khā**]ravela⁴⁷-sirinā jīva-deha-[siri]kā parikhita
15 sukat[ā]-samaṇa-suvihitānam cha sata-disānam ṇan[i]nam
tapas[i]-is[i]nam samghayanam⁴⁸[*] **Arahata-nisīdiyā** samīpe pābhāre var-ā-
kāra-samuthāpitāhi aneka-yojan-āhitāhi pa si. o. silāhi **Simha-**
patha-rañi-Si[m]dhulāya⁴⁹ nisayāni
16 Paṭalako chaturo cha veḍūriya-gabhe thambe patiṭhā-
payati[*] pānatariya sata-sahase⁵⁰[hi][*] **Muriya-kāla**-vochhinam cha
choyath[i] **Amga-satika**[m] turiyam upādayati[*] Khema-rājā sa Vadha-
rājā sa Bhikhu-rājā Dhama-rājā pasamt[o] sunat[o] anubhavat[o] kalā-
ṇāni
17 guṇa-visesa-kusalo sava-pāsamḍa-pūjako sava-de[r-āya]tana-
samkhāra-kārako [a]patihata-chaki-vāhini-balo chaka-dhura-guta-chako pavata-
chako **rājasi-Vasū-kula**⁵¹-vinisrito⁵² mahā-vijayo **Rājā-Khāravēla-siri**[*]
[Symbol].

NOTES ON THE TEXT.

1. For facsimile plates see *J. B. O. R. S.*, Vols. III, IV and XIII.
2. [The reading *Ari*^o was corrected from *Arā*^o after Mr. Banerji's death, with the help of Muni Jinavijaya.—K. P. J.]
3. *Airena* is the equivalent of *Ailena*, meaning a descendant of Ila or Ilā, father or mother of Purūravas. The same title is also to be found in the Mañchapuri Cave inscription of Kūde-pasiri.¹ For the change of *l* into *r* see *T[r]amira* in line 11 below. [In connection with this title the description in the last line *rājasi-Vasū-kula-vinīsrito* may be noted. The Purāṇic tradition of *Rājars̥hi* as well as of the Aila dynasty was thus well-established before Khāravēla's time.—K. P. J.]
4. *Māhāmēghavāhana*.—Probably the reading in the Mañchapuri inscription is also *Māhā-mēghavāhana* and not *Mahāmēghavāhana*. The long vowel over the first syllable *Mā*^o is quite clear in this inscription. The increase in the strength of the vowel indicates that King Khāravēla was a descendant of Mahāmēghavāhana, who might have been the recent founder of the dynasty.
5. *Cheti-rāja-vasa*..—Evidently *Cheti* is the same as Chēdi.² The later Chēdis, Kalachuris or Haihayas of Dābhāla or Dāhala were in occupation of modern Baghelkhand and Chhattisgarh in the mediæval period. Before that in the 7th century the Kalachuris Śaṅkaragupta and Bud-dharāja were in possession of Mālwa and the Northern Mahārāshtra until their conquest by the early Chālukyas of Bādāmi. The Buddhist books mention *Cheti* as one of the sixteen great king-doms or nations of Northern India.³ In the dynastic lists given in the *Purāṇas*, the Haihayas

¹ *Ante*, Vol. XIII, p. 100.² Rhys Davids, *Cambridge History of India*, Vol. I, p. 172.³ Cf. Konow, *Acta Orientalia*, Vol. I, p. 38.

are a branch of the Yādavas.¹ The origin of the Chēdis is thus stated by Pargiter: Vidarbha of the Yādava clan had three sons named Bhīma Kratha, Kaiśika and Lōmapāda. Kaiśika's son Chidi founded the dynasty of Chaidya kings in Chēdi.² From Chidi the name of the clan as well as that of the country became Chēdi. In the Buddhist books Chēti is placed between Malia and Varṇsa indicating that the kingdom lay close to Kauśāmbī in the Allahābād district, and it is very likely that modern Baghelkhand was originally called Chēdi. [Vasu, from whose line Khāravela's family descended (l. 17) was, however, not a Chaidya but the conqueror of the Chēdi country. He was fifth in descent from Kuru who was the 72nd Aīja (*J. R. A. S.*, 1910, pp. 22, 26-29). The Jaina *Harivamśa-Purāṇa* also includes Vasu in the Aījēya list and as the son of the founder of Chēdi-rāṣṭra in the Vindhyas (*J. B. O. R. S.*, Vol. XV, p. 277).—K. P. J.]

6. *Kaliṅg-ādhipatinā*.—The term Kaliṅga is usually applied to the northern part of the Telugu-speaking districts of the Madras Presidency. In the *Purāṇas*, Kaliṅga is associated with Aṅga (south-eastern Bihār), Vaṅga (eastern Bengal), Puṇḍra (northern Bengal) and Suhma (south-western Bengal). The names of these five countries were given according to the names of the five sons of Bali,³ i.e., the tradition treats the kingdoms to be early Aryan conquests and states. In the *Vāyu* and the *Brahmāṇḍa-Purāṇas*, Kaliṅga is associated with the Mahisha country⁴ (later Māhishmatī, modern Mahesor in the Indore State on the river Narmadā). This text would indicate that Utkala was included in Kaliṅga in the time of Khāravela and the later name Ōḍra had not come into existence. The Purāṇic texts further indicate that the term Utkala was applied in early times to the hilly country between Gayā and Orissa, i.e., modern Chhoṭā Nāgpur and the Garhjat States. "The Saudyumnas had been almost overwhelmed by the Ānavas and Pauravas, and were restricted to the Utkalas and other clans which occupied the hilly tracts from Gayā to Orissa."⁵ The transfer of the term Utkala to the plain country along the sea-board is therefore later.

7. *Siri-kaḍāra-sarīra-vaṭā*.—*Kaḍāra* means reddish fair, according to *Amara*, and a slave according to the *Mēdinī*. If it is a Prakrit derivation from *kaṭāra*, then it means "nāgarah or kāmīn," according to the *Śabdamaṇī* (*Vāchaspatyam*). The explanation given in the *Amara-kōsha* is more suitable as meaning "of beautiful reddish body."

8. *Lekha* or Royal Correspondence, a manual of which was written in the time of the Chālukyas of Aṇahilapāṭaṇa and has been published from Baroda.⁶ This *lekha* cannot refer to the art of writing. The subject is dealt with in the *Arthaśāstra* of Kauṭilya.⁷

9. *Rūpa* must be the equivalent of *rūpya* meaning currency. In the present inscription the position of the word *rūpa* shows that the meaning cannot be anything else.⁸ The exact meaning of the term is made clear by the explanation of Buddhaghōṣa on a passage of the *Mahāvagga*. The term is explained thus: "he who learns the *rūpa-sūtra* must turn over and over many *Kārshāpaṇas*."⁹ Finally, the term *rūpa-darśaka* in the *Arthaśāstra* translated as "Examiner of Coins" shows that the term *rūpa* was used in cases as in the present inscription with

¹ Pargiter, *Ancient Indian Historical Tradition*, p. 102.

² *Ibid.*, p. 272.

³ *Ibid.*, p. 109.

⁴ Pargiter, *Dynasties of the Kali Age*, p. 54.

⁵ Pargiter, *Ancient Indian Historical Tradition*, p. 292.

⁶ *Lekha-paddhati*, Gaekwad's Oriental Series, p. 58.

⁷ Mysore edn. (1919), pp. 70-75.

⁸ It is impossible to imagine that the prince learned acting. We can compare the word *lupadake* in the Jōgimārā cave inscription where also it may mean a currency officer. The term is also taken to mean a City-Magistrate who could recognise offenders at a glance. *Annual Report of the Archaeological Survey of India*, 1903-04, pp. 128-30. *Ind. Ant.*, Vol. XLVIII, p. 131.

⁹ *S. B. E.*, Vol. XIII, p. 201 note.

reference to currency. The term did not refer to silver currency alone but to other metals also, as we find the term *lāmra-rūpa* in the *Arthaśāstra*.¹

10. *Gaṇanā*.—This term occurs in the *Arthaśāstra* and has been translated as Accountancy. An entire chapter has been devoted to it there and the subject is explained in detail. It is certain that this term could not have been used for elementary mathematics in this inscription as supposed by Bühler. Knowledge of *lēkha*, *rūpa*, and *gaṇanā* is here coupled with that of law and learning and refers to a post-boyhood period.

11. *Vavahāra*.—*Vyavahāra* meaning Civil Law or Municipal Law as opposed to—

12. *Vidhi* or Religious Law which is mentioned in Sanskrit legal literature as positive injunctions.

13. *Yovarajam*=*Yavarājyam*.—*Yōvarajam* shows the shortening of the internal medial vowel in the second member and the graphic lightening of double consonant, as in the case of *Māhārāja*^o (l. 3), *rañi* (l. 15), etc.

14. *vardhamāna-sesayo*.—Though the incision of these two words is perfectly clear they cannot be satisfactorily explained by us. The equation *vardhamāna-saiśavō* is not quite satisfactory as a change of *v* into *y* is not to be had anywhere else in this record. The meaning proposed in the translation is adopted for want of a better one. There may be a pun intended by the use of the word *vardhamāna* which is the early name of the last Tirthaṅkara. The verb *pāpūnāti*=*prāpnōti* shows that the sentence is in the active voice and complete by itself. After this line the forms are generally causative.

15. *Ven-ābhiviṣayo*.—The reading is perfectly clear. The ancient monarch *Vēna*, father of *Prithu*, was an unorthodox king according to Brāhmanical literature. According to the *Padma-Purāṇa* he began his reign well but subsequently became a Jain. He abolished the law of levirate (*niyōga*) and caused a confusion or abolition of castes, according to *Manu*.² *Vēna* was a great conqueror and therefore the term *abhiviṣayo* is very appropriate in his case. Evidently the tradition recorded in the *Padma-Purāṇa* was well-established in the time of *Khāravela* and therefore the Jain monarch is compared to *Vēna*.

16. *Kaliṅga-rāja-va[m]se*.—In the third line the details about *Khāravela*'s ancestry are made clear. He was born in the royal line of *Chēti* and was the overlord of *Kaliṅga*, but the dynasty to which he belonged was the 3rd dynasty of the kings of *Kaliṅga*. This dynasty was one of the *Aiḷa* dynasties settled in Central and Southern India. The name *Khāravela* (probably, 'one whose waves are brackish'=the Ocean) is unusual, and so is the name of the other king of the dynasty, viz., *Kūḍepa* (*Mañchapurī* inscription). *Khāravela* is described to be an *Aiḷa* or *Aiḷa*, that is, of the Lunar House as opposed to the Solar. *Pargiter* holds that the kings of the *Aiḷa* stock held the Ganges and the Jumna valleys from the *Siwālik* Hills to *Magadha*, the country between the *Rājputāna* desert and the *Beṭār*, with the *Pañjāb* and *Peshāwar* in the north and East *Bibūr* and *Bengal* proper in the east. The town and country of *Vidarbha* is generally recognised to be the modern *Beṭār*.

17. *Māhārāj-ābhishēchanam*.—The regular *abhishēka* of a *Chakravartin* Monarch (called the *Aindra-mahābhishēka* in the *Śatapatha* and *Aitarēya Brāhmaṇas*).³

18. *Padhame*.—In this dialect *tha* becomes *dha* in the majority of cases, e.g., *Goradha*=*Goratha*, *radha*=*ratha*, *Bharadhavasa*=*Bharathavasa* and *Madhuram* for *Mathuram*. The change is well-known and probably it is an influence of Dravidian origin.⁴

¹ Text p. 84, Engl. trans., p. 95. (Dr. Shamasastri's edition.)

² *Mānavadharmasāstra*, Ch. IX, vv. 66-67.

³ *Jayaswal, Hindu Polity*, Pt. ii, p. 27.

⁴ This peculiarity is found in *Jaina-Saurasēnī*, *Saurasēnī*, *Māgadhī* and *Phakkī*. See *Pischel, Grammaire der Prakrit Sprachen*, para. 203.—Ed.]

19. *Kaliṅga-nagara*.—The capital of the Kalinga country, very likely now represented by Kaliṅgapatanam in the Ganjām district. The ancient capital of Kalinga, according to the tradition prevalent in the Chicacole *taluk* of the Ganjām district, was swallowed up by the sea. Fragments of bas-reliefs of the Maurya period with the well-known protuberance on the head-dress have been, however, discovered by RDB. in the temples of Mukhalīṅgēśvara and Kūṁṇēśvara in the locality. The coast from Chhatrapuram to Masulipatam is subject to great cyclones during the north-eastern monsoon and the majority of ancient sites on this coast are buried in drift sand.

20. *Khibīra-isi-tāla*.—We have examined these two words very carefully on the rock, estampages and casts. The reading is perfectly clear but no explanation seems to be possible unless Khibīra is taken to be a proper name of a Rishi who excavated the tank or lake or after whom it was named. In that case, the phrase will have to be taken as referring to a particular tank while *taṭāga* and *pāṭiyo* will refer to artificial excavations.

21. *Pāṭiyo*=Śkt. *Pāṭi*.—Perhaps the same as the *Polhuya* of Western India, cf. *Pāṇḍulēṇa* cave No. 10, inscription No. 10, l. 3.¹

22. *Sātakaṁṇim*.—Evidently Śrī Śātakaṁṇi, the third king of the Sātavāhana dynasty, the husband of queen Nāvanikā of the Nānāghāt inscriptions in the Junnar *taluk* of the Poona district.² [As to the Śātakaṁṇi whose architect Vāsēthiputra Ānanda gave a *tōraṇa* to *stūpa* No. I at Sāñchi see *J. B. O. R. S.*, XVI, p. 254.—K. P. J.]

23. *Kaṁṇha-beṇṇā*—the Sanskrit Kṛishṇavēṇī or the modern Kṛishṇā which rises near Dhom in the Sātārā district. The river flows through the Sātārā, Belgaum and Bijāpur districts and the Kolhāpur and Hyderābād States into the Bay of Bengal through the Kṛishṇā district of the Madras Presidency. It forms the boundary of the Nizam's State from Alampur near Karnūl to Nandigāma in the Kistna district. The rise of the Kṛishṇā and its particular sanctity are described in the *Pātāla-khaṇḍa* of the *Podmapurāṇa*.³ The earliest epigraphical reference is to be found in this inscription and the second in the Nāsik inscription in cave No. 10 of the Pāṇḍulēṇa group where it is called *Karabeṇā*.⁴ In mediæval inscriptions it is called *Kṛishṇa-Vēṇṇā*.⁵ There is no doubt about the fact that Khāravela reached the Kṛishṇā somewhere in the long and erratic course of that river. It is possible that he went westwards because the term *pachhima-disaṁ* is expressly mentioned. But it is uncertain as to where he reached the Kṛishṇā.

24. *Musika-nagara*.—The Mūshikas are a people of Southern India as in the *Mahābhārata* they are mentioned along with the Vanavāsas.⁶ In the *Nāṭya-śāstra* of Bharata they are probably coupled with the *Tōśalas* and the *Kōśalas* under the name *Mōśalas*.⁷ In the *Vishṇu-Purāṇa* the Mūsika country comes with the *Strī-rājya*. According to the commentary *Jaya-maṅgalā* on the *Kāmasūtra* of Vātsyāyana, the latter was a kingdom in the western part of the Vindhya country.⁸ There is a river Mūsī which joins the Kṛishṇā about the Nalgonda and the Kṛishṇā districts. It is mentioned under the same name in the inscription of the Rāshṭrakūṭa

¹ *Ante*, Vol. VIII, p. 78.

² *J. B. O. R. S.*, Vol. III, plate 3. As to the letter-form of this inscription reference may be made to the *Palaeography of the Hathigumpha and Nanaghat Inscriptions*, *Memoirs A. S. B.*, Vol. X, pp. 131 ff. RDB. has proved elsewhere that later and earlier forms of the character used in an inscription depend in the first place on locality.

³ Ānandāśrama edition (1894), pt. 4, VI, 113, p. 1467.

⁴ *Ante*, Vol. VIII, p. 78.

⁵ *Ante*, Vol. VI, p. 211.

⁶ *Bhishma-parvan*, Ch. IX.

⁷ XIII, 27. (*Kāvya-mālā* edition, p. 148.)

⁸ *Sub. Kāma-sūtra*, II, 5, 27.

Gōvinda II of the Śaka year 692=769 A.D.¹ It is quite probable that the Musika city stood on this river.²

25. *Kalinṅga-puṇa-rāja*.—The reading is absolutely certain and the phrase should be read with reference to *tatiye Kalinṅga-rāja-vaṃse*.

26. *Raṭhika-Bhojake* stand for the Mahārathis and Mahābhojas of Sātavāhana inscriptions and the minor inscriptions of the same period at Kānhēri, Kuḍā and Bāḍṣā. The Raṭhikas are mentioned as *Risṭikas* in the Girnār, *Raṭhikas* in the Shāhbāzgarhī and *Raṭhakas* in the Mānsēhrā version of the 5th edict of Aśoka. The Dhauli version supplies the analogous form in *Laṭhika*. In the 13th edict we find the *Bhojakas* mentioned with the *Pitnakas* in Shāhbāzgarhī, Mānsēhrā and Kālsī versions. In the Kānhēri cave inscription of the time of Viṇhukaḍa Chuṭukulānanda a Mahābhōja is also called a *Mahārāja* showing that Bhoja probably was a title. Mahābhōjas or Mahābhōjis are mentioned in five votive inscriptions in the Kuḍā cave. In later periods a Bhojaka is mentioned in the copper-plate inscription of the Pallava king Śivaskandavarman.³

27. *Nanda-rāja*.—King Nanda is mentioned in two places in this inscription, once in l. 6 and again in l. 12. The date in this line apparently refers to an era founded by King Nanda.⁴ His mention in connection with Magadha fixes his identity with the Magadhan Nanda dynasty.

28. *Rājasūyam*.—The reading is perfectly clear on the rock.

29. *samādāna*.—The form of the first letter seems to be a *sa* of the same type as that which we find in *Bahasamīṭam* in l. 12.

30. *vipamuchitu*.—It seems more probable that the reading is *vipamu*[m?] *chitu* not *vipamu-chitum*.

31. *Yavana-rāja-Dimita*.—The word *Yavana-rāja* was read by KPJ. for the first time in 1919. After that the second syllable of the proper name is distinct. The first and the third can be read with great difficulty. KPJ. proposed to read the first syllable as *Di* but RDB. proposed that it is *Di* in which the broad back of the letter is turned towards the right and not the left. In Aśoka's inscriptions both varieties are found but in this inscription the other variety, with the broad back to the proper left, is used in all other cases. The Greek King Demetrios calls himself Dime[tra] in his Kharōshthī coin legends.⁵

32. *agīnathiyā*.—The reading is certain and legible on the rock only. The decay of the stone makes good impressions impossible. Both of us have examined the place carefully and repeatedly. The meaning of the term is also uncertain. It may mean some form of Vedic sacrifice and the original form in Sanskrit might have been *Agn-ishṭi*. What had been read as *sa* before this word is uncertain.

33. *Ava-rāja* was previously read as *pūva-rāja*. It appears that that particular form of *a* in which the left lower curve is much shorter than the upper is also used in this inscription. Therefore the shorter arm of the long *u* may be taken to be the lower left curve of *a*. *Ava* as a dynasty is given by the *Bhāgavata-Purāṇa*, and the *Vishṇu* equates it with the Āndhras. Ptolemy

¹ *Ante*, Vol. VI, pp. 208-13.

² I am of opinion that Khāravela reached the Mahārāshtra country and touched the river Krishnā near its source where it flows directly north to south instead of touching it at any other place, because to reach the Krishnā at any other place he would have had to travel almost due south instead of west. Moreover, I put more reliance on the *Mahābhārata* than on any of the later texts. As the Mūsikas are coupled with the Vanavāsikas it is more probable that they lived on the western coast below Banavāsi (Sirsi taluk of the North Kanara district of Bombay). In my opinion Muziris, a famous port on the western coast, should be identified with Musikanagara of this inscription. (R. D. B.) [See *J. R. A. S.*, 1922, pp. 165 ff., and *Ind. Ant.*, 1923, p. 138.—Ed.]

³ See also *Hindu Polity*, Pt. i, pp. 143, 195.

⁴ See *J. B. O. R. S.*, Vol. XIII, p. 237.

⁵ *Catalogue of the Coins in the Panjab Museum, Lahore*, Vol. I, p. 14, No. 26.

mentions a people called *Avarni* or *Aruarni* near the *Kṛishṇā*. It is quite possible that the city of *Pithumṇā* mentioned by Ptolemy as *Pitundra* (*Ind. Ant.*, Vol. LV, p. 145), was founded by these people (*J. B. O. R. S.*, Vol. XIV, pp. 15 f.).

34. *Pithumṇā*.—According to Ptolemy, a city in the upper part of the Coromandal coast. This city has perhaps to be taken as the capital of the *Ava* or *Avarni*.

35. *Tramira* or *Tamira* is the equivalent of *Tamila* just as *Aira* represents *Aiḷa*. It has been pointed out that *Tamil* is the origin of *Draviḍa* and of *Dramila*.¹ *Tramila* would thus be a perfectly correct substitute for *Dramila*.

36. *Māgadham*.—We have examined the rock very carefully. The cast of the inscription in the Patna Museum shows that the word cannot be *Muriya* as proposed by Dr. F. W. Thomas.² The chisel-cuts of the letters are still clear though the decay of the rock surface has made impressions of this part of the inscription smudged.

37. *Bahasatimitam*.—The *sa* in the word is of the later 2nd century B.C. type in which a clear right-angle has been formed in the right limb of the letter and therefore it looks more like *pa* than *sa*. The reading is absolutely certain.

38. *Kāliṅga-Jina* perhaps means *Śīṭalanātha* who was born at *Bhādalapura*, which is the same as *Bhadrapura*³ or *Bhadrāchalam* in the *Gōḍāvari* district of the Madras Presidency.

39. *paḍihārehi* stands for *pratihāraiḥ*.—The *ḍa* denotes its difference from *parihāra* in l. 9.

40. *Aṅga-Magadha*.—The mention of these two provinces indicates that the campaign of the 12th year was specially directed against South Bihār which now includes the ancient provinces of *Aṅga* (*Bhāgalpur* and *Monghyr* districts) and *Magadha* (*Patna*, *Gayā* and part of *Hazāribāgh* districts).

41. *sata-visikanam*.—The reading is not doubtful though it was read slightly differently before. The reference seems to be to architects (*vaiśmikas*).

42. *hathi-nivāsa-parisaram*.—This reading of the second word of the phrase is more reliable than the previous one (*hathi-nāvana-paripuram*). *nivāsa*=*nivāsa*.⁴ The reference seems to be to elephant preserves or some original form of *khedā* arrangement, invented by *Khāravela*. The elephants of *Kaliṅga* were very famous in ancient India. The strength of *Khāravela* probably lay in elephants. He took the fort of *Pāṭaliputra* with the help of elephants.

43. *Paṇḍa-rājā*.—For the form cf. *rañi* in l. 15. The Sanskritized version of the name of the great Dravidian clan is *Pāṇḍya* and is derived from *Pāṇḍu* by a special rule of early grammarians. In the inscriptions of *Aśoka* also the vowel in the first syllable is long.

44. *Pa-khiṇa-samsitehi*.—The reading seems to be tolerably certain on the rock, though it looks doubtful in the impressions. *Pa-khiṇa*=*prakṣhīṇa*, *samsit*⁵=*samsṛit*⁶.

45. *Yāpa-ñavakehi*.—The first part of the compound cannot be satisfactorily explained by us though the reading is absolutely certain.⁷

46. *vāsā-sitāni*.—The medial vowels except that on the first syllable are somewhat uncertain. It may also be taken to be *-satāni*. It was previously read as *vasāsītāni*.

47. *Uvāsaga-Khāravela* previously read as *Uvāsa-Khāravela*. The *gā* and *kha* are indistinct.

48. *saṃghayanam*.—The reading is certain except of the vowel value on *gh*. Certain improvements have been effected, e.g., *ñaninam* which makes the purport of this term fairly certain.

¹ *Ind. Ant.*, Vol. XLIII, p. 64.

² *J. R. A. S.*, 1922, p. 84.

³ *Ind. Ant.*, Vol. II, p. 136.

⁴ Cf. *Kāmandakīya-nīṭisāra*, XV, 7.

⁵ [See Muni Puṇyavijaya, 'Anekānta' (Delhi), Vol. I, p. 142, where he cites Jaina texts on 'yāpa' ('religious life')] —K. P. J.]

49. *Simdhulāya*.—The recognition of the cerebral *la* is due to a suggestion of Prof. H. Lüders. In other cases the cerebral *la* is changed into *ra* in the dialect used in this inscription.

50. *sata-sahasehi*.—This reading was fully established by us when we examined the rock jointly in November 1919. This reading along with the reading of the passage *Amga*°, etc. brings to a close the long controversy about the existence of a date in the Maurya era in this inscription.

51. [The reading *Rājasi-Vasū-kula*° has been corrected by me (from *-vasa-kula*) after Mr. Banerji's death. King *Vasu* of Chēdi is known to the *Purāṇas* (see *J. R. A. S.*, 1910, p. 22; *MBh.*, I. ch. 3). *Cheti-rā a*° in l. 1 refers to King *Vasu*. The inscription here confirms the Purāṇic genealogy. The Jaina *Harivamśa Purāṇa* also gives *Vasu* in the Chēdi list (Ch. VII) and as an *Aliēva*. *J. B. O. R. S.*, Vol. XV, p. 277.—K. P. J.]

52. *vinisrito*.—This is the only instance of the use of the palatal *śa* in this record. The form is certain both on the rock and impressions.

TRANSLATION.

(Line 1) Salutation to the Arhats (*Arihats*=lit. 'Conquerors of Enemies,' i.e., Jinas). Salutation to all the Siddhas. By illustrious *Khāravela*, the *Aira* (*Aiḷa*), the Great King, the descendant of *Mahāmāghavāhana*, the increaser (of the glory) of the *Cheti* (Chēdi) dynasty, (endowed) with excellent and auspicious marks and features, possessed of virtues which have reached (the ends of) the four quarters, overlord¹ of *Kaliṅga*,

(L. 2) for fifteen years, with a body ruddy and handsome were played youthsomeness sports; after that (by him who) had mastered (royal) correspondence, currency, finance, civil and religious laws (and) who had become well-versed in all (branches) of learning, for nine years (the office of) *Yuvarāja*² (heir apparent) was administered. Having completed the twenty-fourth year,³ at that time, (he) who had been prosperous (*vardhamāna*) since his infancy (?) and who (was destined) to have wide conquests as those of *Vena*,

(L. 3) then in the state of manhood,⁴ obtains the imperial (*mūhārājya*) coronation in the dynasty of *Kaliṅga*. As soon as he is anointed, in the first (regnal) year (he) causes repairs of the gates, the walls and the buildings (of the city), (which had been) damaged by storm; in the city of *Kaliṅga* (he) causes the erection of the embankments of the lake (called after) *Khibīra* Rishi, (and) of (other) tanks and cisterns, (also) the restoration of all the gardens (he) causes to be

(L. 4) done at (the cost of) thirty-five-hundred-thousands,⁵ and (he) gratifies the People. And in the second year (he), disregarding *Sātakamni*, despatches to the western regions an

¹ In *Kalīṅg-ādhipati*, *adhipati* like *adhīrāja* of the inscriptions, would literally denote an 'overlord.' The chief queen of *Khāravela* in the Mañchapuri record calls her husband a *Kaliṅga* emperor (*Kalīṅga-chakavati*). In our record he is expressly described as belonging to the *Kaliṅga* dynasty. The expression 'overlord' would not indicate that he was the overlord of *Kaliṅga*, but an overlord or an emperor belonging to *Kaliṅga*.

² A member of the ministry (*Hindu Polity*, Pt. II, pp. 124, 136). According to the *Divyāvadāna*, *Samprati*, grandson of *Aśoka*, was the *yuvarāja*, while his father *Kuṇāla* was a viceroy at *Takshaśilā*. *Yuvarāja* was generally, but not necessarily, the Crown Prince.

³ Evidently the throne had been vacant and *Khāravela* ascended it after completing his 24th year. According to the *Bṛihaspati-sūtra*, for a prince playing and learning were enjoined up to the 25th year and after that age, politics.

⁴ *Purisa-yuge*.—This has a reference to the 25th year, see the note above.

⁵ The meaning given above is in consonance with the use of similar figures in lines 10 and 16 (*Mahāvijayaṃ pāsāṇam kārayati athatisāya sata-sahasehi*, and *pānatariya*, etc.). The instrumental case before *pakatiyo* may equally be taken to denote the number of the subjects (see *Siddhāntakaumudī* of Bhaṭṭoji Dikshita on Pāṇini, II, 3, 23, and II, 3, 46). RDB. would connect the figure with the sentence beginning with *pakatiyo* in the sense that by the expenditure indicated by the figure the king pleased his subjects (see *J. B. O. R. S.*, Vol. IV, p. 315).

army strong in cavalry, elephants, infantry (*nara*) and chariots (*ratha*) and by that army having reached the **Kaṇha-beṇṇā**, he throws the city of the **Musikas** into consternation. Again in the third year,

(L. 5) (*he*) versed in the science of the Gandharvas (*i.e.*, music), entertains the capital with the exhibition of *dapa*,¹ dancing, singing and instrumental music and by causing to be held festivities and assemblies (*samājas*);² similarly in the fourth year, 'the **Abode of Vidyā-dharas**' built by the former Kaliṅga king(s), which had not been damaged before with their coronets³ rendered meaningless, with their helmets (?) (*bilma*)⁴ cut in twain (?), and with their umbrellas and

(L. 6) *bhājāras* cast away,⁵ deprived of their jewels (*i.e.*, *ratana*, Skt. *ratna*, precious objects) all the **Raṭhikas** and **Bhojakas** (*he*) causes to bow down at his feet. Now in the fifth year he brings into the capital from the road of Tanasuliya⁶ the canal excavated in the year one hundred-and-three of King **Nanda**⁷ Having been (*re-*) *auo-*inted (*he while*) celebrating the Rājasūya, remits all tithes and cesses,

(L. 7) bestows many privileges⁸ (*amounting to*) hundreds of thousands or the City-Corporation⁹ and the Realm-Corporation.¹⁰ In the seventh year of his reign, his famous wife of **Vajiraghara**¹¹ obtained the dignity of auspicious motherhood. Then in the eighth year, (*he*) with a large army having sacked **Goradhagiri**

(L. 8) causes pressure¹² on **Rājagaha** (**Rājagriha**). On account of the loud report of this act of valour, the **Yavana** (Greek) **King Dimi[ta]** retreated to **Mathurā** having extricated his demoralised army and transport. (*He*) gives with foliage

¹ In Sindh this term is found in modern vernacular applied to a village-performance by a row of men who move on cutting antics. *Drava* in Sanskrit, meaning a dance, is connected with motion or running.

² On its meaning as a theatrical performance, see *Ind. Ant.*, Vol. XLVIII, p. 235.

³ (*Makuta*).—Crowns or coronets according to the *Nāṭya-śāstra* (XXI, 118). The *Raṭhikas* and *Bhojakas* were non-monarchical communities (*Hindu Polity*, Vol. I, p. 89).

⁴ *Bilma* in the *Yajur-vēda*, XVI, 35, comes in the company of *kavacha* (coat-of-mail or breast-plate).

⁵ *Bhrīgāra* which was made of gold, formed part of a ruler's paraphernalia according to the *Nāṭya-śāstra* (XXI, 138). So did the *chhatra* or umbrella.

⁶ *Tanasuliya-viṭā* means 'from the road of Tanasuli' or it might have been the name of the canal. *Viṭā* also means an enclosure.

⁷ The opinion of Luders (List No. 1345) and Konow (*Acta Orientalia*, Vol. I, p. 26) is in favour of interpreting *tivasa-sata* as 103 years and not 300 years. This is acceptable in preference to 300 on considerations of chronological and historical data of the inscription discussed elsewhere (*J. B. O. R. S.*, Vol. XIII, pp. 237-238). Such uses of numbers are not unknown in Vedic Sanskrit. The natural explanation is 'the year one hundred and three of King Nanda'. On a Nanda era, see Yeḍarāve inscription of Chālukya Vikramāditya VI (*Bombay Gazetteer*, Vol. I, Pt. ii, p. 43) and on an era beginning in 458 B. C. current in the time of Alberuni, the discussion on the subject in the *Journal of the Bihar and Orissa Research Society* (Vol. XIII, pp. 237-241).

⁸ *Anugaha*.—Consult *Hindu Polity*, II, 93; *Kautiliya Artha-śāstra*, 19, XIII, 171.

⁹ *Pora* = *Paura*.—See the discussion on the subject in *Hindu Polity*, II, Ch. 27, and the next note below.

¹⁰ *Jānapada*.—The discussion in the *Hindu Polity*, II, Ch. 27, sets out the materials. The question of identification of *Jānapada* as a corporate body is now put beyond controversy by the seal discovered at Nālandā which reads *Purikā-grāma-jānapadasya* 'of the Jānapada of the Purikā village'. This seal is in Gupta characters of the 5th or 6th century. [I am publishing it in my article on 'Some Clay Seals of Nālandā'-Ed.] Probably the central *Jānapada* was made up of the representatives of local *Jānapadas*. In the Hāthīgumpha inscription we have *Jānapada* in the singular, that is, it refers to one (general) *Jānapada*.

¹¹ It is an ancient royal mannerism to refer to different queens by the name of the country of their origin of., *Kausalyā*, *Kaikēyī*, etc. The custom still continues in the present ruling families where *rānīs* are so referred to. For instance, a princess of the Udaipur family, if married in the Jodhpur family, would be styled *Sisodhi mahal*.

¹² *Upapīḍāpayati* means presses down, inflicts pain (*Manu*, VI, 62; XII, 80). With the meaning 'devastating, laying waste', which the dictionaries give, the word may mean 'he sacks', but as it is contrasted with *ghātāpṛyātā* ('sacked') we take it that Khāravela only laid siege to the fortress of Rājagriha.

(L. 9) Kalpa¹ (wish-fulfilling) trees, elephants, chariots with their drivers, houses, residences and rest-houses. And to make all these acceptable (*he*) gives at a fire sacrifice (?) exemption (*from taxes*) to the caste of Brāhmaṇas. Of Arhat.....

(L. 10) (*He*) causes to be built a royal residence (*called*) the **Palace of Great Victory** (*Mahāvijaya*) at the cost of thirty-eight hundred thousands. And in the tenth year (*he*), following (*the three-fold policy*) of chastisement, alliance and conciliation sends out an expedition against **Bharatavasa** (*and*) brings about the conquest of the land (*or, country*) and obtains jewels and precious things of the (*kings*) attacked.

(L. 11) And the market-town (?) **Pithumḍa**² founded by the **Ava King** he ploughs down with a plough of asses; ³ and (*he*) thoroughly breaks up the confederacy⁴ of the **T[r]amira** (Dramira) countries of one hundred and thirteen years,⁵ which has been a source of danger⁶ to (*his*) Country (Janapada). And in the twelfth year he terrifies the kings of the **Utarāpatha**⁷ with.....thousands of

(L. 12) And causing panic amongst the people of Magadha (*he*) drives (*his*) elephants into the **Sugamgiya**⁸ (*Palace*), and (*he*) makes the King of Magadha, **Bahasatimita**, bow at his feet. And (*he*) sets up⁹ (*the image*) 'the **Jina of Kalinga**' which had been taken away by **King Nanda**.....and causes to be brought home the riches of **Aṅga** and **Magadha** along with the keepers of the family jewels of.....

(L. 13) (*He*) builds excellent towers with carved interiors and creates a settlement of a hundred masons, giving them exemption from land revenue. And a wonderful and marvellous enclosure of stockade¹⁰ for driving in the elephants (*he*) and horses, elephants, jewels and rubies as well as numerous pearls in hundreds (*he*) causes to be brought here from the **Pāṇḍya King**.

(L. 14) (*he*) subjugates. In the thirteenth year, on the **Kumārī Hill** where the Wheel of Conquest had been well-revolved¹¹ (*i.e.*, the religion of Jina had been

¹ Giving of Kalpa trees was one of the *Mahādānas* or great gifts according to Hēmadri (*Chaturvarga-chintāmani, dāna-khanda*). The tree was made of solid gold.

² *Prithu-aṇḍa* 'the big egg', probably had its origin in the physical feature of the situation of the city.

³ In the Jaina book *Āvaśyakavṛtti*, Hāribhadri, (pp. 685-87) and Hēmachandra's *Viracharitra* (pp. 170-71) it is stated that Koṇika ploughed Vaiśālī with ploughs drawn by asses. (*J. B. O. R. S.*, Vol. XIII, p. 231n.)

⁴ *saṃghāta*.—According to Pāṇini (III, 3, 76, 86; V. 1, 59; and *Hindu Polity*, I, p. 27) the form should be here *saṅgha* and not *saṃghāta*. Evidently this distinction of Sanskrit grammar is not followed by Jaina writers of the time and the regular form *saṃghāta* is used probably owing to the religious significance already attaching to the term *saṅgha* amongst them.

⁵ *Perasa-vasa-satikam*.—We take it to mean 113 years, not 1,300 years old in conformity with the interpretation of *ti-vasa-sata* above.

⁶ [*Bhāvana*=Skt. *bhāpana* (cf. '*bhāpayate*' in the *Siddhāntakaumudī* on Pāṇ. 1, 3, 68). I am adopting the former reading *janapada*. The other reading will also yield nearly the same meaning.—K. P. J.]

⁷ As the record distinguishes *Utarāpatha* from *Bharadvasa* it should be taken to refer to that part of the country of which Takshasilā was the capital as in the *Divyāvadāna* (p. 407). Cf., *Kāvyamīmāṃsā*, p. 94.

⁸ *Sugāṅga* Palace is mentioned in the *Mudrārākṣasa* (Act III) as the palace of Chandragupta Maurya. This must have been near or on the Ganges. Khāravēla's entry by means of elephants implies that it was a fortified palace.

⁹ *saṃnivēsa*..., probably *saṃnivēśayati*, "sets up an image". *Saṃnivēśa* in the sense of an image is mentioned in the dictionaries. The image called the Kālinga Jina was set up by Khāravēla. This image had been taken away by King Nanda. There is no doubt about the reading of the text and the translation of *Nanda-rāja-nīlam*.

¹⁰ *nivāsa-parisaram* = *nirvāsa-parisaram*. Compare the *Kāmandakiya* on *nirvāsa* of elephants (XV, 7). *parisara* is enclosure or stockade.

¹¹ *supavata-vijaya-chaka*: Skt. *supravṛtta-vijaya-chakra*, cf., *pavata-chako* in l. 17; *vijaya-chaka*, 'the wheel of conquest'. Evidently this was a term common to Buddhism and Jainism. That Varddhamaṇa Mahāvira preached Jainism in Kālinga is attested by the tradition contained in Jaina literature (*J. B. O. R. S.*, Vol. XIII, p. 223). The *Hāribhadrīya-vṛtti* says that Mahāvira went to Kālinga where his father's friend was ruling.

preached), (he) offers respectfully¹ royal maintenances, China clothes² (*silks*) and white clothes³ to (the monks) who (by their austerities) have extinguished the round of lives,⁴ the preachers⁵ on the religious life and conduct at the Relic Memorial.⁶ By Khāravēla, the illustrious, as a layman devoted to worship, is realised (the nature of) *jīva* and *dēha*⁷

(L. 15) bringing about a Council⁸ of the wise ascetics and sages, from hundred (i.e., all) quarters, the monks (*samaṇas*) of good deeds and who have fully followed (the injunctions) near the Relic Depository of the Arhat, on the top of the hill,⁹ with stones brought from many miles (*yojanas*) quarried from excellent mines (he builds) shelters¹⁰ for the **Sirīhapatha Queen Sindhulā**.

(L. 16) Pātālaka(?) (he) sets up four columns inlaid with beryl... at the cost of seventy-five hundred thousands; (he) causes to be compiled expeditiously the (text) of the seven-fold *Amgas*¹¹ of the sixty-four¹² (letters). He is the King of Peace, the King of Prosperity, the King of Monks (*bhikṣus*), the King of Religion (*Dharma*), who has been seeing, hearing and realising blessings (*śalyāṇas*)—

(L. 17) accomplished in extraordinary virtues, respecter of every sect, the repairer of all temples, one whose chariot and army are irresistible, one whose empire is protected by the chief of the empire (himself), descended from the family of the Royal Sage **Vasū**, the Great conqueror, the King, the illustrious **Khāravēla**.

No. 8.—KAP COPPER-PLATE OF KELADI SADASIṬA-NAYAKA; SAKA 1479.

BY N. LAKSHMINARAYAN RAO, M.A.

This copper-plate was secured by the Assistant Archæological Superintendent for Epigraphy, Southern Circle, Madras, from **Kāp** a village in the South Kanara district of the Madras Presidency in 1921 and has been noticed in the *Annual Report on South Indian Epigraphy* for that year as No. 8 of Appendix A.

¹ *arāhayaṭe* = *arghayaṭe*.

² *Chīna-vatāṇi* = *chīrna-vastrāṇi* or *Chīna-vastrāṇi*. The latter gives a more reasonable meaning.

³ *vāsā-silāṇi*.—This was formerly read as *rasā-silāṇi*. It would be the earliest reference to the white clothes later on connected with the Śrēṭāmbara sect.

⁴ *samsita* = Skt. *samsṛiti*.

⁵ *Nāvaka* = Skt. *Jñāpaka*.—*Yāpa* in *yāpa-nāvakehi* may be interpreted in view of its use in *Charaka* as “mitigating pain”, or as “supporting life” according to the *Mahābhārata*. [The translation given above is adopted now from the Jaina texts. See *above* p. 85, n. 5—K. P. J.]

⁶ The Jainas raised symbolical graves of saints and *Nishidhi* or *Nishidhi* was the name given to them. (*Cf. ante*, Vol. II, p. 274; *Ind. Ant.*, Vol. XII, p. 99).

⁷ Soul and body: these relate to the Jaina philosophy wherein the topic is very prominent (*Stevenson, Heart of Jainism*, Ch. VII).

⁸ *Saṃghayana* = assemblage.

⁹ *pābhāre* = *prāg-bharē*.

¹⁰ *nisayāṇi* = Skt. *niśrayāṇi*.

¹¹ *Amga* is a technical term meaning the sacred canon of the Jainas. If we read *Amga-satika-turiyam* instead of *Amgasatikam turiyam* then we may translate it as “the *Amgas* (in collections of) 7 and 4”. According to the Jaina tradition the *Amgas*, eleven in number, were discovered after their loss.

¹² *turiyam* = *turīyam*, “expeditiously”, or *turiyam*, “four-fold”. Jaina authors maintain that the Jaina Canon is covered by 64 letters; see *Gōmmatasāstra, Jīva-khaṇḍa* (Sacred Books of the Jains, Vol. V, 1827 edition by J. L. Jaini, Introduction, p. 13).

"The plate which is rectangular in shape is 16·4" long and 11·5" broad. At the top of the plate, just in the centre, there is a flat projection 1·4" broad and 1" high shaped into the form of an arch. There is a small hole in the arch through which passes an ordinary copper ring 1·75" in diameter. The plate has suffered a slight damage at its proper right corner at the top. But the writing on either side is in a good state of preservation. The plate with the ring weighs 230 tolas."

The language of the inscription is partly Sanskrit and partly Kannaḍa. The first six verses are in Sanskrit and the next six in Kannaḍa, the rest being in Kannaḍa prose. The Kannaḍa verses are defective both in diction and in prosody. The record is written in Kannaḍa alphabet and is rather indifferently inscribed. The letter *va* is often written like *ra* and it is not easy to distinguish *pa* from *ru* (as in *Tirumarasa* in line 17). The aspirates are generally distinguished by means of the vertical stroke at the bottom except in the case of *dha*. The secondary form of *va* is sometimes used (*vulla* in l. 36 and *vūrolage* in l. 37). With respect to orthography: (i) the consonants are invariably doubled when they are preceded by *rēpha*; (ii) the nasal is generally changed into an *anusvāra* before consonants of the same class; (iii) the consonants are freely used in place of vowels (e.g., *ye* for *e* in l. 21 and *vo* for *o* in l. 14); (iv) the letter *sa* is sometimes wrongly used for *sha* (ll. 8 and 42); and (v) double *na* is used for *ṇa* as in *arnnava* (l. 9).

The object of the inscription is to register a grant of land made by Madda-Heggaḍe, the chief of Kāp with (the consent) of the assembly (*nāḷinavaru*)¹, communal and professional guilds (*gaṇa-paṇa*) and subordinate officers,² for offerings to Dharmmarāṭha, the 15th Jina Tirthaṅkara. The gift was made at the instance of the Jaina teacher Dēvachandradēva for the spiritual welfare of his guru Munichandradēva, the disciple of Abhinava ēvakirtidēva.

The date of the record is Śālivāhana-Śaka 1479, the cyclic year Naḷa, the first *tithi* of the bright half of Kārttika, and Sunday. According to L. D. Swamikannu Pillai's *Ephemeris* the details correspond regularly to A.D. 1556, October 4, Sunday.

The inscription opens with an obeisance to Dharmmanātha which is followed by a verse in praise of the Jina-doctrine (*śāsana*). It then invokes Vardhamāna (Mahāvīra), the 24th Jina. Verses 3 to 6 describe the high spiritual attainments of a Jaina sage named Bhānu who belonged to Tintriṇī-gachchha, Kāpūr-gaṇa and Mūla-saṁgha. The Kannaḍa verses, which follow, extol the donor Madda-Heggaḍe but tell us nothing material except that he belonged to the Paṅguḷa line (*baḷi*) and that he was the administrator of the beautiful town of Kāp. (Vv. 7-12.) The inscription then states that Rāmarājayya, though he was the lieutenant of king Sadāśīvarāya, was ruling the (*Vijayanagara*) empire (ll. 18-21) and that Sadāśīva-Nāyaka (*of Ikkēri*) was the ruler of the districts of Bārakūru and Maṅgalūru. Next comes an eulogy of Madda-Heggaḍe in an elaborate prose passage which tells us that he was administering the chief town of Kāp with (the help of) the assembly, communal and professional associations and subordinate officers. Then follows the formal portion of the grant. The lands granted were

¹ *nāḷinavaru* is the corrupt form of *nāḷinavaru* which comes from *nāḷu* meaning assembly.

² *gaṇa* 'is an aggregate of kulas' *kulānām hi saṁghas* = *tu gaṇah saṁprakīrtitaḥ* (Kātyāyana, *Vṛhamitrōdaya*, p. 426; quoted by Dr. Pran Nath in his "Economic condition of Ancient India", p. 54); and *paṇa* is a sectarian division. Eighteen *paṇas* are referred to in an inscription of the 17th century, viz., *Vyāvahārikas*, *pāṇchāśas* (five seats of saints), *kumbhālikas* (potters), *tantuṭayins* (weavers), *vastra-bhēdakas* (cloth dyers?), *tila-ghātakas* (oil-millers), *kuraṇṭakas* (shoe-makers), *vastra-rakshakas* (tailors), *dēvāṅgas*, *parikeliti* (*parikeleti-rakas*), *keepers of pack-bullocks*, *gō-rakshakas* (cow-herds), *kirātas* (bunters), *rajakas* (washer-men) and *kshau*. These formed a recognised part of the local assemblies. (*Annual Report on South-Indian Epigraphy for 1918*, part II, paragraphs 84 and 85.)

situated in the village of **Mallāru** and yielded an income of 80 *varāhas*.¹ This income, it states, was to be utilized for the daily rice offering, for the *hālu-dhāre* (milk-bath?) and for feeding the assembly (of sages) on the 17th and 25th days of every month. Provision was also made for extra expenses to be incurred when either of these days happened to be a Maṅgala(ā)-trayōdaśī. Muni Charaṇaviṣṇayaḥ from Poona has kindly pointed out that, according to the colophon of the Digambara Jaina work *Yasōdharachariyā*, Maṅgala-trayōdaśī is the 13th day of the dark fortnight of Āśvina.

Sadāśiva-Nāyaka of the record was the first prominent chief of the **Ikkēri-Keladi** family which held sway over the whole of South Kanara and parts of the Mysore State from the 16th to the 18th century A. D.² Since very little is known about him, a short account of his career may be given here. He was the elder of the two sons of **Chauḍappa**, the governor of **Mallādēsa**, the younger being **Bhadrappa**. Soon after Sadāśiva succeeded his father, his first act was to reduce to submission by the order of Rāmarājayya, who was the *de facto* ruler of Vijayanagara, the kings of Bijāpur and Kalyāṇa. Immensely pleased with this achievement of Sadāśiva, the emperor appointed him governor of Chandragutti, Bārakūru and Maṅgalūru, besides bestowing on him the title of *Kōṭe-kōlāhala*³ (disturber of forts) and the privilege of affixing the term of honour *rāya-nāyaka* to his name. Sadāśiva's next expedition was against the rebellious chiefs of **Chandragutti** and **Bidar** and in recognition of his achievements he got the *biruda* of *Śatru-saptāṅgaharaṇa*. He next put down the chiefs of **Tuḷu** and **Kēraḷa** and set up a pillar of victory. Shortly afterwards, he punished the defection of two chiefs named **Yeḍava** and **Murāri** in the country of **Jālibālu** and received as a reward the title of *Yeḍava-Murāri* from the emperor. Sometime later, he marched against Mādarasa of **Baṅkāpura** and took him prisoner. By this time Sadāśiva's younger brother Bhadrappa who had gone on a pilgrimage came back. After governing the provinces conjointly with his brother for sometime, Sadāśiva nominated him as his successor with the surname **Immaḍi Sadāśiva-Nāyaka** and retired to the forest.⁴

The date of **Sadāśiva-Nāyaka** may now be ascertained. Our grant is dated in Śaka 1479 (A.D. 1556). The latest date available for him, viz., Śaka 1486, Dundubhi⁵ (A.D. 1562) is furnished by a record at Maṇigārakēri near Bārakūr. And Śaka 1473, Sādhāraṇa⁶ (A.D. 1550) is the earliest date that we have for him from his inscriptions. In śaka 1488, Kshaya⁷ (A.D. 1566) Immaḍi Sadāśiva-Nāyaka is known to have been ruling. Sadāśiva-Nāyaka must, therefore, have ceased to rule sometime between A.D. 1562 and A.D. 1566. So the period in which he flourished may be taken to be A. D. 1550-1562. The date assigned to him by Rice, viz., A. D. 1513-1545 is, therefore, not correct.⁸ Here it is necessary to say a word about **Immaḍi Sadāśiva-Nāyaka's place in the genealogy** of the Keladi family. Though a number

¹ A *varāha* is equal to 3½ rupees. But the expression used here is *doḍḍa*-(big) *varāha*, the exact significance of which is not clear.

² For an account of this family see *A. S. R.* for 1911-12, pp. 196 ff; and Rice's *Mysore and Coorg from Inscriptions*, pp. 156 ff.

³ This title as well as others that follow are found in most of the inscriptions of the Nāyakas of Ikkēri.

⁴ This account is based on *Kallōlas* 2-5, *Taranga* V of the Sanskrit Encyclopaedia *Śivatatvatratnākara* edited by Messrs. B. Rama Rao, M.A., LL.B. and Vidvān P. Sundara Śāstrī.

⁵ No. 168 of 1901, *Annual Report on South-Indian Epigraphy*, 1901.

⁶ *Ep. Carn.*, Vol. VIII, Nagar 77.

⁷ *Ibid.*, Nagar 1.

⁸ *Mysore and Coorg from Inscriptions*, table on p. 157.

of his inscriptions¹ has been discovered he has not been included in the table² of the house published by Rice, perhaps, because his relationship to other members of the dynasty was not known to that scholar. Now the work *Śivatatvaratnākara* enables us to say that Immaḍi Sadāśiva-Nāyaka was the younger brother and successor of Sadāśiva.

The sage Bhānu, who has been highly eulogised in the record, must have been one of the Jaina teachers of that name who were replaced by Lalitakīrtis in about Śaka 1286.³ Nothing is known about Dēvachandradēva at whose instance the grant was made, his *guru* Munichandra-dēva and his *guru* Abhinavadēvakīrttidēva.

With regard to the geographical names occurring in the inscription, the village Mallāru may be identified with Mallūru in the Uḍipi Taluk; **Beḷuguḷa** is the well-known Śravaṇa Beḷgoḷa in the Mysore State; **Kopaṇa** is Kopaḷ, a famous place of pilgrimage of the Jains in the Nizām's Dominions; **Parvata** is probably identical with Śrīśailam in the Kurnool District, which is one of the twelve great centres of Śaiva worship.⁴ **Gōkarṇa** is the village of that name in North Kanara; **Tirumale** is the celebrated Tirupati in the Chittoor District. **Ūjjantagiri**, which appears as Ūrjayat-giri in the Junāgaḍh inscription of Rudradāman,⁵ is the Mount Girnar on which there is an ancient temple of Nēminātha.

TEXT.

First Side.

- 1 Śrī-Dharmmanātha[nē] śaraṇu || Śrīmat-parama-gambhīra-syādvād-āmōgha-lāṃchhanaiṃ
[!*] jīyā-
- 2 t=trailōkya-nāthasya śāsanam Jina-śāsanam || [1*] Svasti Śrī sakala-jñāna-sāmrājya
-pada-rājita[h*] | Va-
- 3 rthdha(rddha)māna-Jināddhīśa⁶-syādvāda-maṭha-bhāsuraḥ || [2*] **Timtriṇī-gachchha-**
vārāsēs=sudhāmsur=jñāna-dī-
- 4 dhitiḥ [!*]sa[d*]-dharmma-sarasi-hamsaḥ pravādi-gaja-kēsari || [3*] **Kāṇūr-gaṇa-nabhō-**
bhāgē bābhāti muni-
- 5 kuṃ[ja]raḥ | ajñāna-timir-ōddhūti [h*] Śrīmān-Bhānu-mun-i[śva]raḥ || [4*] Paṃch-āchāra-
śara-dhvasta-paṃcha-
- 6 bāṇa-[śa]ra-vrajaḥ | akhamḍa-śrī-tapō-lakshmī-nāyakō Bhānu-saṃyamī || [5*] Śrīmad-Bhānu-
mu-
- 7 n-īśva[rō] vijayatē syādvāda-dharm-āmbarē śrīmad-jñāna-vinūt[na]-dīdhiti-[śa]ta-dhvast-
āṃdhakā-
- 8 ra-vrajaḥ[!*] śrī-Mūl-āmala-saṃgha-nīraja-mahā-shaṃḍēśv⁷=akhamḍa-śriyam vyāta[nva]-
n=muni-
- 9 kōka-chāru-nikaram saukhy-ārnn(ṇ)avē magnayan⁸ || [6*] **Tuḷu-dēśav=emba bhūpana poḷeva**
mahā-pa-
- 10 dakad=amte yesarg(se)guṃ nichkaṃ⁹ | dharey-oḷage **Kāpina** nagarada nelanan=ā[va] bhūpa
Madda-Heggaḍey=embaṃ || [7*]

¹ *Ep. Carn.*, Vol. VIII, Nagar 2, 3 and 4.

² *Mysore and Coorg*, p. 157.

³ Above, Vol. VIII, p. 129, f. n. 2.

⁴ Nandolal Dey's *Ancient Geography of India*, p. 193.

⁵ Above, Vol. VIII, p. 42.

⁶ Read *Jināddhīśa*.

⁷ Read *shaṃḍēśv*.

⁸ Read *mājjayan*.

⁹ Read *nichkaṃ*.

- 11 Paṅguḷa-baḷi adhipatiyanu poṁ-gaḷasade(a) nelake tānu nṛpa-kuḷa-tilakam | saṁgata-sabhevoḷu
- 12 po[ga]ḷu[m] Arigaja-jaya-Jina-pad-ābja-madhukaran=embaṁ || [8*] Bhū-dēviya mukha-kaṁnaḍi bādēṁ [hē]va]-
- 13 rgge Kāpuv=enisida nagaram ādaradiṁn=adaro[ḷg=ā] mēdini-mata-Dharmmanāthan=ena(se)guṁ Jinapam | [9*] Ā-nagara-
- 14 kk=adhipatiyūṁ Śrī-pati Tiru[ma]rasa-nṛpa [a]vanī-tilakam | vōmanadali¹ ātānuṁ vōtu karam Mukti-La-
- 15 kshmiḡ=ittam manamam || [10*] Yēn-embe Madda-Heggaḍe dāna-chatu[r]-vvidhakke tāne chintā-ratnam sanmu(nnu)ta-guṇa-gaṇa-
- 16 nniḷeyam² umnnata³ śīlavānu tūḷda [nṛ]pa-ripu-saṁhāram || [11*] Dharmadoḷam [dṛiḡha]-chittanu nirmala-
- 17 guru-bhaktiṁvalli Tirumarasa-nṛpam Dharmma-Jina-Jaina-śāsanamam voṁ-mandim tānu māḍi kriti[ya]-
- 18 mṁ(nu)=ittam || [12*] Svasti Śrī || [1*] Jayādbhudaya⁴ Śālivāhana-Śaka-varsha 1479 neya saṁda Naḷa-saṁivatsara-
- 19 da Kārttika-suddha 1 Ādityavāradaḷu Śrīman=mahārājādhirāja rājaparamēśvara satya-ratnākara
- 20 śaraṇāgata-vajra-paṁjara chatu[s*]samudr-ādhiśvara Kaliyuga- chakravartti śrī-vīrapratāpa Sadāśiva-
- 21 rāya-rāja-rājēmdra-dakṣiṇa-bhāga-bhāgya-dēvatā-saṁnibharum=appa Rāmarājayya-navar[u] yē-
- 22 ka-[chha]tradim rājya[va]nu pratipālisut=irdda kāḷadalu Bārakūru Maṁḡgalūralu Sadāsi-(śi)va-Nāyakaru
- 23 rājyavam ge[yi]t⁵=irdda kāḷadalu Tuḷu[va]-dēśa-kāminī-mukha-kamala-tilakāyamā[n]-ānādi-si-
- 24 ddha-prasiddha-Kāpi-siṁhāsan-ōday-āchal-āḷamkaraṇa-taruṇa-[t]araṇī-prakāśarum ananya-rājanya-sau[ja]-
- 25 nany⁶-[au]dāryya-vīryya-dhairyya-[mā]dhuryya-gāmbhīryya-naya-vinaya-satya-śauch-ādy-ananta-guṇa-
- 26 gaṇa-nūtna-ratn-ābharāṇa-gaṇa-kiraṇ-ōdyōtita-Bharatādi-sakala-[pu]rāṇa-purusharum=appa
- 27 Tirumalarasar=āda Madda-Heggaḍeyaru avara nā[ḷi]navaru gaṇa-paṇa-sāvantaru Kāpina rājyava-
- 28 nu pratipālisut=irdda kāḷadalu⁷ || [1*] Svasti || [1*] Śrīmad-rāya-rāja-guru-matḡdal-āchāryya mahā-
- 29 vāda-vādiśvara rāya-vādi-pitāmaha sakala-vidva[ḷi]ana-chakravarttigalum⁸ ity-ādy-anēka-bi-
- 30 rudāvali-virājamānarum Kāpūgra⁹-gaṇ-āgra-gaṇyarugaḷum=appa Śrīmad-Abhinava-
- 31 dēvakīrttidēvarugaḷa śāḷyaru Muṇiḷaṁdradēvarugaḷu [a]varugaḷa śāḷyaru Dēvacham-drādē-

¹ Read *ommanadali*.

² Read *niḷayam*.

³ Read *unnata*.

⁴ Read *Jay-ābhūdaya*.

⁵ Read *geyyuti*.

⁶ Delete *na*.

⁷ Read *kāḷadalu*.

⁸ These *birudas* are also borne by Bha ṭikaḷaṅka, the author of *Sabdānukāsana*, the Kannaḍa grammar in Sanskrit, and several other Jaina teachers.

⁹ Read *Kāpūra*.

- 32 varugaḷu tamma guru Munichamdradēvarugaḷige svargg-āpavarggakke kāraṇav-āgi
Kāpina-
33 lu dharmmavanu māḍabēk-emba chittadiṁḍa Tirumalarasar=āda Madda-Heggaḍeyara
kūṁ(kū)-
34 ḍeyu avara nāḷinavaru gaṇa-[p]aṇa-sāmaṁtara kūḍeyu Kāpina halara sahāyadim-
35 da dharmmakke voṁḍu kshētravanu koḍabēku yeṁḍu chittaisaḷ-āgi avarugaḷu dharmma-
36 pariṇāma-svarūpavane vuḷḷavar=āda kāraṇa guru-bhaktiyiṁḍa tamma simeya-
37 lu Ma[llā]r-emba [vū]r-olage paḍu[va*]ṇa dikkinalu Kaḷaṁtōpatina bāḷkeyalu agaḷi-
38 ṁḍa voḷage beṭṭina gadde l kkaṁ bija baḷḷa mū[va]ttara lekkada batta mūḍe 2 mattaṁ
a-
39 gaḷiṁḍaṁ horage Pāpinadiy=emba ga[dde] l kkaṁ bija baḷḷa mūvattara lekkada bīja
40 mūḍe 4 mattaṁ bāgila gadde l kkaṁ bija baḷḷa mūvattara lekkada mūḍe 4 gadde mū-

Second Side.

- 41 rakkaṁ bija mūḍe 10 ī bhūmigalige vuḷḷa kare mure mane bāvi halasu māvu su-
42 mbe nikkil=urkkamrdde kadiru jala pāsā(shā)ṇa saha mūla-dhāreyaṇu yera(eredu) ko-
43 ṭṭu yisikōṁḍa doḍḍa vara(ā)ha ga 80 akshā(a)radalu yeṁbhattu vara(ā)ha yī ho-
44 nnige yeraḍu beḷeyalu saha varsha l kke baha akki aṁgaḍiya horigeya
45 baḷḷa aivattara lekkada akki mūḍe 24 ī akkige naḍava dharmmada vivara Kāpina basti-
46 ya keḷagaṇa neleyalu Dharmma-Tīrtha[ṁ*]kara-sannidhiyalu madhyāhna-kāladalu nityada-
47 lu dina voṁḍakke voṁḍu baḷḷa akkiya naivēdyakku [Mu]nichamdradēvarugaḷa hesa-
48 rinalu naḍa[va] hāla-dhāregu saha akki mūḍe 10 tiṁgaḷu tiṁgaḷu tappade tiṁ-
49 gaḷalli 17 hōhāga naḍava vāra l mattaṁ ippatta-aidu 25 hōhāga naḍava
50 vāra l aṁtu tiṁgaḷalli yeraḍu vāra samadāya¹ naḍavudakke akki mūḍevu²
51 12 ī vāraṁgaḷalli Maṁgala(ā)-trayōdaśi bahāga ā Maṁgala(ā)-trayōdaśi naḍava-
52 [d=e]ṁ[du*] viśēshav-āgi yirisida akki mūḍe 2 aṁtu akki mūḍe yippatta-nāḷku
53 yī dharmmada sthaḷadalli Baḷḷaḷarige anāya sanāya salladu illa ā sthaḷa³gadalu⁴ idda
54 vokkalige biṭṭi biḍāra salladu kāṇike dese appaṇe padadalli yettu(a) salladu yeṁḍu
55 sarvvamānyav-āgi Tirumalarasar=āda Madda-Heggaḍeyaru avara nāḷinavaru ga-
56 ṇa-paṇa-sāmaṁtara saha tamma dharmma-pariṇāma-nimittav-āgi tamma svarū(ru)chi-
57 yiṁḍa guru-bhaktiyiṁḍa voḍaṁbaṭṭu barasi koṭṭa tāmbra-śāsana imt=a-
58 ppudakke sākshigaḷu ati(dhi)kāri Kāṁta-seṭṭi Chaṭa Bikra-seṭṭi Sāmaṇi Saṁkara-
59 seṭṭi Rāja-seṭṭi Bagge-[se*]ṭṭiya aḷiya Kōsaṇa Mūlūra Beḷile Birumāḷa
60 Dugga Baṁḍāri Birusāmaṇi yimt=inivara vubhay-ānma[ta*]ḍim Ma-
61 ṁgaḷūra Saṁkaḷ-Sēnabōvana baraha [*] yimt=i dharmma-śāsa[na*]kke maṁgaḷa-
62 mahā-śrī śrī śrī[!]*]Sva-dattā[d*]=dviguṇaṁ puṇyaṁ para-datt-ānupālanaṁ[!]*]
63 para-datt-āpahārēṇa sva-dattam niḥ(phalaṁ)bhavēt || Dāna-pālanayōr=mmadhv⁵
64 dānāch=chhrēyō-nupālanaṁ dānāt=svarggam=avāpnōti pālanād=achyutani
65 padaṁ || yī(i) dharmma-śāsanakke āvanān=obba Jainan=ādava tappidare Beḷugu-
66 ḷada Gaṁmaṭanātha Kopaṇada Chāṁdranātha Ūjjanṭa-giriya Nēmiśvara-
67 modalāda Jina-bimbagaḷan=oḍa(e)da pāpakke hōharu Śaivan=ādare Pa-

¹ Read *samudāya*.

² Read *mūḍe*.

³ The letter [ḷa] is written below the line.

⁴ Read *sthaḷadalu*.

68 **rvvata-Gōkarnna**=modalāḍavaralli¹ kōṭi-liṅgavan=oḍa(e)la pāpakke hōharu

69 **Vaishṇavan**=āḍare **Tirumale**=modalāḍavaralli kōṭi-Viṣṇu-mūrtivan=oḍa(e).

70 da pāpakke hōharu | Bhadrām bhūyāḥ=Jina-śāsanaśya [e] Śrī [*]

TRANSLATION.

L. 1. Obeisance to **Dharmmanātha** !

V. 1. For the translation of this verse see above, Vol. XIII, p. 22.

V. 2. Hail! The illustrious Vardhamāna, the lord of Jinas, who adorns the seat (*symbolic*) of universal sovereignty of all knowledge and who brightens the *Syādvāda* school.

Vv. 3 and 4. **Bhānu**, the lord of sages, the ray of enlightenment of the moon to the **Tim-triṇī-gachchha** ocean, the swan in the lake of pure faith (*i.e.*, Jainism), a lion to the elephant of religious disputants, the dispeller of the darkness of ignorance, the elephant among ascetics, shines in the sky of **Kāpūr-gaṇa**.

V. 5. The sage Bhānu who broke asunder the multitude of arrows of Cupid by his arrows, the five practices (*āchāras*²) is the lord of the ever prosperous Goddess of Penance

V. 6. The illustrious Bhānu, the lord of sages, the reducer of the masses of darkness to dust by hundred fresh rays of knowledge, stands victorious in the heavens of *Syādvāda* religion fostering eternal prosperity among the assemblage of lotuses in the (*lake of*) the pure **Mūla-saṃgha** and immersing sages, the herds of lovely *kōkas*, in the ocean of happiness.

V. 7. **Madda-Heggaḍe**, the ruler of the city of **Kāp**—be he ever radiant on the earth like the shining pendant worn by the king, in the form of the **Tuḷu** country.

V. 8. (*This*) jewel of the community of kings, the lord of the territory adorned by golden pinnacles, born in the Paṅguḷa lineage, a bee at the lotus feet of Jina the conqueror of Cupid, is being praised in assemblies (*of great and learned men*).

V. 9. The city known as Kāpu is the mirror of the goddess Earth; therein shines the Jinapa Dharmmanātha honoured by the world.

V. 10. The lord of that city and the favourite of Fortune, king **Tirumarasa**, the ornament of the goddess Earth, gave himself up with one mind and with great zeal to (*the service of*) the Goddess of Final emancipation.

V. 11. How shall I describe (*him*) ? **Madda-Heggaḍe** is the wish-giving gem (*chintūratna*) for the four kinds of gifts, the abode of all virtues and the vanquisher of enemy kings who have haughty demeanour.

V. 12. King Tirumarasa possessed of firm faith in *dharma* granted a Jaina-śāsana (*endowment*) with one mind and with great devotion to his spiritual preceptor and got an inscription written (*to that effect*).

Ll. 18f. Hail! Prosperity ! In the prosperous **Śālivāhana Śaka** year 1479 expired (*corresponding to*) the cyclic year **Naḷa**, on the 1st (*day*) of the bright half of **Kārttika**, on **Sunday**,

Ll. 19ff. when **Rāmarājayya**, who was, as it were, the Goddess of Fortune on the right side of the **Mahārājādhirāja**, the **Paramēśvara**, ocean of Truth, and adamant cage for those who seek refuge, the lord of the four oceans, the emperor of Kaliyuga, Virapratāpa-**Sadāśivarāya**, was protecting the kingdom under one umbrella and while **Sadāśiva-Nāyaka** was ruling (*as viceroy*) the (*provinces of*) **Bārakūru** and **Maṃgalūru**,

¹ Read °*darugaḷalli*.

² The five *āchāras* are : 1. Darśan-āchāra (to induce steady faith), 2. Jñān-āchāra (to increase knowledge), 3. Charitr-āchāra (to improve one's daily life), 4. Tapa-āchāra (to become a great ascetic) and 5. Viry-āchāra (to increase the power of one's inner self). (*Śravaṇa-Beḷgoḷa Inscriptions*, Translations p. 54, f. n. 2).

Ll. 23ff. and while Madda-Heggaḍe who had the name Tirumalarasa, an ornament to the lotus face of the damsel the **Tuḷuva** country, the young sun (*emerging from*) the eastern mountain. viz., the throne of Kāp which is from time immemorial famous in all directions, (*the incarnation as it were of*) all the ancients like Bharata¹ radiant with the rays of multitudes of ornaments of fresh gems, the collection of many virtues, which were possessed by no other man of royal descent, viz., friendliness, generosity, prowess, sweetness, profundity, policy, politeness, truth and purity, etc., was ruling the chieftdom of Kāp assisted by his assembly, communal and professional guilds and his subordinate officers;

Ll. 28ff. hail! 'Munichandradēva, the disciple of Abhinavadēvakīrtidēva, the *āchārya* of the circle of royal preceptors, the lord of great disputants, emperor of all learned men, resplendant with several such *birudas*, the foremost (*follower*) of the *Kāṇūr-gaṇa*;

Ll. 31ff. his disciple **Dēvachandradēva** requested Tirumalarasa *alias* Madda-Heggaḍe, his assembly, communal and professional guilds and his officers to grant a piece of land with the help of several (*people*) of Kāp, with the intention of instituting a charity at Kāp for the final beatitude of his *guru* Munichandradēva;

Ll. 36ff. and as they were of a charitable temperament, they, out of devotion to their preceptor, granted, with pouring of water, on the western side of the village of **Mallāru** (*situated*) within their province, in the place called Kaḷantōpatina-bālke, on the inner side of the trench, one *beṭṭu*² land requiring seed (*for sowing*) of 2 *mūḍe* of paddy calculated at 30 *baḷla*³ (*for each mūḍe*) and outside the trench one wet land called Pāpinadi requiring 4 *mūḍe* calculated at 30 *baḷla* and a *bāgila* land requiring seed of 4 *mūḍe* calculated at 30 *baḷla*; (*in all*) three wet lands requiring seed of 10 *mūḍe*, with the properties attached to them, viz., *kare*, *mure*, house, well, jack-trees, mango-trees, *sumbe*, *nikkil*, *urkkamrddie*, crop, water and stone; (*and Dēvachandradēva*) received 80 big *varāhas*—in words eighty—(*being the money income of the said lands*).

Ll. 44ff. From this gold (*was to be purchased*), at both crops, 24 *mūḍe* of rice calculated at 50 *baḷla* of the standard prevalent in the bazaar. The (*following are the*) details of the charities to be managed with this rice:

Ll. 46ff. 10 *mūḍe* of rice for the rice offering at noon at the rate of one *baḷla* each day and for the *hālu-dhāre*, conducted in the name of Munichandradēva to Dharmanātha-Tirthamkara in the lower storey of the temple at Kāp; 12 *mūḍe* of rice for feeding Jain ascetics (*samudāya*) on 2 days in the month, viz., the 17th and 25th day. If either of these days happened to be a *Mamgalā-trayōdaśī*, 2 *mūḍe* of rice were provided for the extra expenses that would have to be incurred to celebrate that *Mamgalā-trayōdaśī*. Thus the total is 24 *mūḍe*.

Ll. 53f. In this place of charity the taxes *anāya*⁴ and *sanāya*⁵ were not to be levied by the *Ballālas*⁶; the Vokkalu had no *biṭṭi*⁷ and *biḍāra*⁸ and the fees *kāṇike*, *dese* and *appaṇe* could not be raised.

Ll. 55ff. (*This is*) the copper-plate inscription recording the *sarvamānya* gift caused to be written and granted by Tirumalarasa *alias* Madda-Heggaḍe, his assembly, communal and professional guilds and subordinate officers out of their own free will and devotion to their *guru*.

¹ Bharata was the brother of Bāhubali or Gommaṭa and son of Ādinātha, the first Tirthankara. (Above, Vol. VII, p. 108 and *Mysore Arch. Rep.* for 1913, p. 5).

² *beṭṭu* is a wet land capable of yielding one crop annually.

³ *baḷla* is equal to 2 *seers* generally.

⁴ *āya* generally means income but the import of *anāya* is not clear.

⁵ *sanāya* is perhaps a mistake for *senāya*, i.e., tax paid towards the maintenance of an army.

⁶ *Ballālas* are like the *Heggaḍes*, a sect of the Bant class (*South Canara Manual*, Vol. I, p. 159).

⁷ *biṭṭi* generally means free labour.

⁸ *biḍāra* is perhaps a mistake for *birāḍa*, a tax. (See *S. I. I.*, Vol. IV, Nos. 255 and 275).

Ll. 58ff. The witnesses for this (*transaction*) are : Atikāri (*Adhikārī*) Kāmṭa-seṭṭi. Chaṭa Bikra-seṭṭi, Sāmaṇi Saṃkara-seṭṭi Rāja-seṭṭi. Baḡge-seṭṭi's nephew Kēsaṇa. Mūlūra Beḷile, Birumāḷa Dugga and Baṇḍāri Birusāṃṇi. With the consent of all these. Saṇikayī-Sēṇabhōva of Maṃgalūr wrote this. Prosperity and good fortune to this charity deed !

Ll. 62ff. Imprecatory verses.

Ll. 65ff. Any one who violates this charity, if he is a Jaina, shall incur the sin of breaking the images of Gummatanātha of **Beḷagūḷa**, Chandranātha of **Kopaṇa** and Nēṃśvara of **Ūjjan-tagiri** and other Jaina idols ; if a Śaiva, he shall incur the sin of breaking a crore of liṅgas at **Parvata**, **Gōkarṇa** etc. ; if a Vaiṣṇava, he shall incur the sin of breaking a crore of images of Viṣṇu in (*holy*) places like **Tirumale**. May there be prosperity to the *Jina-sāsana* (doctrine). Fortune !

No. 9.—SAMOLI INSCRIPTION OF THE TIME OF SILADITYA ;
[VIKRAMA-SAMVAT] 703.

By R. R. HALDER, RAJPUTANA MUSEUM, AJMER.

This short inscription was found at Sāmōlī in the district of Bhōmaṭ in Mewār and is now preserved in the Rājputāna Museum at Ajmēr. Prof. D. R. Bhandarkar has already noticed it.¹ It consists of twelve well-engraved lines of writing, covering a space of about $9\frac{1}{2} \times 10\frac{1}{2}$ ". The stone being slightly broken at the lower right corner, a portion of the inscription is missing. A few letters here and there are also indistinct. The average size of the letters is about $\frac{2}{5}$ ". On account of its importance as the earliest inscription of the Guhila family of Mewār, a detailed notice of it is given below.

The **characters** belong to the northern class of alphabets of the acute-angled type. They are almost similar to those of the Udaipur inscription of Aparājita ² of V. S. 718 (A. C. 661) though the *mātrās* of the vowels *ā*, *i*, *ī*, *u* and *ū* have different forms. The **language** is incorrect Sanskrit and the inscription is written very carelessly. As a result, the metres employed do not always stand scanning, and the meaning is also not quite clear in a few places. As regards **orthography**, the following points may be noted :—*n* is used for *ṇ* in *ripūnāṇi* (l. 4), and *ṇ* for *n* in *-jaṇānamndī-* (l. 5) and *-vāsiṇyā* (l. 9) ; the *anusvāra* is used for *m* in *-saṃbādham* (l. 8) and is redundant in *-jaṇānamndī-* (l. 5) and *=uṇṭādītanīm=āraṇya-* (l. 7) ; the *visarga* is omitted in *Harē* (l. 2), *-narapati* (l. 5) etc., while it is redundant in *-bhayāḥ* (l. 2), *-mahatarah* (l. 10) and *-janivah* (l. 4) etc. ; *sandhi* is not observed in *-jīvanam āgara*² (l. 6), *-āgata ashtādaśa-* (l. 7) and other places, while it is wrongly used in *-nivaham mavālōkya* (l. 3). Other mistakes and irregularities are pointed out in the text and the footnotes thereto.

The contents of the inscription may be summed up as follows :—After the invocation of the goddess Chaṇḍikā (ll. 1-4), the epigraph praises **Śilāditya** as the conqueror of his foes (ll. 4-5). Ll. 5-7 record that a *Mahājana* (*community*) headed by **Jē[nta*]ka** who had migrated from **Vaṭa-nagara**, started an *āgara* (? Skt *ākara*, a mine) in Āraṇyakūpagiri which became a source of livelihood for the people. In the next two lines it is said that the *Mahatara* (*Mahattara*) Jēntaka, at the command of the *Mahājana*, founded at the place a temple (*dēvakula*) of Arāṇyavāsini (Durgā), which was noted for its eighteen *vautālikas* (bards), hailing from different parts of the country and was always crowded with rich and wealthy people. The sense of the last two lines

¹ *P.R.A.S.*, W.C., 1908-09, p. 48 and *Ind. Ant.*, Vol. XXXIX, p. 189.

² Above, Vol. IV, pp. 29ff.

is not very clear, the inscription being broken at the corner. It appears, however, that the *Mahatara Jēntaka*, having seen the approach of the messengers of Yama entered fire (?) or committed suicide at the holy place of Dēbuvaka. The record ends with the date 703 *Katika* (*Ārṭtika*) *di* (?). Evidently the year belongs to the Mālava-Vikrama era and corresponds to 646 A.C.

As regards the personages mentioned in the inscription it would appear that Śilāditya was a scion of the Guhila family of Mewār. This inference is supported by the documents which have already been published—e.g., the Ātapura¹ inscription of Śaktikumāra, the inscription of Chitōr,² dated V. S. 1331, the Mt. Ābū³ inscription of Samarasirṇha. As has been pointed out by Prof. D. R. Bhandarkar,⁴ the name Śila in the Ātapura inscription stands for Śilāditya who was succeeded by Aparājita⁵ whose inscription, dated V. S. 718 (A. C. 661), has been alluded to above. Nothing of importance is recorded about the *Mahatara Jēntaka*.

Vaṭanagara of the inscription is evidently the same as Vaṭa⁶ (Vaṭapura) which has been identified with Vasantagaḥ⁷ in Sirōhī State and is about 16 miles from Sāmōlī, where the inscription was found.

This inscription is of special interest, as it enables us to rectify a mistake made in connection with the pedigree of Gōha. Col. Tod supposed that Gōha (Guhila, Guhadatta, Guhāditya, etc., the founder of the Guhila family of Mewār, to which Śilāditya of this inscription belongs) descended from the last Śilāditya (Śilāditya VI) of Valabhīpura.⁸ The Alinā copper-plate inscription⁹ of the last Śilāditya of Valabhīpura dated in Gupta Samvat 447 (A. C. 766-67), would show that he was the ruler of the Valabhī kingdom at least up to the date of his inscription, i.e., the latter half of the eighth century A. C.¹⁰ As the date of Śilāditya of the present inscription is Samvat 703 (A. C. 646), that of Gōha or Guhila, the fifth¹¹ predecessor from him, should fall in the latter half of the sixth century A. C., if an average reign of twenty years be assigned to each of the rulers preceding Śilāditya (of Mewār). Thus there is a difference of about two centuries between the reigns of Gōha (Guhila) of Mewār and the last Śilāditya of Valabhīpura. In other words, we might say that Gōha (Guhila) had established his rule in Mewār about two centuries prior to the break up of the Valabhī kingdom. Therefore Gōha could not have been the descendant of the last Śilāditya (Śilāditya VI) of Valabhīpura.¹²

¹ दस्युः खये जगति भोजसदृशनाग-

श्रीलापराजितसदृशभटेकश्रीराः *Ind. Ant.*, Vol. XXXIX, p. 191.

² *Bhāvnagar Inscriptions*, p. 75, v. 18.

³ *Ind. Ant.*, Vol. XVI, p. 348, v. 14.

⁴ *Ibid.*, Vol. XXXIX, p. 189.

⁵ Cf. note 1 above where the kings are mentioned in succession.

⁶ Above, Vol. IX, p. 12.

⁷ *Ibid.*, p. 191. Cf. also *Ind. Ant.*, Vol. XXXIX, p. 187. [But Vasantagaḥ cannot be philologically derived from Vaṭanagara.—Ed.]

⁸ *Tod's Annals and Antiquities of Rajasthan* (W. Crooke's Edition), Vol. I, pp. 253-59.


⁹ *C. I. I.*, Vol. III, pp. 171 ff. Dr. Fleet assigns the inscription to Śilāditya VII. In fact, Śilāditya II of his book (*vide* p. 41, introduction) did not actually reign at Valabhī (*Ind. Ant.*, Vol. V, p. 208 and Duff's *Chronology*, p. 309). Hence Śilāditya VII ought to be Śilāditya VI. [This is a matter of opinion only; cf. Kielhorn's *Northern List* No. 487, footnote 5.—Ed.]

¹⁰ Duff's *Chronology of India*, p. 67. *Tod's Annals and Antiquities of Rajasthan* (W. Crooke's Edition), Vol. I, p. 254, note 2.

¹¹ *Ind. Ant.*, Vol. XXXIX, p. 188, Inscription No. IV.

¹² See *Ind. Ant.*, Vol. LVI, p. 169 74.

SAMOLI INSCRIPTION OF THE TIME OF SILADITYA—[VIKRAMA-SAMVAT] 703.



HIRANANDA SASTRI.

SCALE: SIX-TENTHS.

SURVEY OF INDIA, CALCUTTA.

TEXT.¹

- 1 ओं² नमः ॥ पुनातु दिनक्रम(न्म)रोचिविच्छुरितपद्मपं(प)त्रच्छवि दुरितमाशु
 श्व(च)ण्डिकापादह³-
- 2 यं ॥ हरे(रः)शिखिशिख(भक्ते)मरस्थितमपास्तरज(जो) नूपुरा(र)भयाः(या)च्छुरित-
 दिविभाव(दिविभागं⁴) स-
- 3 दाः(दा) [i*] असुरोर(रः)स्थल(लं) शूलविनिर्भिन(न्न)मुहिरुधिरनिवहं ।
 [समा]लोक्य केसरि(रो) वहति ति-
- 4 रश्च चापलममप्येव⁴ भयमुद्विजनिवः⁵ ॥ जयति विजयी रिपूनां(णां) देव-
 द्विजगुरु-
- 5 जणा(ना)नन्दोः(नन्दो) [i*] श्रीशीलादित्यो नरपति(तिः) स्वकुलाब(म्ब)र-
 चन्द्रमा(माः) पृथ्वीः⁶ ॥ जयति वट-
- 6 नगरविनिर्गतमहाजनं(नो) जे[न्त*]कप्रमुखः(खः) । येनास्य लोकजीवनं
 आ(नमा)गरमु-
- 7 सा(त्या)दितं(त)मारण्यकूपगिरीः(री)⁷ । [i*] नानादिदेशमागत⁸ अष्टादशवेताल-
 [क*]लि(लो)कविख्यातः(तम्) ।(i)
- 8 धनधान्यहृष्टपुष्ट[प्र*]विष्टजननित्यसंवाधं(धम्)॥ एभिर्गुणैर्यु(यु)तं तत्र [जेन्त]-
- 9 कमहतर(त्तरः) श्रीभरण्यवासिण्या(न्या) देवकुलं चक्रे महाजनादिष्ट(ष्टः) ॥
 देवो च प्र[ति]-
- 10 द्वाप्यमनुपालयतु⁹ [चि]रं(रं) स च जेन्तकमहतर(त्तरः) आस
- 11 वस्त्रतद्रूता¹⁰ समवेक्ष(क्ष्य) । देववके सिधा(द्वा)यत[ने]
- 12 लनं¹¹ प्रविष्ट(ष्टः) ॥ ७०० ३ ॥ कति[क]¹² [फि] . .

¹ From the original stone.² Expressed by a symbol.³ 'स्त्रि' is engraved above the line, while 'द' of 'पाद' is engraved just below 'पा'. The sign of 'आ' in 'पा' is bent downwards and is different from other 'आ' marks.⁴ Read तिरश्चां चापलमप्येव ?⁵ Read भयमुद्विजनिवः.⁶ Read पृथ्वी. Probably the metre should be *Udgiti*.⁷ The 'प' of 'कूप' is written below the line under 'गि'. If we read 'निर्गतं' in place of 'विनिर्गतं' (in l. 6) then the metre would be *Udgiti*.⁸ Read नानादिदेशमागताष्टादश.⁹ Read प्रतिष्ठामनु.¹⁰ Read वस्त्रतद्रूतान्.¹¹ Probably स्वलनं was intended.¹² Read कार्तिक.

No. 10.—PATNA MUSEUM PLATES OF RAṆABHANJA—THE YEAR 22.

BY R. D. BANERJI, M.A., BENARES.

These plates were sent to the late Dr. D. B. Spooner by Mr. L. E. B. Colden-Ramsay, I.C.S., Political Agent, Orissa Feudatory States, in 1915-16.¹ A summary of the contents of the inscription they bear, as drawn by the late Rao Bahadur H. Krishna Sastri, was published in the *Annual Progress Report of the Eastern Circle* for that year.²

The plates are three in number and are joined together by a copper ring to which is attached a seal ($1\frac{7}{8}'' \times 1\frac{3}{8}''$) which is ellipsoid in shape and bears the legend *Śrī-Raṇabhañjadēvasya*. They are identical in size and measure $7\frac{1}{4}''$ by $4\frac{1}{2}''$ each. The first plate is inscribed on the inner side only while the remaining two bear inscription on both the faces. There are altogether fifty-seven lines of writing on these three plates, which are distributed as follows : the first plate has eleven lines, the second, eleven lines on each side ; and the third, twelve lines on each side. The writing on the whole is neat and clear but each line abounds in mistakes due both to the composer and the engraver.

The record is written in incorrect **Sanskrit**. The first eleven lines of it are in verse. They contain four stanzas of which the first three are already known from the two Baudh plates of the same prince.³ These verses contain an invocation to Śiva and the genealogy of the donor. This grant mentions two ancestors of Raṇabhañja, namely, Śilābhāñja and Śatrubhañja, while the Baudh grant (B) names only one, i.e., Śatrubhañja, his father. The object of the inscription is to record the grant of the village of Vāhiravādā which stood on the banks of the Mahānadī and was included in Dakṣiṇapali and the Khiṇjali-maṇḍala, to the god Vijaēsara (Vijayēśvara), by Mahādēvi Vijyā (Vidyā) who was the daughter of the illustrious Rāṇaka Niyārnama. The god Vijaēsara is evidently a *Śiva-linga* and the donor, the wife of Raṇabhañja himself. The document describes Raṇabhañja as a devout worshipper of Viṣṇu, the *tilaka* of the spotless Bhañja race and master of both the Khiṇjalis, who had obtained the five great 'śabdas' whose feet were worshipped by the *Mahāsāmantas* and who had obtained the blessing of the goddess Stam-bhēśvari.

Mahānadī is evidently the well-known river of that name in Orissa. Khiṇjali is mentioned in several Bhañja grants which have already been published. I am unable to identify the village Vāhiravādā.

The date of the inscription is, apparently, regular and is given in a half chronogram as *Indu-vāk-viśanti varisē* (= *Indu-vāk-vimśati-varshē*).⁴ Ordinarily this expression would denote the year 2011 of some era but the Baudh plates (B) which are written in the same script as this inscription would show that it stands for 22, *vāk* being taken in the sense of 1.⁴

I edit the inscription from the original plates which were kindly placed at my disposal by Sir Edward Gait, I.C.S., K.C.I.E., the then Lieutenant-Governor of Bihār and Orissa.

¹ *Annual Report of the Archaeological Survey of India, Eastern Circle, 1915-16*, p. 7, para. 6.

² P. 4, para. 5.

³ Above, Volume XII, pp. 323-28.

⁴ [But *vāk* (*vāch*) does not mean 'one' though it might stand for 'four' as it is supposed to have four stages, namely *Parā*, *Paścanti*, *Madhyamā* and *Vaikhari*.—The reading, however, is not certain.—Ed.]

TEXT.

[Metres :—Vv. 1-3, *Vasantatilakā* ; v. 4, *Śārdūlavikrīḍitam* ; vv. 5-19, *Anuṣṭubh* ; and v. 20, *Pushpitāgrā*.]

First Plate.

- 1 Ōm¹ Ōm svasti ' [*] Saṃhāra-kāla-luṭabhug-vikarāla-ghōra-saṃbhrānta-kiṅka-
- 2 ra-ku(kṛi)tānta-[nitānta *]-bhinnam [*] bhinn-Āndhak-āsura-mahā-gahan-ātpatra² |³
taḍ=bhē(bhai)ravam Ha-
- 3 ra-vapu[r*]-bham(bha)vataḥ prapātuḥ⁴ || [1*] Durvvāra-vāraṇa-ṇa-pratipa[ksha-
paksha-la*]kshmi-haṭha-gra-
- 4 haṇa-suprasṛita-pratāpā[ḥ |*] Bhañjan(ān)-narādhipatayō⁵ va(ba)havau(vō) va
(ba)bhu(bhū)vur=udbhūta-
- 5 yō(yē)=tra bhuva(vi) bhu(bhū)ri-sahasra-sa[m *]khyā[ḥ] : [2 *] Tēshām kulē
sakala-bhu(bhū)ta[la *]-pā-
- 6 la-mauli(li)-māl-ārchchhit-āṃghṛi-jugalō⁶ valavām⁷=nṛipō=bhu(bhū)t śrī-
- 7 Śilābhañjadēva[ḥ*] pravakṛaṭa⁸-pauruṣa-raśmi-chakra-nirdānt-āri-
- 8 hṛidayō=sya pitā nṛipasya : [3 *] Gāmbhīryēṇa payōnidhi[ḥ*]⁹ thiratayā¹⁰ bhu-
(bhū)mi[r *]=
- 9 va(ba)lēn-ā[ni *]la[s *]=tējōbhīr=yalanō¹¹=ryamā samatayā ||⁹ śubhrair=jjaśōbhi¹²
śasī(śi) [| *]
- 10 ātmā sarvva-jagana-mana¹³-sthitatayā datt-āvakāśō viyajāta¹⁴ |⁹ śrī-
- 11 Satrubhañja¹⁵ ity=atula-dhī[ḥ*] tasy=ātmaja[ḥ*] Svayammbhu(Śambhu)vata(t) ||
[4*] Anyō-nya-mada-

Second Plate : First Side.

- 12 māna-milita¹⁶-samuddhata-nṛipa-chakra-chaturaṅga-va(ba)la-kshōbha-chali(li)ta-dha-
- 13 rā-maṇḍala-gaja-turaga-khura-nirddāraṇa-prasarad-atula-dhuli¹⁷ -vitāna-saṃ-
- 14 chchhan[n*]a-jany-āṅgaṇa-ga[ja*]-skandha-vēdikā-svayammbva(yamva)r-āyāt(ta-)||⁹ pariṇīta-
ja[ya*]-lakshmi-

¹ Expressed by a symbol.

² Read °ātapatram.

³ Punctuation superfluous.

⁴ Read prapātu.

⁵ [Bhañj : narādhipatayō.—Ed.]

⁶ Read -āṃghṛi-yugalō.

⁷ Read balavān-

⁸ Read prakata-

⁹ Punctuation superfluous.

¹⁰ Read sthiratayā.

¹¹ Read =jvalanō-

¹² Read °jjaśōbhi-

¹³ Read °jagan-manaḥ-

¹⁴ Read viyaj-jātaḥ.

¹⁵ Read Śatrubhanja.

¹⁶ Read °milita-

¹⁷ Read °dhuli-

- 15 samānandita-paura-jana-ma(ā)nasaḥ śrīmad-Bhañja-bhu(bhū)patiḥ purād=Dhṛitipura-
nā-
- 16 mna[ḥ*] | Śa(Śa)rad-amala-dhavaḥ-kara-yaśaḥ-ṭaḥ-dhavalita-dig-va-
- 17 danō(naḥ) |¹ Ā(A)navarata-pravṛit[t*]a-samnārna² -dān-ā[na *]ndita-sakala-janō(naḥ) |³
- 18 Ā(A)ṇḍaja-vañ(m)sa-prabhavaḥ Parama-vaishṇava(vō) mātā-pitṛi-pāda(d-ā)nu-
- 19 dhyāta[ḥ*] Bhañj-āmala-kula-tilaka Ubhaya-Khiñjal-ā(ly-a)dhipati[ḥ *] sama-
dhigata-
- 20 pañcha-mahā-śavda(bdō) mā(ma)hāsāmanta-vandita-[charaṇaḥ*] Stambhēśvarī-lav-
dha(bdha)-vara-prasā-
- 21 da[ḥ*] |⁴ Rāṇaka-śrī-Raṇabhañjadēva[ḥ*] kuśālī [,*] Ih=aiva Khiñjali-maṇḍalē
- 22 bhaviṣyad-rāja-rāja(ā)nak-āntataṅga⁵-kumāra(rā)mātya-mahāsāmanta-vrā(brā)hma-

Second Plate : Second Side.

- 23 ṇa-pradhānā[n *] anyā[m]ś=cha daṇḍapāśika-chāṭa-bhāṭṭa⁶ -vallabha-jātīnā⁷ ||⁸ ya-
- 24 thārhi⁹ mānāyati vaidhayati¹⁰ samādisayati(śati) ch=ānyat ||¹¹ sarvvata[ḥ *]
si(śi)vam=a-
- 25 smākam | Viditam¹²=astu bhavatāḥ¹³ Dakhi(kshi)ṇa-pa(pā)li-prativa(ba)ddha |¹⁴
Mā(Ma)hānadi(dī)-vima-
- 26 la-jala-vijī¹⁵-prakṣhālita-taṭa-Vāhira(Bāhira)vāḍā-grāma[ś*] |¹⁶ chatu[ḥ *]si(sī)mā-paryanta-
[ḥ*] |¹⁷
- 27 nidhya upanidhī¹⁸-sahitam(taḥ) mātā-pitrō-yatma-jaśa¹⁹-puṇy-ābhivṛiddhayē
- 28 salila-dhārāḥ²⁰-puraḥsarēṇa vidhinā | Śrī-Vijyā-māhādēvyā²¹ |²²
- 29 [Para]ma-māhēśvarī(śvāryā) | Rāṇaka-Śrī-Niyārnama-sutā(tayā) Vijaēsarāya²³
- 30 datvā vidhi-vidhānēna²⁴ sa-vidhēya-tāmvrā²⁵-śāsana[ḥ] pratipāditō=yam || Pāram-ma²⁶.

¹ Punctuation superfluous.

² Read °samnārna°.

³ Read °antaraṅga°.

⁴ Read °bhāṭṭa°.

⁵ Read °jātyān°.

⁶ Punctuation superfluous.

⁷ Read yathārham.

⁸ Read bōdhayati.

⁹ At first this was also written dī, which was erased and ta written in its place.

¹⁰ Read bhavatām.

¹¹ Read °tīchi°.

¹² Read °nidhy-upanidhi°.

¹³ Read mātā-pitrōr=ātmanas=cha yaśaḥ

¹⁴ Read °dhārā°.

¹⁵ Read °Vidyā-mahādēvyā.

¹⁶ Read Vijayēśvarāya.

¹⁷ °na is written below the line.

¹⁸ Read tāmra°.

¹⁹ The ma is superfluous.

2 ॐ नमो भगवते वासुदेवाय ॥ अथ श्रीकृष्णार्जुनसंवादे श्रीकृष्ण उवाच ॥
 ४ दृष्ट्वा तु पाण्डुपुत्रो पाण्डुपुत्रं तस्य द्रुपदं तस्य च ॥
 ६ द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं ॥
 ८ द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं ॥
 १० द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं ॥

ii a

१२ ॐ नमो भगवते वासुदेवाय ॥ अथ श्रीकृष्ण उवाच ॥
 १४ द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं ॥
 १६ द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं ॥
 १८ द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं ॥
 २० द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं ॥
 २२ द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं ॥

ii b

२४ ॐ नमो भगवते वासुदेवाय ॥ अथ श्रीकृष्ण उवाच ॥
 २६ द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं ॥
 २८ द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं ॥
 ३० द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं ॥
 ३२ द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं तस्य द्रुपदं ॥

[illegible]

- 31 parya-kulāvatārēṇa ya(yā)vad-Vē¹ sarvva-vachanēna yathā dharma(mā)[h*]
prarōhamti ||² sā(yā)
- 32 sanē(tē)na pratinā(tanō)si sahasrēṇa virōhasi [l*] ēva[m*] vu(bu)ddhā(dhvā) par-
ārdhhañ=cha paratō
- 33 vaṁś-āvatārēṇa(ṇ=ā)py=asmad-antarōr(uṇarōdhād)=dharma-gauravā[ch*]=cha na kēnachi
smalp-āpi³

Third Plate : First Side.

- 34 vā(bā)dhā karanīyā | tathā ch=au(ch=ō)ktaṁ dharmma-sāstrēshu [||*] Phāla-kṛiṣṭā-
[m*] mahī[m*] dadyā[t*]=sa-
- 35 vija(jā)m sasya-mēdinī[m*](sālinīm) | yāva[t*] su(sū)ryakṛit-ālōka⁴ tāva[t*] = svargga⁵
mahīyatē | [|| 5*]
- 36 Vēda-vām-asmayōji⁶ vadanti rishi⁷ -dēvatāḥ[j*] bhu(bhū)mi-hartrā⁸ tath=ānyach=
cha ā-
- 37 hō mā hara mā hara [|| 6*] Yath=āpsu patitaṁ Śakra tē(tai)la-vindu[r*]=
visa[r*]ppati |
- 38 ēvaṁ bhu(bhū)mi- kṛitaṁ dānaṁ sasya(syē) sasyē prarōhati | [|| 7*] Ādityō
Varu-
- 39 ṇō Vishṇu[r*]=Vra(Bra)hmā Sōma(mō) Hutāsana[h*] | Śulapāṇis⁹=tu bhagavām¹⁰
a-
- 40 bhinandranti¹¹ bhu(bhū)mida[m*] | [|| 8*] Āsphōṭaya[m*]ti pitarah pravalgaya(ga)-
- 41 nti pitāmaha(hāḥ) | Bhu(Bhū)mi-dātā kulē jātā(taḥ) sa mē trātā bhavishya-
ti | [|| 9*] Rvvahu.¹²
- 42 bhir=vvasudhā dat[t*]ā rājānaiḥ¹³ Sagar-ādibhi[h*]¹⁴ | [|| 10*] Mā-ru(bhū)d=
aphala-samkā ya paradatēshu
- 43 pālitaṁ¹⁵ | yasya-yasya yadā bhu(bhū)mi[s*]=tasya tasya tadā phala[m*]
[|| 11*] Sva-dat[t*]ā[m*]=para-dat[t*]ā-

¹ Read *Vēd-ārtha*.² [Punctuation superfluous. Cf. above, Vol. XII, p. 324, l. 22 & f.n.—Ed.]³ Read *kēnachit svalp-āpi*.⁴ Read °lōka°⁵ Read °svarggē.⁶ Read *vēda-vāk-smṛitayōjivā*.⁷ Read *rishi*°.⁸ Read *hartrā*. [See above Vol. XII, p. 325, l. 40.—Ed.]⁹ Read *Śulapāṇis*.¹⁰ Read *bhagavān*.¹¹ Read *abhinandanti*.¹² Read *Bahubhir*°¹³ Read *rājābhi*.¹⁴ The second half of this verse has been omitted. [The second half has been put as the second half of the next verse, the latter half of which (viz., *evadānāt phalam etc.*) has been omitted.—Ed.]¹⁵ Read *bhūd=aphala-samkā vaḥ para-dat=ēti pāṇivāḥ*.

- 44 m=vā yō harēd=va(rēta va)sundharām | sa viśṭhāyā[m*] krimir=bhu(bhū)tvā
pitribhi[s*]=saha pachyatē | [12*] Hiraṇya-
- 45 m=ekam gām=ekam(kām) bhu(bhū)mim¹=apy=arddham-aṅgulam | Hara[n*]=nara-
kam=āyāti yāvad=ābhuti(bhūta)-

Third Plate : Second Side.

- 46 samplavaḥ(vaṁ) | [13*] Bhu(Bhū)mi[m*] yaḥ pratigrihṇāti yach(ś)-cha bhu-
(bhū)mi[m*] prayachchhati | ubhau tau puṇya-karmṇau
- 47 niyatau² s[v*]argga-gāminau | [14*] Haratē hārayatē bhu(bhū)-mi[m*]
manda-vu(bu)ddhi=tamā(mō)-vṛitaḥ | sa va(ba)-
- 48 ddhō vāruṇaiḥ pāsai[s*]=tirya[g*]-yōnī(ni)shu jāyatē [15*] Mā pār-
thivaḥ(va) kadāchi[d= dhi*] vra(bra)hmasvaṁ mana-
- 49 sād=api(sā api) | aṁgē padham³=abhaisva(sha)jyam ōtat hālāhalam viśam
[16*] Ā(Na) viśa[m*] viśam=ity=ā-
- 50 hu[h*] vra(bra)hmasvaṁ viśa[m*] uchyatē | viśam=ēkākinō(nam) hantī
vra(bra)hmasvaṁ putra-pautri(tra)ka[m*] | [17*] Lauha-chu(chū)-
- 51 rṇṇ-āsva⁴-chu(chū)rṇṇaṁ-cha viśaṁ-cha jarayē[n*]=naraḥ | vra(bra)hmasvaṁ tri-
shu lōkēshu kaḥ pumām(n)
- 52 jaramājvaramiśhyati⁵ | [18*] Vājapēya-sahasrāṇi⁶ y-Āśvamēdha-śatāni
- 53 cha | gavām-kōṭi-pradattāna⁷ bhu(bhū)mi-harttā na śyudhyati⁸ | [19*]
Iti kamala-dal-ā-
- 54 mvu(bu)-vi[m*]du-lōlā[m*] śriyam⁹=anuchintya shantasya¹⁰-jivitaṁ-cha sakalam=idam-
udāhṛitaṁ=cha
- 55 vudaiḥ¹¹ na hi purushaiḥ paraki(ki)ttā(rtta)yō vilōpyā[h*] | [20*] Vijaya-
rājyē samvva(samvat)sar=ēndu-vvāg-vi-¹²
- 56 santi-varisē(varshē) uktirnnāṁ¹³=cha vaṇika(k)-suvarṇpakāra-Sivaṇāga(gēna) Pāṇḍi-suta
(tēna) [1*] mahā-
- 57 rājakiya-mudrēpati¹⁴ ||

¹ Read *bhūmēr*.

² Read *niyatam*.

³ Read *param=abhai*.

⁴ Read *āśma*.

⁵ Read *jarayishyati*.

⁶ Read *-sahasrāṇi=Āśvamēdha-śatāna*.

⁷ Read *-pradinēna*.

⁸ Read *buddhyati*.

⁹ Read *śriyam*.

¹⁰ Read *manushya*.

¹¹ Read *buddhā*.

¹² [See note 4, p. 100 above—Ed.]

¹³ Read *uktirnnāṁ*.

¹⁴ [Possibly meant for **mudrayā lōchhitam=iti*.—Ed.]

No. 11.—THE KADAMBAPADRAKA GRANT OF NARAVARMAN—V.S. 1167.

By R. D. BANERJI, M.A.¹

The inscription edited below is incised on **two thick plates** of copper which weigh 15 lbs. 7 oz. and now belong to Mr. J. J. Gardar of Nepean Sea Road, Bombay, who purchased them at some place in Central India, and lent to me in November, 1920, for publication. There are two holes in each of these plates through which they appear to have been once tied together by means of two rings like many of the Valabhī plates which have now been published. There is **no seal** attached to them but a kneeling **figure of Garuḍa**, holding a snake in each hand, is incised at the proper right corner of the second plate, as is seen in the Dharampurī plates² of Vākpatirāja of V.S. 1031, the Ujjain plates³ of Bhōjadēva of V.S. 1078 and the Māndhātā plates⁴ of Jayasimha I of V.S. 1112. The plates measure $12\frac{1}{8}$ " by 8" each and are incised on one side only. In all, there are twenty-nine lines of writing on them, seventeen being incised on the first plate and twelve on the second. The average height of letters is $\frac{3}{8}$ ".

The **language** of the inscription is Sanskrit. With the exception of two verses at the beginning, two in the middle and five imprecatory stanzas at the end, the record is written in prose. It refers itself to the reign of the *Paramabhaṭṭāraka-Mahārājādhirāja-Paramēśvara*, the illustrious **Naravarmadēva**, who meditated on the feet of the *P. M. P.*, the illustrious Udayādityadēva, who meditated on the feet of the *P. M. P.*, the illustrious Bhōjadēva, who meditated on the feet of the *P. M. P.*, Sindhurājadēva.

The **object** of the charter is to register the grant of certain pieces of land given on different occasions to a Brāhmaṇa named Dvivēda Āsā(śā)dhara, son of Nārāyaṇa of the Kātyāyana-gōtra and Mādhyandina-śākhā. The gift-land consisted of twenty *nivarttanās* given by the king Naravarmadēva himself on the **12th day of the bright half of Māgha in the year 1167** (=Thursday, the 3rd February, 1110 A.D.) when this grant was issued. The charter also refers to a previous grant of twenty *halas* of land, out of which ten *halas* were given by the *Mahāmaṇḍalika* Rājadēva on the **15th day of the bright half of Kārttika in the year 1154**, four *halas* by his daughter-in-law,⁵ the illustrious Mahādēvī, probably on the same date, and six *halas* by the king himself, on the **15th day of the bright half of Pausa in the year 1159** on the occasion of the Bhūtaraprana (Bhūtarātri ?)-*parvan*.⁶ Thus, **three different dates** are mentioned in the inscription, probably, with a view to bringing together all the grants of land made to the donee up to the time when the present charter was issued. The gift-land lay in the village of Kadambapadraka which was in possession of the *Mahāmaṇḍalika* Rājya(ja)dēva and was situated in the *pratijāgaraṇaka* of Mandāraka in the Upēndrapura-maṇḍala. The measurement was called a plough measure (*hala*) which was of ninety-six rods (*daṇḍas*). The length of the *daṇḍa* in Mālwā at this period is unknown. A town named Upēndrapura is mentioned in the Ranod inscription⁷ of the Mattamayūra ascetics which seems to

¹ [This article was taken up for publication after the sad and premature demise of the author and was revised by Dr. N. P. Chakravarti, Assistant Superintendent for Epigraphy.—Ed.]

² *Ind. Ant.*, Vol. VI, pp. 51 f.

³ *Ibid.*, pp. 53 f.

⁴ Above, Vol. III, pp. 48 ff.

⁵ [Probably *vadhū* is to be taken in the sense of 'wife' here.—N. P. C.]

⁶ [The correct reading seems to be *Udagayana-parvaṇi*. According to Swamikannu Pillai's *Indian Epimeris*, the *udagayana saṁkrānti* took place on Wednesday, the 24th December, A.D. 1102, i.e., two days before the date given in the present grant.—N. P. C.]

⁷ Above, Vol. I, pp. 354 ff.

have given its name to the *maṇḍala*. I am unable to identify either Kadambapadraka or Mandāraka. The grant was issued under the sign manual of the *Mahārāja* Naravarmadēva and the *Dūtaka* of the charter was Ṭhakkura Kēsava.

TEXT.¹

[Metres:—Vv. 1, 2, 4 and 5, Anushtubh; Vv. 3 and 7, Vasantatilakā; V. 6, Indravajrā; V. 8, Śālinī; V. 9, Pushpitāgrā.]

First Plate.

- 1 Om² svasti || Śrī[r*]=jayō=bhyudayaś=cha || Jayati [Vyō]makēśō=sau yaḥ sarggāya vi
(bi)bharttri(rtti) tām | aindavīm śirasā lēkhām jagad-vijāṅga sa kṛitīm³ || [1||*]
- 2 Tanvantu vaḥ Smar-ārātēḥ kalyāṇam=amīśam jaṭāḥ | kalp-ānta-samay-ādāta-⁴taḍid-
valaya-piṅgalāḥ || [2||*] Paramabhadvā(ṭṭā)raka-Mahārājā-
- 3 dhirāja-Paramēśvara-śrī-Sindhurājadēva-vā(pā)dānudhyāta-Parana(ma)bhaṭṭāraka-Mahā-
rājādhirāja-Paramēśvara-śrī-Bhōjadēva-pādānudhyā-
- 4 ta-Va(Pa)ramabhaṭṭāraka-Mahārājādhirāja-Paramēśvara-śrī-Udayādityadēva-pādānudhy-
āta-Paramabhaṭṭāraka-Mahārājādhirāja-Pa-
- 5 ramēśvara-śrī-Naravarmmadēvaḥ kuśali || Upē[*n]drapura-maṇḍalē Mandāraka-
pratijāgarapakē Mahāmaṇḍalika-śrī-Rājya(ja)dēva-bhuyya(jya)-
- 6 māna-Kadamva(mba)padraka-grāmē samupagatāsnamasta⁵-rāja-purushān=Vrā(Brā)-
hmaṇ-āntarān⁶=[pra]tinivāsi-pattakila-janapadādī[m*]ś=cha vō(bō)- | ⁷
- 7 dhayaty=astu vaḥ samviditam || yathā śrīmad-Dhār-āvasthitair=asmābhiḥ snātvā
charācchara-gurum bhagavantam Bhavānīpatim samabhyā[r*]chchya saṁsā-
- 8 rasy=āsaratā[m] dṛiṣṭvā | Tathā hi | Vāt-ābhra-vibhramam=idam vasudh-ādhipaty-
am=[ā]pāta-mātra-madhurō vishay-ōpabhōgaḥ | prāṇās=trī | ⁷
- 9 ṇ-āgra-jala-vindu-samā narāṇām dharmāḥ sakhā param=ahō para-lōka-yānē || [3||*]
Bhramat-saṁsāra-chakr-āgra-dhār-ādhārām=imām śriyam [| *]
- 10 prāpya yē na dadus=tēśhām paśchātāpāḥ param phalam || [4||*] Iti jagatō
vina[śva]ram svarūpam=ākālayy=ādṛiṣṭa-phalam=amgikṛitya chandr-ārkk-ā-
- 11 ṛṇṇava-kshiti-samakālam yāvat=parayā bha[ktyā] | ⁸ śrī-Madhyadēś-āntahpāti-Śrīṅga-
pura-sthāna-vinirggata-Kātyāyana-gōtra-Kātyāyana-
- 12 Kapila-Viśva(śvā)mitr-ēti-trī-pravara-Mādhyamīdina-śākh-ādhyāyi-Vrā(Brā)hmaṇa-Dvir(Dvi)
vēda-Nārāyaṇa-pautra-Dīkshita-Dēvasa(śa)rmma-suta-Dvivēda-⁹Asā(śā)dharāya
- 13 uparilikhita-yā(grā)mātshaṇṇavati-parvva-daṁ(da)ṇḍa-prāmāṇyēna bhēya⁹ dvichatvā-
risan(rimśan)-mādhyakēna bhū-nivarttana-vimśati-pratya | ⁹ | Bhū-
- 14 hala-vi[m*]śatiḥ param=atō¹⁰ Mahāmaṇḍalika-śrī-Rājadēvēna chatuḥpa[m*]chāsa
(śa)d-adhika-śat-aikādaśa-samvatsarē Kā[r*]ttika-śudi-parichada-

¹ From the original plates and impressions.

² Expressed by a symbol.

³ Read *jagad-vij-āṅkur-ākṛitīm*.

⁴ Read *-samay-ōddāma-*.

⁵ Read *°gatāsnamasta-*.

⁶ Read *-ōttarān-*.

⁷ *Daṇḍa* unnecessary.

⁸ *Daṇḍa* unnecessary.

⁹ [Probably we have to read *mēyā* *viśvāntiḥ prattā*.—N. P. C.]

¹⁰ Read *pāraś* | *śat*.

संनिधौ तया सुवयया तया प्रिये मासुरासि यस्मात्तया विन वितां त्वे २
 तं मुमुक्षुमा गानः कल्याणमनिशं तदा गक्या नृसमल्लाधानं तद्विलया भिन्ना प्रमनद्वार कर्म (धारा ३)
 ४ तं जपमिथुनं तिवृषा जहिववाद्या तपनं तदा रकुनदा गजा देवा तपय मिथुन्यो सा जहिववाद्या ५
 तं यमपयस कुमदा गीजा निगज्जपमम्युरथो नदया देवा विवपादा उद्यातपरमसुतनु कर्मदा गजा विराजस ६
 ८ मातृकं कथं पद्वकुया मसचपाता सभस्यो जपसुभा द्यागा त्रयमाति निरासि पट्टि सुजनेन युता द्यावा ७
 १० यमगानुवः संनिदिता यमोश्चो मद्रायावक्षिते रत्नाभिः श्चो च यमसुगुरसरतनु र्वनो पतिरमशुचा संसा ८
 १२ गाम कन निदुस तान गणा धर्मः सुखा एव मद्यापना कल्याने सुमस्य सारस कुयनं शुभ्या मिमं शिषु ९
 १४ पुष्टि यन वदु सुषाण्या तापः परफला तिहरा ना विनू रसुपमा कल्युष्टा धृष्टलभा धिक् च द्यौः कौ १०
 १६ न किं निमकु सया च्य रण नृत्वा शोभवा द्या न भाति युगा पु रश्चान विनिमं त को ग्राध नाना न का म्य सुन ११
 १८ न पन विज्य मनि तं निपु र पमा यि दितुं स्वाद्या विवसु द्धे द्वा गस्था पा तया क्रुतसु भुङ्ग द्धे द्वा सा र म १२
 २० उपरि लिखितया माश्रस वनि पभु वड पा माथ नास्य धि व त्वा रिस माथ कल नू निव न विरा ति पभा सु १३
 २२ दन विरा तिः पप्रम तो मदा मण्ड लो क्यो गज पवन सुतः पच स देविक या ते क दूर सख त संनि क च द प्रव १४
 २४ या च उक्ता कलितु बा द्या धि म नृद त देश क ति वा म द्या मण्ड ली क्यो गज पवन व द्यौः मद्रा द्या य वृ क लान १५
 २६ त्वा म नृद न व द्यौः त वा म
 २८ पन द्या स ता स स्मा पुन १६
 ३० पर्व निरु श्रित व द नृद न षट् प व य १७
 ३२ चो ग नृद न विधा १८

निःसनीमाहलप्रतिगो

साधुषिवायासन्नगृधुय

वाभिपद्विन्नतपादेयैवा

नतश्चोसोमायंचितमुय

पाननोयद्याउक्तवदु

वन्नानिपुगनपद्विदोना

कुलकम्पुवोरमुदाह

पउपाननतसवोन्नत

चउपयैन्नासदिरणसगाहोगसोष

यरोतिद्वयराशासत्रानादकपूवकतया

यमानेनागस्मात्कचदिरण्यादिकेसाक्रुगवगा

निरुस्मयन्नवस्मादयन्नवस्मादयन्नवस्माद

मिस्मयन्नवस्मादयन्नवस्मादयन्नवस्माद

मिस्मयन्नवस्मादयन्नवस्मादयन्नवस्माद

मिस्मयन्नवस्मादयन्नवस्मादयन्नवस्माद

मिस्मयन्नवस्मादयन्नवस्मादयन्नवस्माद

तरसधोवायसमे

पुदत्रातमन्वाननि

पुदत्रातमन्वाननि

पुदत्रातमन्वाननि

पुदत्रातमन्वाननि

पुदत्रातमन्वाननि

पुदत्रातमन्वाननि

पुदत्रातमन्वाननि



सुहसौयंमदागजरीनसुवर्मदेवग्रा॥

पुनः

- 15 **śyā[m]** sva-bhuktō kasyitam vāddhāpita(?) -bhū-hala-daśakati-(bhi)rvvā¹ Mahāmaṇ-
ḍalika-śrī-Rājadēva-vadhū-śrī-Mahādēvyā pū[r]vva-kalpē ta(da)-²
16 tvān(ttā) bhū-hala-chatusṭayam | Tathā asmābhir=**ēkōnashashṭy-adhika-śat-**
i(ai)kādaśaka-samvatsarē Pausa-śudi-
17 **parichadaśyā[m]** samjāta-bhūtaraprana-parvvaṇi kasyitatvam³ (?) bhū-hala-shaṭka
[m*] | Ēvam yathāyatham bhū-hala-vi[m*]śa-⁴

Second Plate.

- 18 tiḥ sa-sīmā-triṇa-[yū]ti-gōchara-paryantā sa-hiraṇya-bhāga-hō(bhō)ga-sōparikara-sarvv-
ādāya-samētā
19 sāvā(mātā)-pitrōr=ātmanas=cha puṇya-yaśō-bhidri(vri)ddhayē śāsanēn=ōdaka-pūrvva-
katayā pradattā [| *] Tē(Ta)n-matvā tan-ni-
20 vāsi-paṭṭakila-janapadair=yathādiyamāna-bhāga-bhōga-kara-hiraṇy-ādikē(ka)m=ājñā-śra-
vana=vidhēyair=bhu(bhū)tvā sarvvam=amushmē(shmai) samupa-
21 nētavayam | Śāmānyam ch=aitat=puṇya-phalam vu(bu)ddhvā asmaḍamsajair=any[ai]r=
api bhāvi-bhōktriḥbhir=asmat-p[r*]adatta-dha[r*]mm-ādāyō=yam=anumantavyaḥ | ⁴
22 pālaniyaś=scha | Uktam cha | Va(Ba)hubhir=[vva]sudhā bhuktā rājabhiḥ Sagar-
ādibhiḥ | yasya yasya yadā bhu(bhū)mis=tasya tasya tadā phala[m] | [| ⁵ ||*]
Yān=iha
23 dattāni purā narēndrair=ddānāni dharmm-ārtha-yaśaskarāṇi | nirmālya-vānti-pratimāni
tāni kō nāma sādhuḥ punar=ādādita [| 6 ||*] Asma-
24 t-kula-k[r*]jamam=udāram=udāharadbhir=anyaiś=cha dānam=idam=abhy anumōdaniyam
Laksh[m*]jyās=taḍid-valaya-vudvuda(budbuda)-chamchalāyā dānam phalam para-
sha(ya)śaḥ-
25 paripālanam cha [| 7 ||*] Sarvvān=ēta(tān)=hā(bhā)vinaḥ pāthivēmdrān=nripō nūyō⁶
yāchatē Sa(Rā)mabhadraḥ | śā(sā)māny=ōyam dharma-sētur=nripāṇām kālē kālē
pā-
26 lanīyō bhavadbhiḥ [| 8 ||*] Iti kamala-dal-āmvu(bu)-vind[u*]-lōlām śriyam=anuchitra
(ntyā) manushya-jīvitam cha || ⁷
27 sakalam=idam=udāh[ri]ta sa vudha⁸ na hi purumai(shaḥ) para-kīrttayō vilōpyā iti ||
[9||*] Samvat 1167
28 Māgha-(ś)udi 12 [| *] Dū° || **Ṭhak[k*]ura-śrī-Kōśavaḥ** || Maṅgalam mahā-śrīḥ ||
cha śrīḥ ||
29 Svastō-yam mahārāja-śrī-Naravarmmadēvasya ||

TRANSLATION.

Om Hail! (*May there be*) prosperity, victory and success. Let that Vyōmakēśa (Śiva), who, for the sake of the creation, holds on his head the crescent of the moon which has a form like the shoot from the seed of the Universe, be victorious (1). May the matted hair of the Enemy of the god of love (i.e., Śiva) which is reddish like the fierce circles of lightning at the time

¹ [I would read sva-bhuktō(ktau) kalpitavād-dāpita[m*] bhū-hala-daśaka[m*] tīdāt (| Tathā).—N. P. C.]

² [I would read pū[r*]vva-kalp[ī]yatvāt.—N. P. C.]

³ [The reading appears to be °nū(U)dagapra(ya)na-parvvaṇi Kasyi(lpi)tatva(tvā)t.—N. P. C.]

⁴ Daṇḍa unnecessary.

⁵ Read asmad-va māsajair=.

⁶ Read bhūyō bhūyō.

⁷ Only one daṇḍa is required.

⁸ Read udāhṛitān-cha buddhvā.

of the end of the world, grant you prosperity incessantly (2).¹ The *Paramabhaṭṭāraka-Mahārāja-dhirāja-Paramēśvara* the illustrious *Naravarmadēva*, who meditated on the feet of the *P. M. P.* the illustrious *Udayādityadēva*, who meditated on the feet of the *P. M. P.* the illustrious *Sindhurājadēva*, being in good health, informs the various officers, Brāhmaṇas and others, Paṭṭakilas and inhabitants of towns, assembled in the village of *Kadambapadraka* which is being enjoyed by the *Mahāmaṇḍalika śrī-Rājadēva* (and which is situated) in the *prati-jāgarāṇaka* of *Mandāraka* of the *Upēndrapura-maṇḍala*. Let it be known to you that while residing at Dhārā, having bathed and worshipped Bhagavān (*Śiva*) the ruler of the world and the lord of Bhavānī and having perceived the worthlessness of the world—as it is said, “This ownership of the earth is (*as transient*) as clouds moved by the wind, the enjoyment of property is sweet only for the time being, lives (*of men*) are (*as unstable*) as drops of water on the points (*of blades*) of grass, Dharma is the only friend in the journey to the other world (3). Those who, having obtained this fortune which is as unstable as the sharp edge of the moving wheel of the world, do not give it (*to the needy or the deserving*), for them the only result will be great repentance afterwards (4). So, having ascertained the transient nature of the world and having agreed to the result of fate, with great devotion, twenty *nivartanas* of land, measured by the rod of ninety-six *parvas* in length (?) and forty-two in breadth (?) from the above-mentioned village² are given by us, to last as long as the sun, the moon, the earth and the sea, to the Brāhmaṇa *Dvivēda Āsādhara*, son of *Dikshita Dēvaśarman* and grandson of *Dvivēda Nārāyaṇa*, who was an immigrant from *Śringapura*, situated in the Middle-country (*Madhyadēśa*), who belonged to the *Kātyāyana-gōtra* with the three *pravaras* *Kātyāyana*, *Kapila* and *Viśvāmitra*, (and) who was a student of the *Mādhyandina-sākhā*. Also² twenty plough measures of land were given by the *Mahāmaṇḍalika*, the illustrious *Rājadēva* on the 15th day of the bright half of *Kārtika*, in the year 1154, from land being enjoyed by him and therefore retailed (? *vaddhāpita*); also ten plough measures given by the illustrious *Mahādēvī*, the daughter-in-law of the *Mahāmaṇḍalika*, the illustrious *Rājadēva*. So also four plough measures given in a previous *kalpa*; so also six plough measures given by us on the occasion of the festival of *Bhūtaraprana*(?) on the 15th day of the bright half of *Pausa*, in the year 1159. Thus, the twenty plough measures of land, in its regular order, with its boundaries, with rights of grass, *yūti* and pasturage, with rights of mining gold, of shares and easements with additional taxes and with all other income is given for the increase of the merit and fame of our own self and of our father and mother, by means of a (*copper*)-plate after a previous libation of water. Having regard to this, all shares, easements, taxes, rights of gold mining, etc., hitherto given by the Paṭṭakilas and the townsmen inhabiting the place, are to be given to him (*the donee*). (Here follow the usual formula and five imprecatory verses.) The year 1167, the 12th day of the bright half of *Māgha*. The *Dūtaka* (*of this grant was*) *Thakkura śrī-Kēśava*. My own sign manual “the *Mahārāja*, the illustrious *Naravarmadēva*.”

¹ [The passage may be translated as ‘twenty *nivartanas* of land from the abovementioned village out of the forty-two (*nivartanas*) measured by the rod of ninety-six *parvas*,’ etc.—N. P. C.]

² [The meaning of the word *kalpita* as used in the text is not certain. This term also occurs in the grants of *Bhōjadēva* of V.S. 1078 (*Ind. Ant.*, Vol. VI, p. 53) and *Yasōvarmadēva* of V.S. 1192 (*Ibid.*, Vol. XIX, p. 349). Possibly it has to be taken in the sense of ‘settled’ or ‘fixed’. I would translate ll. 14-17 as follows:—

Additional twenty plough measures of land (*were also granted*). Out of these ten *halas* of land were caused to be given in his own *bhukti* by the *Mahāmaṇḍalika* the illustrious *Rājadēva* onfrom (*his own*) settlement (?), four *halas* of land (*were given*) by the illustrious *Mahādēvī*, the wife of the *Mahāmaṇḍalika* the illustrious *Rājadēva*, from her previous settlement (?) and six *halas* of land (*are now given*) by us onon the occasion of the *udagayana-parvas* from (*our*) settlement (?).—N. P. C.]

No. 12.—TWO SINDA INSCRIPTIONS FROM BENACHAMATTI, SAKA 1088 AND SAKA 1109.

By R. S. PANCHAMUKHI, M.A., OOTACAMUND.

These two records are engraved on a stone tablet lying in front of the temple of *Īśvara* at Benachamatti in the Gajēndragāḍ State which is included in the *Ron taluk* of the Dhārwar district. They are edited here for the first time from the estampages secured by me under the orders of the Government Epigraphist for India in the year 1927-28.¹ The first inscription covers an area of 2' 9½" by 2' 3½", the size of each letter being about ½" in height. The area occupied by the second inscription is 2' 3½" by 6½" and the size of each letter is roughly ¼". The latter is the continuation of the former. I am calling them A and B respectively for the sake of convenience. They are in a fairly good state of preservation excepting that some letters of B are lost at the right corner of the lower edge where the stone is broken.

Both the inscriptions are **Kannaḍa** records of the **twelfth century** of the Christian era. In A the long *ī* is distinguished from the short one by an inside coil at the top as in *pāṭhina* (l. 1), *Chāṃdaladēvi* (l. 19), etc.; the *u*-sign at times has a short downward bend by the side of the letter with which it is connected as, for example, in *Chāvūṇḍa* (l. 10), *sudhā* (l. 11), etc.; the *ai*-sign is represented, in some cases, by a horizontal line at the bottom of the letter concerned with a curve on the left side and, in others, by a cursive upward stroke shooting from the bottom to the right end, as in *Mandara-dhairyaṃ* (l. 18), *sainyaṃ* (l. 26); the letters *m*, *y* and *v* have very often been represented by their special cursive forms as in *baḷiyim* (l. 6), *°y-aḷiyam* (l. 7), and *dēv-āyatanamumam* (l. 37) respectively; the *anusāra* is written by the side of the letter connected therewith in four places, i.e., in *yenisidam* (l. 19), *kulaṃgaḷim* (l. 29), *dēv-āyatanamumam* (l. 37) and *gāmbhīrya* (l. 42). The **Orthography** is generally free from errors. It may be noted that in A the engraver has filled up the space left at the end of lines 3, 6, 10, 12, 13, 20, 24, 35, 38, 41, 46, 49, 51 and 52 by the addition of a superfluous mark resembling the English letter S. In B the consonant *ḷa* is, in several places, wrongly used for *ḷa*, as in *pāḷa* (ll. 3, 5 and 6), *kaḷagaḷoḷu* (l. 5), etc., and the letter *te* in *Nōhilana teradi* (l. 4) is written like *ḷe*.

Excepting the first verse which is in Sanskrit, A is written in Kannaḍa poetry interspersed with prose in ll. 8, 10, 31, 32, 36-38 and 44-54. B is also composed in Kannaḍa poetry with a prose passage in ll. 10-16.

After the usual invocation to Śambhu (i.e., Śiva), A describes the ocean (ll. 2-3), the Jambūdvīpa and the Mēru mountain (ll. 3-4), the Kumtala country and its past kings (ll. 4-5) and the reigning sovereign **Kaḷachurya Bijjaṇa** who is stated to have wrested the royal glory from the (Western) Chāḷukyas (ll. 5-7). It then introduces Bijjaṇa's son-in-law **Chāvūṇḍa-nṛipa** of the Sinda family whose pedigree is given in lines 8-29. Further it tells us that, of the seven brothers—namely **Ācharasa**, **Nāka**, **Sirga**, **Dāsa**, **Dāvaṇa**, **Chāvūṇḍa** and **Chāva**—**Chāvūṇḍa** was a powerful warrior and that to Ācharasa was born **Bammarasa**, a moon to the ocean of the Sinda family. His brother was the renowned **Ācharasa (II)**, son of **Sirgha** (or Singa). To him were born **Perma** by queen **Mahadēvi** and **Chāvūṇḍa (II)** by queen **Chāṃdaladēvi**. Of **Chāvūṇḍa** it is recorded that when the **Hoysala** king met him with a huge army, the Sinda prince destroyed its general together with other opponents and captured his elephants in large numbers. Again when the **Pāṇḍya** chieftain **Kāmanṛipa** waged a war against **Chāvūṇḍa** with a view to conquer him, he met with a crushing defeat and had to flee away for life in the forest. When **Chāvūṇḍa** was ruling his territory from his capital at **Erambarage** (which is compared in lines 28-31 to the celestial **Amarāvati**, **Ayōdhyā**, **Mathurā** and **Ujjayinī**), the **Fifty Families of Telligas** extolled in ll. 32-36 constructed the

¹ Nos. 31 and 32 of 1927-28 of the Bombay Karnatak Collection. App. E. A. R. on S. I. Epigraphy, 1927-28.

temple of **Telligēśvara** in the south-east quarter of that town and made certain gifts to it after laving the feet of **Chāṇḍramauḷi-vratin** of the Lākṣa sect, the *āchārya* of **Simhēśvara-maṭha**,¹ on the day specified in ll. 46-47 during the reign of the **Kaḷachurya king Tribhuvanamalla Bijjanadēva** (ll. 44-45). Lines 38-44 give the genealogy of the *Āchārya* **Chāṇḍramauḷi-vratin** as follows :—**Vigrahēśvara-vratin**, his disciple **Yogēśvara-yati** and his disciple **Chāṇḍramauḷi-yati**.

Inscription B introduces, after prayer to the god **Telligēśvara**, mentioned above, **Vira-Bijjala** and **Vira-Vikrama** as sons of **Chāvuṇḍa** by **Sridēvi** and describes the elder of the two, namely **Vira-Bijjala**, as a great devotee of **Siva** like **Nāmbi**² and **Ohila**³ and a scholar like **Bāṇa** (ll. 1-4). His wife was **Tripurādēvi** (l. 5). His brother **Vikrama** was a munificent donor and an invincible warrior looking majestic as if he was a *Chakravartin* (ll. 6-9). In lines 10-12, the two brothers are mentioned with the usual titles, *Mahāmaṇḍalēśvara*, *Sāhasottuṅga*, etc., as ruling over **Kisukāḍu-70**, **Bāgaḍage-70**, **Keḷavaḍi-300**, **Nareyaṅgal-12** and **Kariviḍi-3[0]**. At the request of the Fifty Telligas and a certain **Murhaya-Sāhaṇi** they are stated to have granted some land to the temple of **Telligēśvara** (ll. 13-16) on the date specified in lines 12 and 13.

The details of the date given in A are :—**Śaka 1088, Vyaya, Pushya amāvāsyā, Monday, Uttarāyaṇa-saṁkrānti** and **vyatipāta**. They are not quite regular. The *Pushya amāvāsyā* ended on Sunday at 95 and the *Makara (Uttarāyaṇa)-saṁkrānti* had occurred on *Mārgaśīrsha* ba. 30, Saturday (24th December). The date intended probably was **Monday, 23rd January, A.D. 1167** which was a day of *Kumbha-saṁkrānti* in *Uttarāyaṇa*.

The details of the date given in inscription B are :—**Śaka 1109, the cyclic year Plavaṅga, chaturdaśi, Monday, Saṁkrānti**. According to *Swamikannu Pillai's Ephemeris*, *chaturdaśi* combined with a *saṁkrānti* did not fall on Monday in any of the months of *Plavaṅga*. But, for *Chaitra* śu. 14 which was a day of *Mēsha-saṁkramaṇa*, the details would be correct except for the week day which was a Tuesday. The nearest equivalent would, therefore, be **24th March, A.D. 1187**.

The two inscriptions under publication are important inasmuch as they furnish in unambiguous phraseology the genealogy of the **Sinda** princes of **Erambarage** from **Āchugi I** down to **Vira-Bijjala** and **Vira-Vikramāditya**, sons of **Chāvuṇḍa II**. Inscription A reveals for the first time that **Perma** and **Chāvuṇḍa** were the sons of **Ācharasa II** from different mothers, viz., **Mahādēvi** and **Chāṇḍaladēvi** respectively and thus supplements the information contained in the *Ron* record⁴ of A.D. 1180, where they are represented apparently as full brothers. The genealogy given in A is in perfect agreement with the one gathered from the published records⁵ of the family, although an ambiguous verse in the *Paṭṭadakal* inscription⁶ "*ātana tammaṁ Siṁga-mahī-taḷa-patiy=ātan=ātma-jātam bhuvana-khyātam negaḷd=Ācharasam*" had led *Fleet*⁷ to introduce another *Siṁgi* (II) and make him the father of **Āchugi** (II). *Dr. Barnett*

¹ This *maṭha* was, apparently, named after **Simha**, a brother of **Āchugi I**.

² **Nāmbi** probably refers to *Sundaramūrti-Nayanār* who was known as **Nāmbi-Ārūrār**. See *Tamil Lexicon* S. V.

³ **Ohila** was a great devotee of the god **Sōmanātha** in *Saurāshtra*. The story of his guileless devotion is narrated in the 43rd and 44th chapters of the *Basava-Purāṇam* of *Bhimakavi*.

⁴ Above Vol. XIX, p. 227.

⁵ So far, only eight records of the *Erambarage* branch of the *Sinda* princes are critically edited : *J. B. R. A. S.*, Vol. XI, pp. 224-30 ; 239-42 ; 247-49 ; 253-55 ; 259-66 ; 274-75 (re-edited in *Ind. Ant.*, Vol. IX, p. 96) and above Vols. XV, p. 109 and XIX, p. 227.

⁶ *J. B. R. A. S.*, Vol. XI, p. 257.

⁷ *The Dynasties of the Kanarese Districts*, p. 573. Subsequently the mistake was rectified by him in a footnote on p. 266 of *Ind. Ant.*, Vol. XXX.

who has written an excellent note on the Sinda chiefs in this journal¹, evidently followed Fleet in this respect; but, while editing the Sūdi inscription of the Kaḷachurya king Saṃka-madēva, he felt the incongruity of this interpretation and remarked "it seems to confuse Āchugi's brother Siṅgi I with the former's son Siṅghi II."² Since the Ron record edited by the same scholar states clearly that Ācharasa II was the son of Siṅga, a brother of Āchugi I, he has recognised this difference as being only a variant version of the pedigree recorded in the Sūdi inscription mentioned above. But it may be remarked that all the epigraphs, if understood properly with the aid of A, yield the same genealogy. The verse in praise of Āchugi II in A runs as follows :—

ātan=anujātan=avani-khyātaṃ śrī-Siṃha-jā-
tan=ūddhata-ripu-saṃghāta-hati-niratan=
enisidan=ātata-tējaṃ pratāpadim̐=Ācharasaṃ (ll. 13-14)

meaning that his (i.e., Bammarasa's) brother was the powerful Ācharasa who was the son of Siṃha. This statement is fully borne out by the relevant portion in the Sūdi inscription, viz.,³ *vistarīsidud=alli Siṃgarasaṃ=ātmajan=Āchugimaṇḍalēśvaraṃ* (l. 24), i.e., among them (alli) Siṃgarasa's son was Āchugimaṇḍalēśvara. As Ācharasa II is thus described in unmistakable terms to be the son of Siṃha without introducing any prince of the latter name before, excepting Āchugi (I)'s brother Siṅga, there is no other alternative but to suppose that he was the son of this Siṅga and consequently a cousin of Bammarasa I. The expression 'ātana tammam' must, therefore, be taken to mean his brother, i.e., the brother of Āchugi I.

We know from inscriptions at Arasibīḍi⁴ and Kaṭgēri⁵ that Chāvunḍa had married three queens, namely, Dēmaladēvī, Lakshmādēvī and Siriyādēvī, of whom the last two were the daughters of the Kaḷachurya King Bijjala. He begot on Dēmaladēvī, Āchugi III and Permaḍi III and on Siriyādēvī, Vira-Vijjaṇa and Vira-Vikrama, the donors of inscription B. Vira-Vijjaṇa's queen was Tripurādēvī. The portion containing the name of Vikrama's wife is unfortunately broken off.

The Sinda chiefs who played an important part in the mediaeval history of **Karṇāṭaka** began their political career as feudatories of the Western Chāḷukyas of Kalyāṇi during the last quarter of the 11th century A. D. The first prince of the family was Āchugi I who is described in the Sūdi and Niḍgundi⁶ inscriptions with the significant epithet "*āḍimaṇḍalika*," thereby indicating that with him came into being the rule of the Sinda princes of Erambarage. From the fact that he is extolled as *Vikramādityana kaṭṭid-alagu*⁷ (a sharpened sword-edge of Vikramāditya VI) and that his son Bammarasa was, according to an epigraph at Savaḍi,⁸ ruling Kisukāḍu and other provinces in the Chāḷukya Vikrama year 7 (A. D. 1083), the origin of the family as a ruling power may be placed in or about A. D. 1076, the year of Vikramāditya's accession to the throne. It is therefore not possible that the *Mahāmaṇḍalēśvara* Singappa-dēva of a Niḍgundi inscription⁹ who was governing Kisukāḍu-70 in A. D. 1076 under Bhuvanaikamaliadēva, could be identical with the Sinda prince Siṅga I as originally suggested by Fleet¹⁰ and still accepted by Dr. Barnett in his note referred to above. There is no evidence to show that Āchugi's brother Siṅga ruled at all whereas it can be definitely inferred from

¹ Above Vol. XIV, pp. 268ff.

² Above Vol. XV, pp. 109.

³ The expression *vistarīsidudalli* has been taken as one word and translated "In dwelling upon the excellence etc." See *ibid.*, p. 112. But it has to be split up into two words as *vistarīsidud* and *alli*.

⁴ No. 37 of the Bombay Karnatak Collection for 1928-29. ⁵ No. 151 of the same collection.

⁶ No. 205 of the same collection for 1926-27.

⁷ No. 35 of the same collection for 1927-28 and the Sūdi inscription mentioned above.

⁸ No. 2 of the same collection for 1927-28.

⁹ *Ibid* No. 202 for 1927-28.

¹⁰ *Dyn. Kan. Dist.*, p. 574. But he has doubted this identification in *Ind. Ant.*, Vol. XXX, p. 266.

inscription A that Bammarasa, the son and successor of Āchugi I was succeeded by Āchugi II, the son of Simha to whom there is only a passing reference.¹ Bammarasa had, according to the Pattadakal record, won the favour of the reigning sovereign, i.e., Vikramāditya VI and received from him a position of honour and rank in the State. His territory comprised Kisukāḍu-70 and Narayaṅgal-12.² He appears to have died without issue as, otherwise, the Sinda throne would not have passed to the descendants of his uncle Simha. From an inscription at Arasibīdi³ which states that *Mahāmaṇḍalēśvara* [Ava]rarasa was administering under Vikramāditya VI, Kisukāḍu-70 and Karivīdi-30 in A.D. 1087, it may be surmised that at the time of Bammarasa's death, Āchugi II was either a minor or not powerful enough to assert the rights of his family. Subsequently, however, he appears to have acquired possession of his hereditary provinces through the favour of Vikramāditya, which, thereafter, continued in his line till the end. Only three dates⁴, viz., 1113-14, 1121-22 and 1125-26 are known for Āchugi II who defeated, for his master Vikramāditya VI, the Pāṇḍya, Hoysaḷa and other rebels. Thus it may be stated that the three chiefs from Āchugi I to Āchugi II were the feudatories of the Western Chāḷukya emperor Vikramāditya VI and took a prominent part in the conquests of their overlord.

After Āchugi II, the two brothers Permāḍi⁵ and Chāvūṇḍa II held the Sinda territory as subordinates of Perma-Jagadēkamalla and Trailōkyamalla Taila III, respectively. It was during the latter's reign that the Chāḷukya dominions were usurped by Kaḷachurya Bijjaḷa who is described in A as having dragged by force the lady of the Chāḷukya sovereignty. Permāḍi is stated in his inscriptions to have vanquished Kuḷaśēkhara, besieged and decapitated Chatta pursued Jayakēśi and seized the royal power of Hoysaḷa Vishnuvardhana.⁶ The Ron inscription adds that he "captured the Hoysaḷa king's elephants as well as his treasure-waggon." In the present record (A), however, the defeat of the Hoysaḷa king's army and the capture of his elephants are attributed to Chāvūṇḍa II for whom we have several dates ranging from A. D. 1151⁷ to 1160-70. Besides, he is credited with having put to flight a certain Pāṇḍya chieftain named Kāmadēva. These events must be different from those noticed above⁸. For, it is natural that the Hoysaḷa prince should again have risen in vengeance against the declining power of the Chāḷukyas and tried to assert independence and that the Sindas, as faithful servants of the Chāḷukyas, should have checked his aggression on the battle-field. And Kāmadēva, evidently Kāmadēva of Uchchangi, otherwise known as Vijayapāṇḍyadēva, who succeeded his brother Vira-Pāṇḍya sometime after A.D. 1148⁹ and lived on up to at least A.D. 1189¹⁰, was for a longer period a contemporary of Chāvūṇḍa II than of his elder brother Permāḍi. It is worth noticing that Chāvūṇḍa, who had abstained from acknowledging the Kaḷachurya suzerainty in his earlier records dated before A. D. 1163,¹¹

¹ Not a single known inscription has described Simha independently except as the father of Ācharasa II. This would suggest that he never enjoyed any power.

² Savaḍi inscription referred to above.

³ No. 35 of the Bombay Karnatak Collection for 1928-29.

⁴ *Ibid* No. 219 for 1926-27, *J. B. R. A. S.*, Vol. XI, p. 247 and No. 218 of the B. K. collection for 1926-27.

⁵ An inscription at Kōḍikop bearing an impossible date in Śaka 872 introduces this prince as a feudatory of Vikramāditya VI. Since we know that his father Āchugi was living in A. D. 1125-26, the last year of Vikramāditya, it may be presumed that he ruled conjointly with his father or his father must have died in that year so that Permāḍi, who succeeded him, could become Vikramāditya's feudal chief.

⁶ *Dyn. Kan. Dist.*, p. 575.

⁷ No. 37 of the Bombay Karnatak collection for 1928-29.

⁸ These exploits of Chāvūṇḍa do not find mention in other records of himself or of his sons. Excepting the defeat of Kāmadēva which is nowhere ascribed to Permāḍi, the rest might as well be supposed to have been achieved by Chāvūṇḍa in conjunction with his elder brother as the latter is known to have accomplished similar acts.

⁹ *Mysore and Coorg from Inscriptions*, p. 151.

¹⁰ *Dyn. Kan. Dist.*, p. 466.

¹¹ No. 147 of the B. K. collection for 1928-29. See also *Dyn. Kan. Dist.*, p. 462.

though it was well established by then, had begun to recognise it by A. D. 1167, as is evident from the preamble to the grant portion of inscription A. It appears that he was holding the reins of government in conjunction with his sons Āchugi and Permādi in A. D. 1163 when the Paṭṭadakal inscription was engraved. It is not known under what circumstances the Sinda chiefdom passed to the sons of Siriyādēvi after the death of Chāvunḍa II.

Chāvunḍa's rule must have ended in A. D. 1169-70, for we find his sons Vira-Bijjaṇa and Vira-Vikrama ruling over Kisukāḍu-70, Bāgaḍage-70, and Keḷavaḍi-300 in A. D. 1170 as recorded in the Aihole inscription¹ dated in Virōdhin, corresponding to the 94th year of the Chāḷukya Vikrama era, whereas an epigraph from Hirēmaṇṇūr² bearing the date Śaka 1091 (A.D. 1169) introduces Chāvunḍa as a donor of some gift. Further the Harti inscription³ of Vira-Bijjaṇa dated in the cyclic year Vijaya falling in his 7th year fixes the date of his accession sometime in Virōdhin. Vira-Bijjaṇa and Vira-Vikrama appear to have **ruled conjointly** as is shown by the preamble to inscription B which states that both the princes were ruling together from their capital at Erambarage. This is corroborated by other inscriptions also.⁴ There are, however, a few epigraphs⁵ which were issued by the two brothers independently of each other. But this does not vitiate the above conclusion inasmuch as joint rulers could make donations separately as well. There are reasons to hold that the **two princes** were **very young** when they were **invested with power**. Two inscriptions at Nidgundi⁶ with dates in Śaka 1094 (A. D. 1172) and Śaka 1096 (A. D. 1174) style them as *kumāras* and introduce *paṭṭamahādēvi* Siriyādēvi as making some gifts in conjunction with her two children. This seems to indicate that their mother Siriyādēvi was actually governing the Sinda territory as **regent** during their minority.⁷ That they were children then, as said above, is rendered quite probable by a record⁸ of A. D. 1220 in which year Vikramāditya was still holding the Sinda dominions under the Yādava Siṃgaṇaḍēva, after a rule of not less than fifty years.

It is significant to note that inscription B **does not mention any overlord** but proceeds to describe the two brothers straightaway as if they were independent rulers. After the Kaḷachurya usurpation which lasted for twenty years, the Sindas retransferred their allegiance to the Chāḷukyas under Sōmēśvara IV, who revived his ancestral sovereignty in A. D. 1183. Sometime after this date, the Chāḷukya territory appears to have again become a prey to the constant attacks of the Yādavas of Dēvagiri on the north and the Hoysaḷas of Dvārasmudra on the south. During this period of turmoil, the **Sinda princes** must have **declared independence**. This is indicated by the expression "*Chakravarti-padavi-patiy=inn=itan=enal=esevan=urvvi-khyāta-yasam Vira-Vikramāvanipālām*" in inscription B which means that the powerful Vikrama was then the fit person to bear the title of *Chakravartin*. But this independence did not continue long, for we find from the Amnigere and Gadag inscriptions of Yādava Bhillamaḍēva, dated respectively in A. D. 1189 and 1191, that the Yādava king held the country south of the Malaprabhā and Kṛishṇā as well as the northern provinces,⁹ thus precluding the possibility of the Sindas remaining free and unassailed. Since Jaitugi counts his reign from the latter date, **Bhillama** must have died in that year probably in an encounter with Vira-Ballāḷa. This is proved by the existence of Vira-Ballāḷa's record at Gadag

¹ J. B. R. A. S., Vol. XI, pp. 274. It was re-edited more correctly in *Ind. Ant.*, Vol. IX, p. 96.

² No. 4 of the Bombay Karnatak collection for 1927-28.

³ No. 57 of 1926-27 of the same collection.

⁴ *Ibid.*, No. 221 of 1926-27.

⁵ Ron and Harti inscriptions mentioned above.


⁶ Nos. 208 and 205 of 1926-27 of the Bombay Karnatak collection.

⁷ *Ibid.*, No. 35 of 1927-28.

⁸ *Dyn. Kan. Dist.*, p. 504.

itself dated in A. D. 1192 and by the statements contained in his Anṇigere inscription¹ of A. D. 1202 representing Bhīllama as having been killed in the fight. The Harihar inscription of his son Narasimha II adds to his father's conquests the capture of all the strongholds between Soratūr, Erambarage, Kuṛugōḍ, Gutti, Bellittage, etc.² From this it is evident that Vira-Ballāḷa had successfully wrested from the Yādava king some portion of the territory which the latter had taken from Sōmēśvara IV, subjugated the Sindas of Erambarage and made them pay homage to his banner. The Yādavas, however, were not keeping quiet all this while. They were biding time to reclaim the lost country. Jaitugi's son Siṃgaṇadēva who carried his conquests far and wide led an expedition against the Hoysaḷas during the last days of Vira-Ballāḷa and snatched back from him the portion of land lying to the south of the Kṛishṇā and Malaprabhā and even extended his arms farther south as is proved by his inscription at Baḷagāmve³ in Mysore, dated in A. D. 1215. This event must have taken place in or about A. D. 1210 for, an epigraph at Dōṇi⁴ states that the sixteenth year of Siṃgaṇadēva's entry into that tract corresponded to the cyclic year Vijaya (A. D. 1226). This statement proves that the Yādavas were once again in possession of the territory under contest which must have included Kisukāḍu-70 of the Sindas. That the Sinda chiefs became their subordinates and continued to acknowledge their suzerainty till the end is clear from a stone record at Kaḷakappanagudda⁵ in which the Sinda Vikramāditya figures as a feudatory of Siṃgaṇadēva in the latter's 21st regnal year falling in Vikrama, i.e., A. D. 1220. Nine years later, we find Mahāpradhāna Vāsudēva-Nāyaka ruling under the orders of Siṃhaṇa, Erambarage "which had caused itself to be called the capital of Kisukāḍu-70"⁶. Presumably the Sinda prince Vikrama had passed away between A.D. 1220 and 1229 and his territory was then annexed to the Yādava kingdom, thus ending the rule of the Sinda chiefs after a glorious career of about 150 years.

From the facts set forth in the foregoing pages, a revised genealogy of the Sinda princes with dates is reconstructed below for the sake of ready reference.



¹ No. 193 of the Bombay Karnatak collection for 1928-29. Among the descriptive epithets applied to Vira-Ballāḷa in this record occurs the expression "Bhīllama-bala-jaladhi-baḍavāṇaḷam".

² *Dyn. Kan. Dist.*, p. 504.

³ *Dyn. Kan. Dist.*, p. 505.

⁴ No. 79 of 1927-28 of the Bombay Karnatak collection. See also *A. S. R.*, 1927-28, p. 141.


⁵ No. 35 of the Bombay Karnatak collection for 1927-28.



⁶ No. 200 of 1926-27 of the same collection.

The following places and subdivisions are mentioned in the two records :—the celestial Amarāvati, Āyōdhye, Madhure, Ujjayinī, **Erambarāpuram**, **Kallūru**, **Kisukādu-70**, **Bāgaḍage-70**, **Keḷavaḍi-300**, **Nareyaṅgal-12** and **Kariviḍi-30**. Of these **Kallūru** is the modern village of that name near Mushigēri in the Ron taluk of the Dhārwar district. On **Kisukādu-70** and **Kariviḍi-30** see Fleet's exhaustive note in *Indian Antiquary*, Vol. XXX, pp. 259 ff. **Bāgaḍage-70** comprised a portion of the modern **Bāgalkot** taluk in the Bijāpur district with **Bāgaḍage**, i.e., **Bāgalkot** as its chief town. **Keḷavaḍi-300** derived its name from its chief place Keḷavaḍi which is at present a small village in the Bādāmi taluk of the Bijāpur district. **Nareyaṅgal-12** was a small circle of villages with its headquarters at **Nareyaṅgal**, i.e., the modern **Naregal** in the Ron taluk of the Dhārwar district. The remaining places are too well known to require any remarks.

TEXT.


A

- 1 Namas=tuṅga-śiraś-chumbi-chandra-chāmara-chāravē | trailōkya-nagar-ārambha-mūla-
stambhāya Śambhavē || [1||*] Vṛi || Viluṭhat-pāṭhina-puchchha- sphurita-
- 2 gurutar - āsphālana - sphāra-kōḷāhaḷa-niryyad-dhairyya-nakra-krama-kashaṇa-nishamṇ - ōru-
nirēbha-bhikṣich-chaḷa-hast-āghāta-masta-
- 3 prakāṭhiṇa-kamaṭha-bhrānti-nirmukta-mukt-āviḷa-vichī-samchayam kang=esedudu
bahaḷa-dhvāna-raudram samudram || [2||*] Tad-vārdhhi-chāru-pa-(S)
- 4 rikhā-sadvalayitām=enisi nāḍe sogayisuvudu Jambūdvīpa-v=alli chāru-kubhṛid-
varan=ene nāḍe Mēru-giri ramjisugum || [3||*] Ā Kanak-ādri-
- 5 ya teṅkal=Bhū-kāmtā-kuntaḷ-ōpamam Kuntaḷav=amt=ā kām̐ta-vishaya-rakshakar=ī
Kaliyugadalli puṭṭidar=**Chālukyār** || [4||*] Ā Chālukya-mahī-
- 6 śarim̐de baḷiyim̐ durvittaram̐ geldu dhātri-chakram̐ nere bam̐pnisal-bhujā-
baḷ-āvasṭambhadim̐ Kuntal-ōrvvī-chaṁchach-chatur-āṁganā-kacha-samākarsā(S)-
- 7 graham̐ **Bijjapa-śrī-chakrēśvaran**=opputirpan=adaṭam̐ vidvisṭa-viddrāvaṇam̐ ||
[5||*] Tach-chakravarttiy=alīyam sach-charitam̐ viśada-kīrtti **Chāvum̐ḍa-nripam̐**
nichchaṭa-
- 8 gali Kali-kāla-viyach-charan=ene pesarin=esevan=ī vasumatiyoḷ || [6||*]
Ā mahānubhāvan=anvay-āvatārav=em̐t=em̐ḍade  Āchu-
- 9 gi-bhūmi-pālana sah-ōdarar=apratima-pratāpa-bhūp-āchaḷa-vajra-dam̐dar=ene Nāka-
nripam̐ nripa-tuṅga Sim̐gan=ātm-ōchita-vikra-
- 10 mam̐ negaḷda Dāsarasam̐ kali Dāvaṇam̐ jaya-śrī-chatura-priyam̐ vibhu
Chavun̐darasam̐ guni Chāva-bhūbhujam̐ || [7||*] Avarolage || Ahit-ōdyad(S)-
- 11 baḷa-jālakam̐ kadanadoḷ=māṛāntu tāgal=mahā-mahimam̐ sūlige-goṇḍu kōpad-odaviṁ
kom̐d=ikki vidvisṭaram̐ mahiyoḷ=tāḷdi sudh-ām̐-
- 12 su-nirmmaḷa-yaśaḷ-śrī-kāmtiyam̐ saṁtatam̐ mahaniyam̐ kali **Chavum̐ḍa-bhūpan**=
esevam̐ śrī-Sim̐ḍa-vaṁś-ōdbhavam̐ || [8||*] Ka || Avarolag=Āchara-sam̐g=u
(S)-
- 13 dbhavidisan=adhika-pratāpa-nidhi jaya-lakshmi-pravaṇam̐ **Barhmarasam̐** kīrtti-viḷāsam̐
Sim̐ḍa-vārdhhi-varddhana-chaṁdram̐ || [9||*] Ātan=anujātan=avani-khyātām̐(S)
- 14 śrī-Sim̐ha-jātan=uddhata-ripu-sam̐ghāta-hati-niratan=enisidan=ata-tējam̐ pra-
tāpadim̐d=Ācharasam̐ || [10||*] Ant=enisid=Ācha-bhūpana kām̐te
- 15 dayā-vaṁte bhāgya-vaṁte nitāmtam̐ sānte naya-vaṁte sat-kuḷa-vaṁte
Mahādōviy=em̐ba pesarim̐d=esevaḷ || [11||*] Vṛi || Ācha-mahibhujam̐gav-
esev=ā

- 16 **Mahadēvigav**=udgha-vikramam khē-chara-kirtti sambhavisidam kali **Permma-**
mahidharām manōjñ-ācharaṇam raṇ-ōddhata-viruddha-nṛipāḷaka-jāḷa-bā-
- 17 **likā-lōchana-nirggaḷad-vimala-lōḷa-jal-āviḷa-saṅgar-āṅgaṇam** || [12||*] **Ā** **Permma-**
bhūpan=anujam rūpa-Manōjam manōjña-guṇa-gaṇa-yu-
- 18 **ktam vēpita-ripu-nṛipa-hṛiday-ālāpaṇ** **Chāvumḍa**-maṇḍal-ēsam negaḷdam || [13||*]
Mandara-dhairyaṇ ripu-nṛipa-bṛimda-śiraḷ-kamduk-ālī-kēḷi-ka-
- 19 **ḷitam Chāṇḍaladēvi-sutan**=amaḷ-ēmd-ūjvaḷa-kirttiy=enisidam Chāvumḍam || [14||*]
Munis=ābhīḷa-nṛipāḷa-mēgha-paṭaḷa-prōtsāra-jham-
- 20 **jhāṇiḷam vanadhi-prāvṛita-kirtti** sāmḍra-vikirat-kālēya-pāp-āndhakāra-nirās-ōjvaḷa
chamḍra-didhiti lasad-dānam budha-brāta(S)-
- 21 **dausthya-nag-ōdbhēdana-vajrav**=āgal=eṣevam **Chāvumḍa-bhūpālakaṇ** || [15||*]
Samar-ōdyad-baḷa-**Hoysaḷa-kshitipa**-sēn-ānikam=ōmd-āgi
- 22 **vikramadiṇ tāge** parākrama-krama-yutam Simḍ-ānvay-āmbhōdhi-chamḍraman=
ērvvaṭṭi tad-iśanam maledaram koṇd=ugra-matta-ē-
- 23 **bha-saṅghaman**=ādam piḍidam pratāpa-tapanam **Chāvumḍa-bhūpālakaṇ** || [16||*]
Vṛi || Bhūruḷaḷam śaraṇ-buguvarām bhayad=uṭṭudan=ikki nilu-
- 24 **varaṇ vāruvadimḍ-iḷā-taḷake** vapparan=āmt=iṛiyalke pēsi sad-vīraṇ=eyde
koṇd=eṣeva miṣegaliṇ huri-gomḍa gaṇḍa perḍāra-
- 25 **man=āḷda** Simḍa-kuḷa-maṇḍananoḷ paḍiy=appa gaṇḍar=ār || [17||*] **Nija-**
chāturbbaḷa-garbbadiṇ bhujā-baḷa-prakshōbhadiṇ **Pāṇḍyan**=āji-jay-ā-
- 26 **kāmksheyin**=eyde vaṇḍu kaḍupimḍam tā[ge] **Chāvumḍa**-bhūbhujan=ēk.
āṅgade gelda sainyaman=adam kaṇḍ=uṭṭudam biṭṭu nirrvijayam
- 27 **Kāma-nṛipāḷan**=ōḍidan=avam beṇḍoṭṭu kāl-vaṭṭeyim || [18||*] 
- Vaṇḍita[v=I]mḍranimḍav=Amarāvati Rāghavanimḍ=Ayōdhya
- 28 **Gōvimḍanin**=ujvaḷan-Madhure Guttanin=Ujjayanī-puram Maruṇ-naṇḍananimḍe
Hastinapuram neṇe raṇjisuv-ante saṇtataṇ **Simḍa-Chavumḍa-**
- 29 **bhūbhujanin**=oppaman=āḷdud=**Eraṇbarāpuram** || [19||] **Dēvakuḷamgaḷim** [va
vadhū]kuḷa-harmmya-śataṇgaḷim mahidēva-grihaṇgaḷim Dhana-
- 30 **pati-prabha-vaiśya-kadamba-gēhadim** pāvanavat-tapō-vana-tapō-dhana-śālegaḷimḍe
kaṇḍe-vaṇḍ=i vaṣudh-āgradoḷ sale virājisut-irppu-
- 31 **d=Eraṇbarāpuram** || [20||*]  **Alli** || **Telligar**=ayvatt=okkal=sal-lalita-guṇ
āḍhyar=Abhava-pada-yuga-vimal-ōtphulla-saras(i)-ja-ṣaṭ-padar=ullasi-
- 32 **ta-sit-ābhra-kirtti-vallabhar**=enipar || [21||*] **Mattam** || **Vṛi** || **Śaraṇ-āyāt-ādri-**
rakṣhā-kshama-saradhigaḷ=uddamḍa-vidviṣṭa-dusṭ-ōtkara-
- 33 **kāmtāra-pradāha-prabaḷatara-mah-ōgr-ānaḷar**=Sambhu-śumbhaḥ-charaṇ-āmbhōjāta-guṇjat-
su-ruchiratara-rōḷamba-
- 34 **reṇḍ=emḍu** bhāsavad-dharey=sivatt=okkalam takkaran=atīśayadiṇ kirttikum
mechchi nichchaṇ || [22||*] **Sujana-stutyar**=ssu(su)-satya-bratar=aparimit-
āchāra-sad-dharma-
- 35 **vaṇmmar=ṇṇ(ṇṇ)i**ja-kāmt-ānanta-mōḍa-pramudita-vimala-svāntar-ātmiya-dēva-dviḷa-pād-
āmbhōja-pūjā-nirataṇ=enute kay-vā(S)-
- 36 **radim kūḍe** baṇḍan-brajev=sivatt=okkalam baṇṇipud=avanī-talam mechche
e-ānamadadiradāṇ || [23||*] **Va** || **Amṭu** pogaḷte-vaḍed=sivatt=okkaligaḷ-ēka sṭha-
- 37 **r=ig=iḷi**=**Eraṇbarāpurad-iśāna**-dīg-viḷhāḍadoḷ **Telligēvara-dēvara** pratish-
ṭheyam tad-dēv-āyatanamumam māḷiḍidar=ā sthānad=ā-

- 38 **chāryyar=appa** **Chāṁdramaulidēvara** gurukuḷ-ānvayav=em̐t=em̐dade || Maṁ-
neya-vaḷiyol=ati-stuta=um̐nata-yasa(S)-
- 39 n=āsrit-āśrayaṁ kali-kāl-ōtpaṁna-Lakuḷīsan=enipaṁ samnuta-mati **Vigra-**
hēśvara-brati-tiḷakaṁ || [24||*] Tat-pāda-kamaḷa-sēvā-tatpa-
- 40 ran=anavadya-charitan=Aṁgaḷa-kudhar-ō(r)dyat-pavi **Yōgēśvarayati** sat-puṁnyaṁ
Lakuḷ-āgam-āmbuja-mitraṁ || [25||*] Ā munimukhyana
- 41 śishyaṁ bhū-mahitaṁ naishṭhik-āgra-gaṇyaṁ vibudha-stōma-sura-bhūjan=
Aṁgaḷa-sāmaḷa-gaḷa-vaīri **Chāṁdramauli-yatim̐draṁ** || (S) [26||*]
- 42 Nija-dān-ōṁnati kalpa-bhūja-tatiyaṁ mūla-brataṁ stutya-Vāyu-janaṁ sat-
yav=anim̐dya-Satyatapanam̐ gāmbhīryav=ambhōdhiyaṁ tṛi(tri)-jagad-byā-
- 43 pta-yasaṁ śaś-āṁka-ruchiyaṁ kiḷ-māde rārājipaṁ vijit-ōdyat-Kali
Chāṁdramauli-yatipaṁ vidvaj-jan-aik-āśrayaṁ || [27||*] 
- 44 Vachana || Svasti [||*] Samasta-bhuvan-āśrayaṁ Śrī-Prithvī-vallabha ma-
hārāj-ādhirāja paramēśvara paramabhāṭṭārakaṁ **Kaḷachuriya-kula-**
- 45 **kamaḷa-mārttaṁdam̐** kadana-pracham̐dam̐ nām-ādi-samasta-prasasti-sahitaṁ
śrī-mat-Tribhuvanamalla **Bijjanadēvara** vijaya-rājyam=u-
- 46 ttar-ōttar-ābhivrid̐dhi-pravard̐dham̐nam=ā-cham̐dr-ārka-tāraṁ saluttam=ire [||*]
S(ś)aka-varsha 1088-neya Byaya-sam̐vatsarada Pushyad-am̐vāsye (S)
- 47 **Sōmavārav=uttarāyana-sam̐krānti** **hyatipātad=am̐du** śrī-mat-**Telligēś-**
varadēvargge **Telligar=ayvatt-okkalgaḷ=ēka**-stharaḷgi **Sim̐hēśva-**
- 48 rada maṭhad=āchāryyar=appa **Chāṁdramaulidēvara** kālaṁ karchchi
dhārā-pūrvvakam̐ māḍi biṭṭ-āyav=em̐t=em̐dade [!*] **Dam̐din=okkalum̐** taḷad=o-
- 49 **kkalum̐** devasav=aḷav=em̐ne gānadalli soḷasav=eraḍu dēva-gānad-okkalalli
devasav=aḷav=em̐ne soḷasav=om̐du chaitra-pavitraṁga(S)-
- 50 joḷu gānadalli viṣav=aidu gānaṁ meṭṭuvaralli viṣav=aidu maṭhakke
bam̐d=abhyāgataralli naḍava manushyar-āhāra-dānakke tiṁgaḷiṁg=okka-
- 51 lgaḷoḷ joḷa koḷagav=om̐du Kallūra batṭeyim̐ paḍuvala.....nam̐d=iṇuva
tōm̐taṁ mattar=om̐du **Dipāvāḷiya** parvvadalli(S)-
- 52 y=okkalol=em̐ne māṁsav=om̐du maḷigeyoḷag-ainūrvvar=Svāmigaḷ biṭṭ-āyaṁ hom̐ge
koṭṭavaralliy=aḍakey=om̐du koṁḍava(S)-
- 53 ralliy=aḍakey=om̐du enisida dhoregaḷalli pratyēkav-aḍakey=om̐du tam̐-
buligarv=viṭṭ-āyaṁ bham̐ḍig=ele nūru hē-
- 54 riṁge nūru tale-voreg=aiy(ai)vattu dēvara mun̐dan=aṁgaḍiy=eraḍu ||

B.

- 1  Śrī-vidita-Telligēśvaradēvaṁ manam=osedu kuḍuge rāja-śrī-
- 2 yaṁ [!*] bhū-vinuta-**Vira-Bijjaladēvaṁgam̐** **Vira-Vikrama-kshatipaṁgam̐**
[||1||*] Nuta-guṇa-**Chāvum̐ḍ-ōrvvī**-patigaṁ **Siridēvigaṁ** kumār=kkam̐-
[num̐] [!*] gatiyum=e-
- 3 ne puṭṭidar=b(h)bhūpati-Bijjala-**Vira-Vikram-āvanipāḷaru** || [2||*] Avaroḷu
piriyaṁ Bhāv-ōdbhava-rūpaṁ **Vira-Bijjan-ōrvvī-nāthaṁ** [!*] Śiva pada-
paṁkaja-shaṭpadan=akhiḷa-stuta-kī-

lady, the land of Kurntala by resorting to strength of arms, after conquering the refractory (*chiefs*) so as to be highly praised by the whole circle of Earth.

V. 6. The son-in-law of the emperor was the well-behaved prince **Chāvuṇḍa** of white fame, a tough warrior, renowned on earth as a Gandharva of the Kali age. As regards the genealogy of that high-souled (*hero*) :

V. 7. King **Āchugi's** brothers, viz., prince **Nāka**, **Śiṃga**, the chief of kings, the famous **Dāsarasa** endowed with valour befitting his rank, the valiant **Dāvaṇa**, king **Chāvuṇḍarasa**, a handsome lover of victory and prosperity and the virtuous prince **Chāva** were (*powerful*) like a thunderbolt to mountains, the kings of uncomparable prowess. Among them

V. 8. the brave king Chaṇḍa, born of the **Sinda family**, ever praiseworthy shines on earth with the splendour of fortune and fame unsullied like the nectar-rayed (*moon*), looting and crushing the foes in furious rage when the confederacy of hostile armies met him in fight.

V. 9. Among them, to Ācharasa was born **Bammarasa**, a moon to increase the ocean, the Sinda (*lin. age*), brilliant with fame, a repository of great prowess and endeared to victory and wealth.

V. 10. His younger brother was **Ācharasa** of exceeding splendour who, born of the illustrious Simha and renowned on earth was, on account of his valour, (*known to be*) ever engaged in killing the hosts of haughty foes.

V. 11. The wife of Ācha-bhūpa, thus described, was known by (lit. shore with) the name **Mahādēvī** and was of noble family, prudent, extremely calm in disposition, kind and possessed of good fortune.

V. 12. To king **Ācha** and the beautiful **Mahādēvī** was born the powerful prince **Perma**, famed like a Gandharva, exceedingly brave, pleasing in conduct, who rendered the battlefields impure with pure and rolling tears proceeding from the eyes of the young wives (lit. girls) of the collection of enemy kings who rose in battle.

V. 13. The younger brother of that Perma-bhūpa was the renowned chief **Chāvuṇḍa** a Cupid in form, possessed of a number of excellent qualities and who was a woe to the trembling hearts of the enemy kings.

V. 14. **Chāvuṇḍa**, son of **Charṇḍaladēvī**, courageous like Mount Mandara and expert in playing with the rows of balls, the heads of the groups of hostile kings, attained fame glowing like the clear moon.

V. 15. The king **Chāvuṇḍa** was, when exasperated, a storm to disperse the gathering of clouds, the formidable hostile kings, a brilliant ray of the moon to remove the enveloping and dense darkness, the sins of the Kali age, with fame encompassing the oceans. (*A bestower*) of magnificent gifts he shone like a bolt to tear asunder the mountains, the vanities of groups of scholars.

V. 16. When the army of the **Hoysala** king who had prepared himself for battle met him bravely with a united front, prince **Chāvuṇḍa**, the moon in the ocean of the Sinda family stepping forth valiantly (lit. with valorous steps) rushed through, burning like the sun, killed its general and other opponents and, further, captured groups of fierce and intoxicated elephants.

V. 17. What hero, indeed, would equal the ornament of the Sinda family who was the master of valiant marauders that stimulated themselves by twisting their moustaches after destroying completely brave warriors, feeling disgusted to fight and kill those that were timid, those that sought his protection, those that cast away their garment through fear and stood (*helpless*) and those that got down on earth from horse (*back*) ?

V. 18. Puffed up at (*the strength of*) his fourfold army and itching with the might of his arms the **Pāṇḍya chieftain** started immediately and met king **Chāvuṇḍa** with force to conquer him

(*Chāvuṇḍa*) conquered (*his*) army single-handed. Seeing it king **Kāma** threw off his garment and losing (*hopes of*) victory fled by the forest track turning **his** back.

V. 19. Just as Amarāvati looked ever beautiful with Indra who was bowed to (*by all*), Ayōdhya with the descendant of Raghu (*i.e.*, Rāmachandra), the lovely Mathurā with Gōvinda, Ujjayini with Gutta and Hastināpura with the son of Mārut (*i.e.*, Bhīmasēna), so also **Eraṇbarāpura** attained much gracefulness with the Sinda chief **Chāvuṇḍa**.

V. 20. **Eraṇbarāpura** shines greatly on the face of this charming earth with temples, numerous palaces containing groups of maidens, houses of gods on earth, *i.e.*, Brāhmaṇas, and of the hosts of Vaiśyas who resembled Kubēra (*in wealth*) and with the hermitages of ascetics in sacred groves of penance.

V. 21. There, **Fifty Families** of Telligas (*i.e.*, oilmen), endowed with pleasing virtues and possessing brilliant fame (*bright*) as white clouds, were like bees on the pure and full-blown lotuses, the two feet of Śiva.

V. 22. Further, the bright Earth is ever pleased with the deserving Fifty Families and praises them high saying "they are like the ocean capable of protecting the mountains, the refugees, like the intensely furious conflagration powerful enough to burn away the forests, the turbulent foes and chief villains, and like the handsome bees humming in the lotuses, the beautiful feet of Śambhu.

V. 23. Groups of (*their*) relatives extol with gestures of hands the Fifty Families so as to be well appreciated by the whole world saying, "They are worthy of praise by the good, avowedly truthful, armoured with piety and inestimable conduct, gladdened in their pure hearts at the innumerable delights of their wives and are ever busy in the worship of the lotus feet of gods and of *devījas*".

Lines 36-38. The Fifty Families, thus praised, assembled and performed the installation of god **Telligēśvara** in the north-east quarter of **Eraṇbarāpura** and also constructed a temple for the deity. To describe the succession in the family of the preceptor of **Charṇdra-maulidēva**, the *āchārya* of that temple :—

V. 24. There was an ornament of ascetics named **Vigrahēśvara** of much extolled intellect, who was greatly praised in (*his*) respectable family¹, an abode of refugees, and was known as **Lakulīśa** born in the **Kālī** age.

V. 25. The meditator on his lotus feet was the righteous **Yōgēśvarayati** of blameless conduct, a bolt lifted up at the mountain, the Cupid, a sun to the lily of **Lākulāgama** (*i.e.*, works of the **Lākuja** sect).

Vv. 26 and 27. The disciple of that excellent *muni* was the best *yati* called **Charṇdramauli**, the sole resort of learned men, who has conquered the rising **Kālī**; his generosity surpassed the group of desire-yielding trees, his vow of (*subsisting on*) roots, the praiseworthy son of **Vāyu** (*i.e.*, **Hanūmān**), his truthfulness, the unblamable **Satyatapa**, his serenity, the ocean and his fame pervading the three worlds, the lustre of the moon.

Ll. 44-46. Hail ! When the victorious reign of the illustrious **Tribhuvanaśaila Bijjapa-dēva**, an asylum of the whole world, Lord of Fortune and Earth, possessed of all the laudatory titles like **Mahārājadhirāja**, **Paramēśvara**, **Paramahatthāraka**, a sun to the lotus of the **Kaṇchuriya** family, terrible in fight, was advancing in the course of continuously increasing prosperity as long as the sun and the moon last,

¹ *Manneya* may also be taken to mean a particular sub-division of the teacher's lineage.

Ll. 46-48. On **Monday**, the new-moon day of **Pushya**, which was the day of **Uttarāyana-samkrānti** and **Vyatipāta** in the cyclic year **Vyaya** corresponding to the **Śaka year 1088**, the **Fifty Families of Telligas** met together and granted the following income with the pouring of water to the glorious god **Telligēśvara** after laving the feet of **Chandramauli-dēva**, the *āchārya* of **Simhēśvara-maṭha**.

Ll. 44-52. Each family in Cantonment and Town (*should*) each day measure out two *soḷasa* of oil for an oilmill; in the family (*maintaining*) the god's oil mill, oil measuring one *soḷasa* (*should be received*); five *vīṣas* on an oil mill for (*the offering of*) *chaitra* and *pavitra*; and five *vīṣas* from every one of those that press the mill; one *koḷaga* of *jwarry* per month from each family for conducting the feeding of people (*i.e.*, guests) that come to the *maṭha*; one *matṭar* of garden situated at.....west of the path leading to **Kallūru**; on the sacred occasion of **Dīpāvali**, one *māna* of oil from each family (*should be received*).

Ll. 52-54. The income granted by the Five hundred *svāmins* in (*their*) storehouse: for every gold coin, one areca-nut from sellers and one from buyers; one areca-nut from the counting officers each time (*they count*). The income granted by the dealers in betel-leaves: a hundred leaves for one cartload, a hundred for a bullock-load, fifty for a man's load and two shops in front of the temple.

B.

Verse 1. May the glorious and famous god **Telligēśvara** grant with kindness the prosperity of kingdom to the world-renowned **Bijjaladēva** and king **Vīra-Vikrama**.

V. 2. There were born to king **Chāvunḍa** of reputed virtues and to **Siridēvi** (*two*) sons namely, king **Bijjala** and king **Vīra-Vikrama** as if they were the (*two*) eyes or (*two*) goals of life (*of their parents*).

V. 3. Of them, the elder was prince **Bijjala**, a Cupid in form, a bee in the lotus feet of Śiva, with fame sung by all and an ocean of polity.

V. 4. King **Vīra-Bijjaṇa** trusted Śiva like Nambi and was like Ōhila, a devotee who did not observe any religious rites—what more—he was learned like Bāṇa.

V. 5. This prince **Vīra-Bijjala** of increasing fame, a shaft in the hearts of his foes and an expert, forsooth, in the sixty-four arts was the husband of **Tripurādēvi**.

V. 6. King **Vīra-Vikrama** looks majestic with fame extolled on earth as if he was then the (proper) lord (*to bear*) the title of **Chakravartin**.

V. 7. If (*the name of*) a tiger is taken (*to compare his valour with*) he would mock at it, he would.....host of serpents, oppose in a fitting manner.....and cow down the Death God. O! God!! **Vīra-Vikrama** is indeed a veritable warrior.

V. 8. Who, indeed, can survive.....(*after witnessing*) the force of the prowess of his arms? Who does not shrink in power? Who does not run away helpless after opposing (*him*) in battle? Who does not tremble or be perturbed in mind and will not.....offer everything of his own? What person is there that does not stretch his hands for the gifts of the renowned **Vīra-Vikrama**?

V. 9. The powerful chief **Vīra-Vikrama** gives (*gifts*) to one that praises him; protects if one seeks his shelter and is a beautiful swan to the lotus plant.....**dēvi** who equalled **Lakṣmī**.

Lines 10-12. Hail! When the illustrious **Mahāmaṇḍalēśvara**, **Sāhasōttuṅga**, **Bhujabala**....king.....**ladēva** and **Vīra-Vikramadēva**, possessed of all the laudatory *birudas*, were ruling in their capital **Erambarage**, with the diversion of pleasant conversation, **Kisukāḍu-70**, **Bāgaḍage-70**, **Keḷavaḍi-300**, **Nareyaṅgal-12** and **Kariviḍi-3[o]**.

Ll. 12-16. On **Monday**, the auspicious day of **Samkrānti**, the fourteenth day.....in the cyclic year **Plavaṅga**, corresponding to the **Śaka year 1109**, **Bijjaladēva**

and **Vīra-Vikramadēva**.....granted at the request of the **Fifty Families** as *sarva-namasya*, with the pouring of water and with immunity from all claims, twelve *matṭar* of land field by the pole (*measuring*) twenty-seven (?) spans, on the north of the land of god Jagatēśvara, to god **Telligēśvara** of **Erāmbarage**, the fortunate town existing from times immemorial (*anādi-paṭṭaṇa*), and at the request of **Murujaya-Sāhaṇi**, one *matṭar* of paddy land to the west.....

No. 13.— DABOK INSCRIPTION OF THE TIME OF DHAVALAPPADEVA; [HARSHA—]
SAMVAT 207.

By

R. R. HALDER, RAJPUTANA MUSEUM, AJMER.

This inscription was found engraved on a large stone lying in a field at the village of **Ḍabōk**, eight miles to the east of Udaipur in Mewār. It was removed to the Udaipur Museum by Rai Bahadur Gaurishankar H. Ojha, and I edit it from the ink-impression, which he so kindly placed at my disposal.¹ Dr. D. R. Bhandarkar has noticed it in this journal.²

The record contains fifteen lines of writing covering a space of about 3 ft. 6 ins. × 1 ft. 7 ins. The average size of the letters is $\frac{3}{4}$ in. The **characters** belong to the northern class of alphabets, commonly known as *Kuṣṭha lipi*. They are almost similar to the Jodhpur Inscription³ of Pratihāra Bāuka. Palæographically, the inscription is important, as the date given in it contains the letter-symbol of 200, which is worth noting. The **language** is incorrect Sanskrit and, excepting the two imprecatory verses, the whole record is in prose. In respect of **orthography**, the following points may be noted—consonants are doubled after *r*, as in *Durgādēvyā* (l. 4), *-mārgga* (l. 9), etc.; and before *r*, as in *-puttra* (l. 2), *kshētram* (l. 5), etc.; *s* is written for *ś*, as in *°svarasya* and *sāradya* (l. 4), and for *sh*, as in *°sēdhyō-* (l. 13), *-aṭavīśv-a-* (l. 14), etc.; the *anusvāra* is used for *n* in *asmim-* (l. 1), *-chandrārka-* (l. 11), etc., and is redundant in *-vridhyartham* (l. 11), and *haram-* (l. 15); *m* is written for *v* in *-nimī* (l. 3), etc.; rules of *sandhi* are, as a rule, violated in almost all the lines. The *upadhmāniya* is used in *punar=ādadita* (l. 14). Other mistakes and irregularities are pointed out in the footnotes accompanying the text.

The inscription is of the time of **Śrī-Dhavalappadēva**, who, as shown by the titles *Parama-bhaṭṭāraka*, *Mahārājādhirāja*, *Paramēśvara*, appears to have been a paramount chief. The record is dated in the eighth day of the bright fortnight of **Bhādrapada** of the **Samvat 207**. The object of the inscription is to record the grant of some fields and, probably, shops, too, by Vaidya Giyaka, son of Nāgadāman, a resident of Dhavagartā (the present town of Dhōṛ in the Jahāzpur district of the Udaipur State) to the temples of the god Mahāmahēśvara and the goddess Durgā called Ghaṭṭavāsini.

As the era to which the year belongs has not been specified, the date cannot be ascertained with certainty. The characters, however, are of a period not earlier than the 8th or 9th century A. D. In consideration of this fact, the date can be referred to the Harsha era, in which several other inscriptions⁴ of Rājputānā are dated. In that case the date would correspond to Monday, the 8th August A.D. 813. The family to which Dhavalappadēva belonged is not mentioned in this inscription. From the Dhanōp inscription⁵ of Chachcha, dated Samvat 1063

¹ The impression is not very clear. Consequently the reading is not free from doubt in several places.

² Above Vol. XII, p. 11.

³ Above Vol. XVIII, pp. 87 ff.

⁴ See *Annual Reports of the Rajputana Museum, Ajmer*, for 1916-17 and 1919-20, 4(b) L.

⁵ *Ind. Ant.*, Vol. XI, p. 174

(A.D. 1006), we know that the Rāshtrakūṭas were ruling over Rājputānā in the eleventh century A.D. We also know from the Sirūr inscription¹ of the Rāshtrakūṭa king Amōghavarsha I that Gōvindarāja III conquered Kērala, Mālava, Gurjara, etc., as far as Chitrakūṭa (Chitōr in Mewār). This would show that the Rāshtrakūṭas of the Deccan held their sway over some parts of Rājputānā in the beginning of the ninth century A.D. Possibly the Rāshtrakūṭas of Dhanōp, which is near Mewār, were related to the Rāshtrakūṭas of the Deccan, and Dhavalappadēva may also have been related to them. His name seems to be of South-Indian² origin.

The epigraph under notice describes Dhanika as the son of Guhila, who then ruled over Dhavagartā (l. 2). The Chāṭsū inscription³ of Bālāditya mentions a Dhanika as the son of Guhila. One Dhanika figures as a local ruler in the inscription⁴ dated Saṃvat 887 (A.D. 830), recently discovered at Nāsūn in the Kharwā estate in Ajmer-Merwara, but, there, he is described as the father of Īśānabhaṭa. The Dhanika of the Chāṭsū inscription was the great-grand-son of Īśānabhaṭa. Consequently there must have been two Dhanikas and two Īśānabhaṭas.

The contents of the inscription may be summed up as follows:—

After making an obeisance to the god Śiva and giving the date as the eighth day of the bright fortnight of Bhādrapada of the saṃvat 207 (200 in letter-symbol and 7 in figure), the first five lines state that, during the reign of *Paramabhaṭṭāraka Mahārājādhirāja Paramēśvara Śrī-Dhavalappadēva*, Vaidya Gīyaka, son of Nāgadāman of the Kāyastha family and an inhabitant of Dhavagartā, which was being ruled over by Dhanika, a Guhilot, made permanent endowments of some *śāradyagraishmika* fields (the fields that can be tilled in autumn as well as in summer) to two temples—one of Mahāmahēśvara established by him (Gīyaka) and the other of Durgādēvī previously established by Vaidya Yaśōdēva. Lines 4-5 inform us that the above fields were in the share or inheritance of Chachcha (probably one of the sons of the donor). In lines 5-10 are given the boundaries of the fields and of the two shops. Lines 10-11 tell us that the fields were granted for the increase of religious merit and fame of the donor and his parents, as also for the repairs and maintenance of the above temples. In lines 12-13, the allotment of the fields and the share of their produce is made. The fifteenth or the last line tells us that the inscription was engraved by Vṛiddhināga, son of Vaidya Gīyaka.

TEXT.⁵

- 1 श्रीं नमः शिवाय ॥ सं २०० ७ भाद्रपदशुद्ध ८ अक्षिंदि(क्षिन्दि)वसे
परमभट्टारकमहाराजाधिराजपरमेश्वरश्रीव(ध)वस्यदेवप्रवर्ध(धं)-
- 2 मानराज्ये । गुहिलपुत्राणां श्रीव(ध)निकस्योपभु[ज्य]मानायां व(ध)वगर्त्तायां
वास्तव्यवैद्यगोयकनागदामपुत्रनेगम-
- 3 जात्य(त्यः) श्रीमहेश्वरपौरसामान्यदेवदायत्वेन अक्षयनीमी(वीं) प्रयच्छति
आत्मीयस्य कारितदेवद्रोशीप्रतिष्ठापितस्य देवाधिदेवमहामह-

¹ Above Vol. VII, p. 207.

² Names ending in *ppa* generally denote the names of persons of South India; for instance, *appa* (above, VI, 117), *Tailappa* (*ibid.*, III, 271), *Dhōrappa* (*ibid.*, II, 217), *Dhādiyappa* (*ibid.*, II, 217), etc. Such instances are rare in northern India. The name Dhavalappa also occurs in a grant of Krishṇa II (*ibid.*, I, 83), but he must be a different person.

³ Above, Vol. XII, p. 14.


⁴ *Ind. Ant.*, Vol. LIX, p. 22.

⁵ From the impression.

⁶ Expressed by a symbol.

- 4 ख(ख)रस्य । तथा च पु(पु)र्व्वतरवैद्ययस(शो)देवकारितदेवद्रोणीप्रतिष्ठा-
पिताया घट्वासिनीनामश्रीदुर्गादेव्या अर्द्धार्द्धत(तः) । आत्मीयस्ववीर्योत्पत्तो-
(का) सारद्यद्वैभिकचेत्तादी'पूर्व्वभुज्य(क्त?)भुज्य-
- 5 माना अचाटभटप्रवेशा [ख]पुच्छाणां श्रीचक्षदाया । ह(ध)वगर्तापु(पु)र्व्वत-
(तः) सा(शा)[र]द्यद्वै(शै)भिकचेत्ता [1*] यस्याघाटनानि पूर्व्वतः [सा]-
बटचेत्ता वकटा च [1*] दक्षिणत(तो) राजकीयचेत्ता । पश्चिमत(तः)
पङ्कण-
- 6 प्यकपाक्षी । उत्तरत(तो) वर्त्ता(र्त्त) । तथा नागादित्यभटा(ट)स्य चाग्रते
(तः) शारद्यद्वै(शै)भिकचेत्ता । पूर्व्वत(तो) ब्रह्मसोमवाउट^२कचेत्ता वकटा
च ॥ दक्षिणत(तः) तटाकोदकं ॥ उत्तरत(तो) भर्म्भकभवकचेत्ता ॥ तथा
ह(ध)वगर्ता
- 7 दक्षिणत(तो) वाह्नियालीनाम अरह्मि(ह)हचेत्ता । पूर्व्वत(तो) गर्ता वर्त्ता
(र्त्त)च । दक्षिणत(तो) राजकीय[चे]त्ता । पश्चिमत(तः) पुष्कर(रि)-
णीघाली ॥ उत्तरत(तो) वर्त्ता(र्त्त) ॥ तथा कर्कतटाक^३ चाग्रत'अरह्मि-
चेत्ता [1*] पूर्व्वत(तो)
- 8 गर्ता । दक्षिणत(तो) राजकीय(या) अरह्मि(ह)कुक्का(स्या) । पश्चिमत(तो)
वकटा । उत्तरत(तो) राजकीयचेत्ता । तथा अमारघट्टवकटाकस्य
पृष्ठते(ष्ठतः) काश्चपियचेत्ता । पूर्व्वत(तो) । विष्णुसोमचेत्ता । दक्षिणत(तः) पश्चि-
मत(तो) राजकीयचेत्ता । उत्तरत(तो) गोम्यचेत्ता ॥ तथा हृष्टमध्ये बीडो
हे दाक्षेणाभिमुखा(खे) ॥ पूर्व्वतो(तः) पश्चिमत(तः) [सा]उल्लवीथी । दक्षि-
णत(तो) हृष्टमार्ग(र्गः) । उत्तरत(तः) प्रणा[ली] ॥ एवं च-
- 10 तुराघाटनोपकर्त्तितं(तं) । तथापरमपि सा(शा)रद्यचेत्तादी(दि) यत्किमपि
तत्त्वमस्तं(स्त)म[च] गुगुलदोपतैत्या(ला)र्थे खण्डस्फुटितसमारा(रो)पणार्थे च
माताप(पि)त्तो[रात्मनश्च] पुण्य-
- 11 यशोभिद्वध्य(ज्य)र्थ(र्थ)माचंद्रार्काण्यवयवचक्षुश्चक्षितिसितिसमकाखीमतया पुच्छयौ-
क्काव्यक्रमभोम्यतया च देशदशत्येन अचयनीमि(वि)काचारेण अ[तिष्ठापि]-
ता(तं) ॥
- 12 अनाघेयविधया ।^४ मन्म(म)पुच्छपौमात्मजै(जै) यैभिकचेत्तादी(दिः) सप्तमविभा-
जीय क(क)ष(षं)बीया(यः) ॥ सा(शा)रद्यचेत्तादी(दिः) सप्तदमीयकहृष्टकुटकेन
क(क)ष(षं)बीया(यः) । हावपि चतु-

^१ Read 'अरद्यद्वैभिकचेत्तादि'.^२ Read 'वाद्यतोऽरह्मि'.^३ 'ह' is written below the line.^४ The stroke is redundant.^५ Read 'तटाकस'.



- 13 (द्रु)मी(मी)श्को¹ [मासि] दातव्यो(व्यः) ॥ अपरकृषकै(कैः) यद्योपरिलिखितभागो दातव्येति² ॥ म(म)दीयगोच(च)जैरन्यतरैर्वा कालान्तरैश्च(च)पि न(न) के(कै)श्चि(चित्) प्रतिसे(षे)धो [न च] व्य(व्यः) । यानी-
- 14 इ संस्मा(सा)रभयाक्षरेन्द्रेव्व(ना)नि धर्मायतनीकृतानि [1*] निर्माव्यवात्स-
प्रतिमानि तानि [को नाम सा]धु × पुनराददोत [1*]³ विंध्याटवीस्व(च)-
तोयासु शुष्ककोटरवासिन(नः) [1*] कृष्णसर्प⁴भि-
- 15 जायन्ते देवदायं हरं(र)न्ति ये⁵ ॥ उत्कीर्ण्यं भिषः⁶गीयकसु(सु)नुना हृदि-
नागेन प्रस(प्र)स्तिरिति ॥

No. 14.—FOUR CHANDELLA COPPER-PLATE INSCRIPTIONS.

BY RAI BAHADUR HIRALAL.

Impressions of the four inscriptions, edited below, were forwarded to me by Dr. Hirananda Sastri, Government Epigraphist for India, who received the plates from the Ruling Chief of Charkhārī State, Bundelkhand, Central India, through the Director General of Archaeology in India. No details as to their provenance were available from the State office records. For the sake of convenience, I am here noticing the inscriptions in their chronological order.

A.—CHARKHARI PLATE OF DEVAVARMADEVA : [VIKRAMA-]SAMVAT 1108.

This charter is incised on a large copper-plate, 18½" by 12½", with its corners rounded off and weighing 360½ *tolas*. The plate is surmounted by a copper-hook, 2½" long, which is rivetted to it and holds a ring 2½" in diameter. Just below this is carved the figure of the four-armed goddess *Lakshmī* with an elephant on each side pouring water on her head with raised trunk. Under her seat is inscribed the sign-manual *Śrīmad-Devavarmmadēvaḥ sva-hastah* in two lines. The figure occupies a space, 4 inches long and 3 inches high, just in the middle of the first 6 lines. Each complete line is on the average 16" long.

The inscription is engraved in Nāgarī characters, their average size being ⅜". The language is Sanskrit. But there are numerous mistakes in spelling, etc., some of which appear to be due to the oversight of the engraver. There is a palpable instance of the latter being influenced by local *patois*, viz., the Bundelkhandi Hindī in which *jē* is still used for the Sanskrit *yē*, of which it is an exact equivalent. In line 21 the engraver had used the correct form but in the next line the more familiar vernacular word asserted itself. The orthographical peculiarities are similar to those which the late Dr. Kielhorn pointed out in editing another copper-plate charter of the same king issued a year before the present one.⁷ The latter was issued on the occasion of the anniversary of his mother's death, while the present record was issued on the occasion of a lunar eclipse for the religious benefit of himself and

¹ Probably this word is connected with *dramma*.² Read व्य इति.³ Metre, *Indravajrā*.⁴ Read सर्पा वि.⁵ Metre, *Anushubh*.⁶ Read भिषग्.⁷ *Ind. Ant.*, Vol. XVI, p 206.

his parents. The date of this record is Samvat 1108 Mārgasīra śudi 15, Sōma-dina.¹ On this day the Chandēlla king Dēvavarmadēva, Lord of Kālīnjara, meditating on the feet of Vijayapālādēva who meditated on the feet of Vidyādhara-dēva, offered water to the names of his ancestors, worshipped Sūlapāni or Śiva and gave the village Bhūtapallikā, situated on the bank of the Yamunā river in the *vishaya* of Nava-rāshṭra-maṇḍala, to Paṇḍita Kīckana of the Krishṇātrēya-gōtra with 3 *pravaras* whose ancestors had emigrated from Kum-bhaṭibhaṭagrāma. This Brāhmaṇa was ever ready to expound the Vēdas, the Vēdāṅgas, Itihāsa, the Purāṇas and Mīmāṃsā and was devoted to *shaṭ-karma* (*shaṭ-karm-ābhirata*), the prominent mention of which leads me to infer that he practised Yōga,² which is more awe-inspiring than the ordinary six³ duties of a Brāhmaṇa.

The localities mentioned in this record have not yet been identified, excepting Kālīnjara, whence the record was issued, and the Yamunā river on whose bank the village of Bhūtapallikā was situated. Both of them, viz., the fort of Kālīnjara and the river Yamunā or Jumnā are too well known to require identification. The mention of the latter indicates sufficiently the locality of the village and the district in which it was included. Dēvavarmadēva was the 12th king of the Chandēlla dynasty and, if this record shows anything in regard to his capital and extent of his dominions, it indicates that he lived in the Kālīnjara fort and that his *rāj* extended at least up to the Jumnā in the north. But almost the same conclusion is derivable from his other record referred to before and those of his predecessors, an account of which has been given by the late Dr. V. A. Smith in his exhaustive essay on the history and coinage of the Chandēlla dynasty.⁴ But it may be noted here that in his zeal to show the great antiquity of the Chandēlla dynasty and its kingdom Jējākabhukti—the designation was later on changed to Jajhauti and taken as given after Jējāka or Jayaśakti, the third king of the line—he has fallen into a blunder, to which enthusiasts, howsoever great, are sometimes liable. In his article he has attempted to prove that *Chih-chi-i'o*, visited and described by Yuan Chwang in 641 or 642 A.D., was no other than Jijhōti. This would mean that the country was named after a king, who was born about 200 years later, as according to him⁵ Jējāka ascended the throne about 860 A.D.

TEXT.

1. ओं नमः शिवाय ॥ स्वस्ति परमभट्टारकमहाराजाधिराजपरमेस्वर-
श्रीविद्याधरदेवः(व)पादानुध्यातः(त)परमभट्टा-
2. रकमहाराजाधिराजपरमेस्वरः(र)श्रीमहजयपालदेवः(व)पादानु(नु)ध्यातः(त)पर-
मभट्टारकमहाराजाधिराज-
3. परमेस्वरः(र)श्रीकालंजराधिराजः(ति)श्रीमहेश्वरदेवः(व)पादानां मन्त्रो(वा)-
प्रवर्द्धमानकल्याणविजयराजो स-

¹ This date is irregular. According to Swamikannu Pillai's *Indian Ephemeris*, V. S. 1108, Mārgasīra śn, 15 fell on Wednesday, the 20th November of A.D. 1051, with no lunar eclipse on that date. The date in V, 15, 1109 would correspond to Tuesday, the 8th December, A.D. 1052, when there was a lunar eclipse.

² The six *hatha-yōga* practices are:

Dhautir-basti tathā nēti naulikī trātakas=tathā |
kapāla-bhātī ch=antāni shaṭ-karmnāṇi samācharit ||

³ See Apte's *Sanskrit Dictionary* under *shaṭ-karma*.

⁴ *Ind. Ant.*, Vol. XXXVII, pp. 114 ff.

⁵ *Ibid.*, p. 131. 'The kingdom was known as Jajāhūti (Jajāhōti, Jijhōti),

⁶ *Ibid.*, p. 127.

- 4 स्वत्सरसहस्रैके षष्टोत्तरशताधिके अंकतोपि ११०८ मार्गसिर(शीर्ष)सु(शु)दि
१५. सोमदिन(ने) [१*] अद्येह ओ-
- 5 कालिंजरात(त्) इत्यस्मिन्क ले वर्त्तमाने सा(शा)सनदाता नास्त्रामवः(?)
एकाङ्क[१*] सू(शू)द्रक्षेव(क इव) निसि(शि)तापिधारादा-
- 6 रितारिदग्गः विस्त्र(णु)रिव सधरधरा(धराधर)कन्दरगुफा(हा)न्तरालयस(शो)ध-
वलितदिग्वधूवदनं(नः) व(व)लिकरैयि(ण्णावि)व क-
- 7 नकगोधरादानविष्या(ख्या)ता(त)कीर्त्ति[१] युधिष्ठिरव(र इव) सत्यमौ(शौ)चगुरुहि-
जदेवशुसू(यू)धारतर(तो)नङ्गमिव(इव) रूपसोभाग्ययुक्तं(क्तः) परकुलःकृत्वाव-
(व)भु[१*]
- 8 मुनिरिव विदितात्मा काव्याल(लं)कारकन्द(न्दो)लषः(ज)णगुणगणाधिष्ठान(नः)
युगसमानर्दसित्वंस्व^१न्दिजनमंकोर्णस(श)तद्वार(रः) निन्ना(यी)सितत-
- 9 स्तरादिभयंच(भयस)न्देलान्वयः परममाहेस्व(स्व)रः परमभट्टारकमहाराजाधिराज-
परमेस्व(स्व)रः ओमदेववर्म्मदेव(वो) महासामन्तरा-
- 10 जपुत्रवन्दितः(त)पादः(दः) रंभागर्भोपम(मं) संसारमाकल्य(ल्य) तडित्चञ्चल-
वन्नश्मो^२ ज्ञात्वा य(ज)लवुद्(बुद्)दोपम(मं) जोवितमिदं भुत्वा यौवनचांज-
- 11 लितुकमिवा^३स्थिरत्वं(च्च) सुचिरमपि वसि(उषि)त्वा नास्ति कामेषु तृप्ति[स्सु]
धिरमपि सुविचिन्त्य धर्ममे(ए)को हि साखाय(सखा) [१*] आ[यु]र्वर्षम(श)तं
नृणा(णां)
- 12 परिमित(तं) रात्र्या [त]दर्श(र्हं) हृतं तस्यार्हस्य कदाचिदर्हमधिक(कं) वाद्विज्य-
(वाह्म्य)वाले(वाल्मे) म(ग)तं [१*] से(शे)वं व्याधिजराधियोगमरणैः सेवादिभि-
र्क्षीयते ॥^४
- 13 जीवे वारितरङ्गचञ्चलवलैः(तरे) सौख्यं कुतः प्राणिना(नाम्) [११॥*]^५ एवं
संसारधर्ममेको(कं) हि असा(शा)स्त्र(स्व)तं ज्ञात्वा दानमतिवके (?)
[स्त्र]भोगावा[म]-
- 14 नवराष्ट्रमण्डलविषये यमुनातटे भूतपत्निकानामग्रामोय(यं) सोमातुणकाष्ठवो^६पर्य-
न्तं(न्तः) ओदेववर्म्मन(वर्म्मणा) अद्यः(द्य) पौष्णमासोमग्राहे
- 15 कीटितोर्थे ज्ञात्वा पितृतर्पणं [च] कृत्वा ओसू(शू)लपाणिदेवमर्स्व(र्षं)यित्वा
यथाविधि च धु(हु)त्वा मातापितृचात्मन(पितृरात्मन)स पुन्य(स्थ)यसो(शो)
विहृषये[ति](इति) कुम्भटोभट-
- 16 ग्रामविनिर्भूताय कृष्णाचेयस्व(स)मोत्राय अत्रिअर्चनानससोवास(श्यावाश्वेति)^७स्तुः-
(चि)प्रवराय वहु(वाहु)चसा(शा)स्त्रिने ब्रा(ब्रा)ह्मणपण्डित-ओजयस्वामिपीत्राय
पण्डि-

^१ Read °दक्षिणार° (?)^२ Read अत्रिचक्षुर्वा जक्षी°^३ Read दोषं च वृत्तायलनलनिष्टवद° (?)^४ Strokes not required,^५ Metre, Śārdūlavakṛīḍia.^६ Read °काष्ठगोचर°.^७ See Max Müller's *History of Sanskrit Literature*, p. 197.

- 17 तः(त)श्रीसोमेस्क(ख)रपुत्राय पंडितः(त)श्रीकिक्कनः(नाय) वेदवेदाङ्गेतिहासपुराण-
मोमांसाव्या[ख्या]नतत्पराय षड्दर्माभिरताय ब्रा(ब्रा)ह्मणाय
- 18 आश्र(शास)नं¹ प्रदत्तं(त्तः) यथा दीयम(मा)नस्य भागभोगकरहिरन्य(ण्य)दण्डा-
दायादिकुवितान्वचितं(कमुचितानुचित)प्रभृतयस्तत्सर्वमस्योपनेतव्यं ॥ सर्वान्ये-
(ने)तान्म(ग्भा)-
- 19 विनो(नः) पार्थिवेद्रा[न्*] भूयो भूयः(यो) याचते रामभद्रः [1*] सामान्योयं-
धर्मसेतुर्नृपाणां काले २ पालनीयो भवद्भिः ।[1२॥*] भूमी(मिं) यः प्रति-
गृह्णा(ह्ना)ति ।² यश्च
- 20 भूमिं प्रयच्छा(च्छ)ति । उभौ तौ पुन्य(ण्य)कर्माणि ।² नियतौ स्वर्गगा-
मिनौ [॥३॥*] षष्ठि वर्षं(षष्टिं वर्ष)सहस्राणि स्वर्गे मोदति भूमिदः [1*]
अ(षा)च्छेता(त्ता) आन्म(नुम)न्ता व्व(च) तने(तान्ये)-
- 21 व नरक(के) वये(से)त(त्) ।[1४॥*] स्वदत्तां(त्तां) परदत्तां(त्तां) [वा] ।² ये(यो)
हरन्ति(हरेत) वसुन्धरां । स्वा(स्वा)नयोनिस(ग्र)तं गत्वा ।² चाण्डालेष्व-
भिजायते ।[1५॥*] विंध्याटवीष्वतोयासु शुष्ककोटर-
- 22 वासिनः [1*] मरुसर्पाभिजायन्ते ।² जे(घे) हरन्ति रसुहचां³ ।[1६॥*] वापी-
कु(कू)पसहस्राणि ।² अश्वमेधस(ग्र)तानि च [1*] गवां कोटिप्रदानेन
भूमिहर्ता न
- 23 शुध्वाति ॥[७॥*] मङ्गलं महाश्रीः । अक्षपटलिकयशोभटेन लिखितं ॥

B.—CHARKHARI PLATES OF PARAMARDDIDEVA : [VIKRAMA-]SAMVAT
1236.

These are two copper-plates having raised rims ($\frac{3}{8}$ " high) rivetted to them. Each plate weighs 180 $\frac{1}{2}$ tolas, but their sizes differ a little, the first measuring 14 $\frac{1}{2}$ " by 11 $\frac{1}{4}$ " and the second 14 $\frac{1}{2}$ " by 10 $\frac{3}{8}$ ". The former contains 18 lines of writing against 14 of the latter. On the first plate there is a figure of **Lakshmi** in the middle of the first three lines, and at the bottom, a round hole in the middle of the last line. In the second plate space was left for a hole, but it was never made and hence the plates were not strung together as was originally intended. The size of the letters in the first plate is $\frac{1}{2}$ ". They are smaller and more beautiful than those in the second plate, to cover the whole of which the engraver Pālhaṇa, a skilful artisan, as he calls himself, had had to raise the size to $\frac{5}{8}$ ". In the case of the Mahōbā plates of Samvat 1230,⁴ I remarked how Pālhaṇa worked up his way from the position of a *pūtalahāra* to that of a *vijñānin*, and this time, *tie.*, six years later, he raised himself to the position of a *vaidagdhi-vivakarma*⁵ (l. 32). Despite this, there is hardly any improvement in his engraving. The fact remains that the

¹ Read शासनेन.

² Daṇḍa not required.

³ Read वसुन्धरा.

⁴ Above, Vol. XVI, p. 10.

⁵ [The Icholihāwar plates (*Ind. Ant.*, Vol. XXV, pp. 208 ff., l. 35) also give this epithet.—Ed.]

letters *va*, *dha*, *cha* and *ra* have been so formed as to cause confusion with one another, for instance, in l. 4 *Paramarddidēvō* has been engraved as *Paramarddidērō*. *Ba* has not been at all distinguished from *va* and the symbol for the medial *u* has been sometimes so broadened as to give the appearance of a *ta*, e.g., *bhūtvā* (l. 17). In the text letters or their parts are, in some cases, omitted in consequence of which the sense is also affected. The *anuvāra* and the *rēpha* have been in many cases omitted through sheer inattention, cf. *śaṭ-tri[m*]śa²* (l. 8) and *Prithivīva[r*]mma°* (l. 3). On the whole the record is well written. The language is Sanskrit and the text is similar to the one found in other records of the same king. The composer of the record or rather the adopter of the prescribed form, with necessary changes, was one Śubhānaṁda Vāstavya, who was probably a relative of Prithvīdhara Vāstavya, the writer of some of the previous records of Paramarddidēva.

This charter was issued from Vilāsapura and records the grant of Sagauḍō village situated in the district of Kirāyīḍa to a number of Brāhmaṇas, whose forefathers had immigrated from Mutāutha-Bhaṭṭāgrahāra, by the P. M. P. Paramamūhēśvara Paramarddidēva, meditating on the feet of the P. M. P. Madanavarmadēva, who meditated on the feet of the P. M. P. Prithvīvarmadēva, descended from the heroes Jayaśakti and Vijayaśakti of the Chandrātrēya (Chandēlla) lineage. The grant was made for the increase of the religious merit of the donor and his parents on Monday, the seventh day of the bright fortnight of Chaitra in the Vikrama-Samvat 1236¹ which regularly corresponds to Monday, the 27th March 1178 A.D. The record does not supply any new information worth being mentioned and which is not given in the numerous inscriptions² of this king which have already been found. [It is interesting to observe here that in the gift-village exception was made of the five *halas* of land gifted to Buddha (l. 14) for that would show that a Buddhist monastery was in existence there and was endowed with that land.—Ed.]

Of the localities mentioned in it, Kālāñjara is too well known to require identification. Kirāyīḍa may be Kirāḍi, 5 miles from Mahōbā. I have not been able to trace Vilāsapura, Sagauḍō and Mutāutha villages.

TEXT.

First Plate.

- 1 [श्री] स्वस्ति ॥ जयत्याह्वाद्यन्विष्टं विश्वेश्वरशिरोधृतः । चन्द्रात्रेयनरेन्द्राणां
वंशचन्द्र इषीज्ज्वलः ॥ [१॥*] तच्च प्रवर्द्धमा-
- 2 ने विरोधिविजय(य)भ्राजिष्णुजयशक्तिविजयशक्त्यादिवीराविर्भावमास्वरे परमभट्टा-
रकमहाराजाधिरा-
- 3 जपरमेश्वरश्रीपृथ्वीवर्मा(र्षी)देवपादानुध्यातपरमभट्टारकमहारजाधिराजपरमेश्वरश्री-
मदनवर्मादेवपा-
- 4 दानुध्यातपरमभट्टारकमहाराजाधिराजपरमेश्वरपरममहिष्वरश्रीकालञ्जराधिपतिश्री-
मत्परमर्हिंदेरो(वो) विजयी ॥ स एष

¹ This must be taken as the current year.

² See above, Vol. I, p. 208, Vol. IV, pp. 157 ff., Vol. XVI, p. 9; *Ind. Ant.*, Vol. XIX, p. 37, Vol. XXV, 206; Cunningham's *A. S. R.*, Vol. XXI, pp. 74, 173, 174, and *J. A. S. B.*, Vol. XVII, p. 313.

- 5 दुर्विषहतरप्रतापतापे(पि)तसकलरिपुकुलः कुलवध्व(धू)मिर(व) वशु(सु)श्वराश्व-
राकुशां परिपालयन्नविकलविवेकनिर्मलीकृतमतेः(तिः) । किरायि-
- 6 उविषयःन्तःपातिसगौडोग्रामोपमतान्वा(न्वा)ह्मणानन्या(न्यां)श्च मान्यागधिकृता-
न्कुटुम्बि(म्बि)कायस्थदूतवैद्यमहत्तरान्मेदचण्डालपर्य-
- 7 ज्ञान्सर्वान्सम्बो(म्बो)धयति समान्नापयति(ति) चा[स्तु]वः सम्बिदितं यथोपरि-
लिखितोयं ग्रामः सजस्यलः सस्वावरजङ्गमः साधकजुर्गं भूतभ-
- 8 विष्णुदत्त(र्त्त)माननिःशेषादायसहितः प्रतिषिद्धचाटादिप्रवेशास्माभिर्विलासपुरे
षट्त्रि(ट्रि)शदधिकशतद्वयोपेतसहस्रतमे
- 9 सम्बल्लरे चैत्रे मासि शुक्लपक्षे श(स)प्तम्यान्तिथावङ्गतोपि स(सं)वत(त्) १२३६
चैत्रशुदि ७ भो(सो)मवारि पुष्यतीर्थोदकेन वि-
- 10 धिवह्मत्वा देवादीन्सन्तर्प्य भास्करपूजापुरःसर(रं) चराचरगुरु(रुं) भगवन्त(न्तं)
भवानोपनिमन्त्र्य हुतभुजि हुत्वा माता-
- 11 पिभोराजनस्य पुष्यशोविह्वये । सुताउद्यभट्टाग्रहारविनिर्गतेभ्यो वत्सगोदेभ्यो
वत्सभार्यवच्यवना-
- 12 प्रवानौर्व्या(जा)मदम्येतिपञ्चप्रवरभ्योऽह(भ्यः)दोगशाखाध्यायि[भ्यो] नानाप्रपो¹
पीचभ्यो नामा(ना)पो¹(पो)चेभ्यो नाना-
- 13 पुचेभ्यो नानानामशर्मभ्यो ब्रा(ब्रा)ह्मणेभ्यः कुशलतापूतेन हस्तोदकेन स्वस्ति-
वाचनपूर्वचन्द्रार्कसम-
- 14 काल(र्त्त) पुत्रपीचाद्यन्वयानुगामि देवश्रीवी(वी)हसत्पञ्चहलानि व(व)हिःकृ(कृ)त्
से(शे)षभूमिः शासनीकृत्य प्रद-
- 15 ता । मध्ये ॥ ति । दावरपुत्र ति । मोमेकस्य पदद्वयम(म्) । ति ।
वाह्नेपुत्र ति । स्वपटस्य पदमेकम(म्) । ति । पापेपु-
- 16 त्र ति । रतनस्य पदमेकम(म्) । ति । सूक्ष्मपुत्र ति । सीढस्य पदमे-
कम(म्) । इति मत्वा भवद्विराज्ञाश्व(श्व)वणपिवे-
- 17 ये(विधेयै)भूत्वा भागभोगपशुहिरण्यकरशुल्कादि सर्व्वमस्त्रो(स्त्रो)² समुपनेतव्य(व्यं)
[।*] तदेनमवा(स) सम(मं)दिरप्राका-
- 18 र(रं) सनिर्ममप्रवेश(शं) ससर्व्वशनेक्षुर्कपांसकुशु(सु)मस(श)शाममधूकादिभूदह(हं)
सवगखनि-

¹ The letter पो is superfluous.² [Plural ought to have been employed.—Fd.]

Second Plate.

- 19 निधानं सलोहलवणतुणप[णी]द्याकरं समृगवे(वि)हङ्ग[म]जलचरं सकाशकपंक-
वणिग(वणिग्)वास्तव्यं¹ स-
- 20 कावे(ष्ठे)ष्टिकापाषाणं सगोकुलमपरे(रै)रपिसीमान्त[र्ग]तेव्व(र्व)स्तुभिः सहितं
सवा(वा)ह्याभ्यन्तरादायं भुञ्जा(ञ्जा)-
- 21 मामं(नस्य)² के(क)र्षता(तः)³ कष(र्ष)यतो² दानाधानविक्रयस्वा कुर्वतो³ न
केनाच(नचि)त्काचिद्वा(दु बा)धा कर्तव्या । अत्व(त्र) च राजरा-
- 22 जपुरुषाटविक³चाटादिभिः स्वस्वमाभावं परिहृत्तव्यमिदञ्चास्महानमनाच्छेद्य(द्य)-
मनाहार्यश्चेति
- 23 भाविभिरपि भूमिपालैः पालनीयमित(ति) । उक्तञ्च ॥ शङ्खभद्राश(स)नं च्छत्रं
वराखा वरवारणाः । भू-
- 24 मिदानस्य पुष्पाणि फलं स्वर्गः पुरदंर(न्दर) ॥[२॥*] सौवर्णा यत्र प्राशा-
(सा)दा चा(द्या)शाद्वा(द्वा)रा[ः*] स्वकामदाः । गन्धर्वा-
- 25 मरसो यत्र तत्र गच्छन्ति भूमिदाः ॥[३॥*] भूमिं यः प्रतिष्ठह्नाति
यश्च भूमिं प्रयच्छे(च्छ)ति । उभौ तो (तौ)
- 26 पुण्यकर्माणौ नियतं स्वर्गगामिनौ ॥[४॥*] व(व)हुभिर्वसुधा भुक्ता राजभिः
सगराहि(दि)भिः । यस्य
- 27 यस्य यदा भूमिस्तस्य तस्य तदा फल(लं) ॥[५॥*] सर्वानेताभ्यावे(वि)नः
पार्थिवेन्द्राभूयो भूयो याचते
- 28 रामभद्रः । सामान्योय(यं) धर्मसेतुर्नृपाणां काले काले पालनी[यो] भव-
द्भिरिति¹ ॥(ङ्गिः ॥ इति ॥)[६॥*] स्वहस्ता(स्तो)-
- 29 य(यं) महाराजश्रीपरमहिंदेवस्य मतमम ॥ विशदगुणगणो(णौ)घोषामवास्त-
व्यव(व)-
- 30 [श्यो] विदितसकलशास्त्रः श्रीशुभानंदनामा । अलिखदवनिपालस्याज्ञया धर्म-
- 31 लेखी स्फुटललितनिवेशि(शै)रक्षरि(रै)स्ताम्रपट्टम(म्) ॥[७॥*] रजपालस्य पुत्रेण
पाञ्चणे-
- 32 न च सि(शि)ल्पिना । उत्कीर्णा वर्णघटना वेदध्वीविस्त्र(श्च)कर्मणा
॥[८॥*] मङ्गलमहाश्रीः ॥

¹ This expression appears to be new. Its exact implication is not understood. [Does it mean, "together with potter's mud and what has been left by merchants?" *Vāstavya* is applied to what is left as a worthless remainder on any spot.—Ed.]

² [Plural should be used.—Ed.]

³ *Atavika* I took to be "wild tribes", see above, Vol. XVI, p. 14, n. 1, but it indicates a Government Officer, viz., one in charge of the forest and wild tribes. This finds a mention even in Kaṭṭya's *Arthaśāstra*. See Dr. Sharma Sastri's Sanskrit Text, p. 254.

**C.—CHARKHARI PLATE OF VIRAVARMADĒVA : [VIKRAMA-]SAMVAT
1311.**

The present charter is the **earliest record** of the **Chandēlla** king **Viravarmadēva** yet found. The **copper-plate** on which it is engraved measures $15\frac{1}{8}$ " by $11\frac{3}{8}$ " and weighs $230\frac{1}{2}$ *tolas*. It has a raised rim, $\frac{1}{2}$ " in height, rivetted with nails all round it. In the middle of the first six lines there is a seated figure of the four-armed goddess **Lakshmi**, holding lotus flowers in the two upper, and water pots in the two lower, hands. Over her head is a semi-circular hole apparently meant for a ring, which is wanting. There are 19 lines of writing with well formed letters the size of which is $\frac{1}{8}$ " on an average.

The **language** is Sanskrit and the **orthographical peculiarities** are the same as found in other Chandēlla records published before. The record is not free from spelling and other mistakes, but they are comparatively fewer than in other similar records of the family.

The charter was **issued from Vilāsapura** by the **P. M. P. Viravarmadēva** the devout worshipper of Mahēśvara, and the **Lord of Kālāñjara**, son of the **P. M. P. Trailōkyavarman**, son of the **P. M. P. Paramarddidēva**, son of the **P. M. P. Madanavarmadēva**, descended from **Jayaśakti** and **Vijayaśakti**, the famous heroes belonging to the **Chandrātrēya** (Chandēlla) lineage. It records the grant of **Ṭumutūmā** village in the **Ḍāhī vishaya** to **Rāūta Abhi**, son of **Rāūta Haripāla**, son of **Rāūta Jagadēva**, son of **Rāūta Dēvashamū** of the **Kāśyapa-gōtra** belonging to the family of **Chandrēśvara**, on **Āśvina śudi 8, Sōmavāra, Samvat 1311**, which regularly corresponds to **Monday, the 21st September 1254 A.D.** The grantee is stated to have performed a deed of valour in a tussle with **Dabhyuhaḍavarman** in the battle of **Sōndhī**, as a **recognition whereof** this grant appears to have been made in spite of the fact that the purpose has been recorded as one for increasing the religious merit of the grantor **Viravarmadēva** and his parents. In the present case the grantee does not appear to have been a **Brāhmaṇa**, as the omission of his *pravara*s indicates. Moreover, the family name **Chandrēśvara** and the title **Rāūta** point to the same conclusion. Apparently **Sōndhī** is identical with **Seondhā** fort, now called **Kanhārgaḍh**, lying on the banks of the **Sind** river in the **Datia** State, whence it took its name. It is stated in the *State Gazetteer* (Luard's, p. 129) that "Seondhā is certainly an old town as the remains of the earlier settlement can be traced close to the present town. It has been suggested as the **Sarua** fort taken by **Mahmud** of **Gazni** in 1018 when in pursuit of **Chand Rai**". Our record refers to a battle a little more than a hundred years later, apparently between members of the same lineage, viz., the **Chandēllas**, if the termination of the opponent's name **Dabhyuhaḍavarman** would indicate anything to that effect. It must have been a battle of some importance to have been referred to as *saṅgrāma* or war. That was the time of disturbance as **Viravarmadēva's** grandfather **Paramarddidēva** had been defeated by **Prithivīrāja Chāhamāna** in 1182 A.D. In fact the late **Dr. V. A. Smith** remarks that "the history of the **Chandēlla** dynasty as one of the powers of Northern India ends in 1203 A.D. with the death of **Parmāl** (**Paramarddidēva**) and the capture of **Kālāñjara** and **Mahōbā** by the **Muhammadan** invaders. **Trailōkyavarman** succeeded his father **Parmāl** as a local chieftain holding the eastern part of the ancestral kingdom and in due course was succeeded by **Viravarman** and **Bhōjavarman**¹".

The other villages referred to in this record have not been traced yet.

¹ *Ind. Ant.*, Vol. XXXVII, p. 146.

TEXT.

- 1 ॥ ओं सिद्धिः ॥ जयत्याह्वाद्यन्विष्टं विश्वेश्वरसिरे(शिरो)धृतः ॥¹ चन्द्राते
(त्रे)यनरेन्द्राणां वंम(श)रुद्र इवोज्ज्वलः ॥[१॥*]
- 2 तत्र प्रवर्द्धमाने विरोधिविजयभा(भा)जिष्णु(णु)जयस(श)क्तिविजयम(श)[क्त्या]दिवो-
राविर्भावभाश्च(स्व)रे
- 3 परमभट्टार[क*]महाराजाधिराजपरमेश्वरश्रीमदनवर्मदेवपादानुध्यात्(त) ।¹ परम-
[भ*]ट्टारकम-
- 4 हाराजाधिराजपरमेश्वरश्रीपरमर्हिदेवपादानुध्यात् ।¹ परमभट्टारकमहाराजा-
धिराज-
- 5 परमेश्वरपरममाहेश्वरश्रीचैलोक्यवर्मदेवपादानुध्यात् ।¹ परमभट्टारकमहा-
- 6 राजाधिराजपरमेश्वरपरममाहेश्वरश्रीकालंजराधिपतिमहाराजश्री(श्री)महो-
- 7 रवर्मदेवो विजयी [१*] स एष दुवि(र्वि)षहतरप्रतापतापितसकलरिपुकुलः
कुलवधूमिव निराकुलां वसुं-
- 8 धरां परिपालयन्नविकलविवेकनिर्मलीकृतमतिः ॥ डाङ्गीविषयान्तःप[१*]तिटु-
मुटुमाग्रामोपगता-
- 9 न(न्) वा(वा)ह्मणानन्यांश्च मान्यान(न्) कुटुंबि(वि)कायस्थदूतवैद्यमेदचाण्डाल-
पय(य)न्तान(न्) समस्तप्रजालोकान्संबो(बो)ध-
- 10 यति समाजा(जा)पयति च अस्तु वः स(सं)विदितं यथोपरिलिखितोयं
ग्रामः सजल[स्थ]ल[१*] सस्थावरजंगमः
- 11 स्वसीमावच्छिन्न(न्नः) साधजर्डी(भृङ्ग(तभ)विथतव(व)र्तमाननिःसे(शे)षादाय-
सहितः प्रतिषिद्धा(चा)टादिप्रवेस(श)श्चास्माभिः श्री-
- 12 विलासपुरे संवत्(त्) १३११ आश्विनशुदि ८ सोमवारे पुण्यतीर्थोदकेन स्नात्वा
भास्करपूजापुर(रः)सरं मातापिचोरा-
- 13 लनः पुण्यशोषिवर्द्धये(वृद्धये) ।¹ व(चं)द्रेश्वरान्वये क[१*] स्य(श्य)पगोत्राय
राउतदेवषमूपपौत्राय राउतजगदेवपौत्राय राउतहरि-
- 14 पालपुत्राय सौधीसंग्रामे दभ्युहडवर्मयुवे कृतवीर्यातिस(श)ये प्रशा(सा)दे राउत-
षभिनाम्ने शासनीक(क्त)त्य प्रदत्त इति मत्वा
- 15 भण्डिराज(जा)श्रव[ल*]विधेयैर्भूत्वा भागभोगादिकं सर्व्वमस्मै² समुपनेतव्यं
तदेवमस्य ग्रामं समंदिरप्राकारं सनि[र्ग]मप्र-
- 16 वेसं(शं) [स*]वाद्या(वाह्या)भ्यन्तरादायं भुंजानस्य वा(वा)भ्रा केनापि न
कार्या । अत्र च । राजराजपुरुषादिभिः स्वस्वमाभाव्य(व्यं) परिहा(ह)-
तव्यमि-

- 17 दं चास्मत्(द)दानमनाहार्यं चेति भाविभिरपि भूमिपालैः पालनीयं । उक्तं
च । शंखं भद्रासनं कृत्वा वरास्त्रा(श्वा) वरवारणाः । भूमिदा-
18 न[स्य] पुष्पाणि फलं स्वर्गः पुरंदर ।[1२*] भूमिं यः प्रतिगृह्णा(श्वा)ति
यच्च(श्च) भूमिं प्रयच्छ(च्छ)ति ।[*] उभौ तौ पुन्य(स्य)कर्माणौ नियतौ
स्वर्गगामि-
19 नौ । [1१*] समवशेक्षतिक्षीणे कीपि राजा भविष्यति ।[*] तस्य
दासस्य दासोहं मम की[र्त्ति]र्ण(र्त्ति न) लोपयेत(त्) ।[४*] सुम(शुभं)
भवतु ॥

D.—CHARKHARI PLATE OF HAMMIRAVARMADEVA : [VIKRAMA-]SAMVAT
1346.

This is the first copper-plate charter of the Chandēlla king Hammiravarmadēva, whom I brought to notice, a decade ago, in my *Damoh Dipaka*, the *Hindī Gazetteer* of the Damoh district in the Central Provinces, from a *satī* record which I found in the village Bamhni of that district.¹ When I visited the Ajayagadh fort, I came upon another *satī* stone record² mentioning his name, which I included in the new account³ of the Ajayagadh fort inscriptions revised since the visit of General Sir Alexander Cunningham as detailed in his *Survey Report*, Vol. XXI. It appears to me that the Hamirpur district of the United Provinces, in which Mahōbā, the civil capital of the Chandēllas, is included, derives its name from this Chandēlla king. Of course, this district which borders on the Charkhārī State, took its name from the town of Hamirpur, which is situated on the confluence of the Jumnā and the Betwā, 110 miles north-west of Allahābād.

The record is engraved on a copper-plate 11½" long and 8½" broad, with a raised rim ½" in height running all round the plate and secured on the latter by nails. Its weight is 48 *tolas* only. In the middle of the first four lines of writing there is a figure of the four-armed goddess Lakshmi holding lotuses and water pots. On the top of the figure there is a hole for a ring which was either not put in or has been taken off and lost. The plate shows signs of corroding without serious damage to letters, which are rather small, their average size being ¼". The engraving is badly executed.

The language of the record is Sanskrit, the style being in the prescribed form used by the Chandēllas; but, from what little the writer composed, it is clear that he was no Sanskritist, as he has committed many spelling as well as grammatical mistakes. The insertion of the title *Sāhi* against the names of all the kings mentioned indicates the growing Muhammadan influence, which finally ousted the Chandēllas, apparently during the reign of the grantor of this very charter. Hammiravarmadēva, who styled himself as the *Paramabhāṭṭāraka Sāhi Rāj*.

¹ See above, Vol. XVI, p. 10, f. n. 4.

² The record runs as follows :—

L. 1. संवत्(त्) १२६८ समये यावच्चसुदि ६ बुधे

L. 2. सती बालसुभद्र मेने सा सुभे श्रीमहा-

L. 3. राजश्रीहमीरवर्मादेवराज्ये सुभौ मंग-

L. 4. लं करोति

³ Contributed to *Mādhyam*, a Hindi Journal of Lucknow, see Vol. V, pt. 2, number 2,

āvali-tray-ōpēta,¹ Lord of Kālāñjara, meditating on the feet of the P. M. P. *Sāhi Mahārāja* Viravarmadēva, who meditated on the feet of the P. M. P. *Sāhi Mahārāja* Trailōkyavarmadēva, who meditated on the feet of the P. M. P. *Sāhi Mahārāja* Paramarddidēva, announced the grant of Kō(or Kī?)kaḍagrāma in the *Vēdēsaitha-vishaya* to two Brāhmaṇas who were apparently brothers, on Sunday, the twelfth day of the dark fortnight of Bhādrapada and the Pushya-nakshatra in the Vikrama Samvat 1346, corresponding to Sunday, the 11th September, 1289 A.D.² It will be noticed that in his own case Hammiravarmadēva has left out the grandiloquent title of the *Mahārājādhirāja Paramēśvara*, which he duly attached to his elders. This indicates that either he was fully conscious of his reduced position, which induced him to be content with a humbler title, or that he was never recognised as the *Mahārāja* while his elder brother Bhōjavarmadēva was on the throne. In the Ajayagaḍh fort there is a *satī* record of Samvat 1346, which refers to the reign of Bhōjavarman.³ This copper-plate dated in the same year would therefore point to a usurpation of the throne, unless Bhōjavarman died in the same year before the month of Bhādrapada, when the grant under publication was made.

The document was written by Paṁ[ḍita*] Raṁ(Rāma)pāla.

The localities mentioned in the record are not traceable.

TEXT.

- 1 [ओ] सिद्धिः ॥ जयत्याल्हा(ह्वा)दयन्विश्वं विश्वस्वर(ख)रशिरोधृतः [।*]
चे(चं)द्रात्रेयनरेद्राणां वंशस्त्वं(चं)द्र
- 2 इवोज्ज्वल(लः) ।[।१॥*] तर्ज(त्र) प्रवर्द्धमाने विरोधिविजयभ्राजिपु(ण्)जयश-
क्तिविजयस(श)क्त्यादिरी(वी)रावे(वि)-
- 3 भ्राव(भवि)भास्वरः(रे) ।⁴ परमभट्टार(र)कमहाराजाधिराजपरमेस्व(ख)रपर[म]-
माहेस्वर(ख)रमा(सा)हि-
- 4 महाराज[ओ]मसन(मत्पर)मर्हि[दे]वपादानुध्यात्(त) ।⁴ परमभट्टारकमहाराजा-
धिराज पर-
- 5 मेस्व(ख)रपरममाहेसरे(ख)रसाहिर(म)हाराजश्रीमन्नैलोक्यवर्मदेवपादानुध्यात् ॥⁴
परम[भ]ट्टारक[म]हारा-
- 6 जाधिराजपरमेस्व(मेस्व)रपरममाहेसरे(ख)रसाहिरमहाराजश्रीमदीरवर्मद(दे)वपादा-
नुध्यात्(त) ॥⁴ परमभट्टार-
- 7 के(क)साहिराजाप(व)लीचभो(यी)पेतकाल(लं)जरा[धिप]तिमहाराजश्रीमह(ह)मी-
रवर्मा[देवी] विजय(यी) । स एख(ष) रु(दु)र्विषह-

¹This is exactly the title used in the Bamhni *satī* record which I misread as परमभट्टारकेजाधिराजावलीचयोपेत.
See above, Vol. XVI, p. 10, f. n. 4.

²In Bhādrapada of V.S. 1346, ba. 12 commenced on Sunday at '98 but the *nakshatra* Pushya ended on that day at '23.

³See *Mādheri*, Vol. V, pt. 2, number 2.

⁴Punctuation unnecessary.

- 8 तरप्रतापतावि(पि)तप्र(स)कलरि[पु]कुल(लः) कुलधूमिव वसुधरां निराकुसां
व(प)रिपलयन(न)विकलविवेकनि-
- 9 र्श(र्श)लोह(ल)तमतिता(र)स्नाभिः ॥¹ वेदेस्यविषयान्त(न्तः)पातिः(ति)कोकडग्राम-
गतान्वाङ्मणान्यांश्च(ग्रामोपगतान्वाङ्मणानन्यांश्च) मानकुटुंबि-
- 10 कायस्वनापितमहरनेदधीवरचोडालप्रजन्तान्सं(मानकुटुस्विकायस्वनापितमहरनेदधी-
वरचाङ्गालपर्यन्तान्सं)वो(वो)धयति समाप्तापयति च । व(व)स्तु वः
संविदितं यथा(थो)-
- 11 परलिखितोयं ग्रामः सजलस्थल(लः) सख्याय(व)रजंगमम(जंगमः) ससीरा-
(स्वसोमा)वह्नि(च्छिन्नः) साधऊर्द्धभूतभविष्यवर्त्तमा-
- 12 ना(न)नि(निः)[शिषादायसहितः*] र(प्र)ति[षि]डचाटादिक[प्रवेशः*] लोषागर-
पसणरधभूरुहनिधिनिषेप(लवणाकरपाषाणवनभूरुहनिधिनिषेप)[सहितः*] स-
वाङ्माभ्यन्तर(रः) अपरै[रपि] व[स्तु]भिः[*] ।
- 13 संवत्(त्) १३४६ समये ॥¹ भार(द्र)पदप(व)दि १२ रवौ ।¹ पुष्यनक्षत्रे ॥¹
भार्हा(रहा)जगोत्राय[य] ।¹ ठ¹ ।¹ सुभराजप्रपौत्राय ठ ।² विद्या-
- 14 ध]रप्रपौत्राय ।¹ ठ² ।¹ सठेलपुत्राय ।¹ पं ।¹ श्रीधर ।¹ पं ।¹ चाभि
(उभाभ्यां) चा(त्रा)ङ्माभ्यां को(or को)कडग्रामो . . . तोऽस्मलौ
(स्नाभिः ?) विजा-
- 15 वड ? वाराणा० ? वाषालि . . संकल्पेण(न) प्रदत्त[इ]ति । इति
मत्वा मन्य(भवद्भि)राज्ञाश्रवणविधेयैर्भूत्वा भाग-
- 16 भोगादिकं समुपनेतव्यं ॥ वडु(वडु)भिर्वसुधां(धा) भुक्त्वा राजभिस्सगरादिभिः
[।*] यस्य यस्य यदा भूमिं(मि)त(स्तु)-
- 17 स्व तस्य तदा फलं ॥१॥ षष्टि(षष्टिं) वर्षमहपा(सहस्रा)णि स्वये(र्गे) वसति
भूमिदः [।*] आह्वेता(आच्छेत्ता) वानुमन्ता च तानेव (तान्येव) न-
- 18 रक्तं व्रजेत् ॥२॥ स्वदत्तां परदत्तां वा यो हरेत्(त व)सु(सुं)धरां [।*]
म(स) विष्ठावा(यां) क्र(क्त)मिर्भूत्वा पितृभिस्सह मज्जति ॥३॥[*]
- 19 भूमिं षः(यः) प्रतिगृह्णीयात्(प्रतिगृह्णाति यस्तु) भूमिं प्रयच्छति [।*]
उभौ तौ पुन्य(स्व)कर्माद्यौ नियतौ स्वयं(र्गं)गामिनौ ॥४॥[*] पं रौ-
- 20 पाले[न] लिखितमिति ॥

¹ Punctuation unnecessary.² Abbreviation for Thākura or Thākura.³ Omit it.

1
 2
 3
 4
 5
 6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50
 51
 52
 53
 54
 55
 56
 57
 58
 59
 60
 61
 62
 63
 64
 65
 66
 67
 68
 69
 70
 71
 72
 73
 74
 75
 76
 77
 78
 79
 80
 81
 82
 83
 84
 85
 86
 87
 88
 89
 90
 91
 92
 93
 94
 95
 96
 97
 98
 99
 100
 101
 102
 103
 104
 105
 106
 107
 108
 109
 110
 111
 112
 113
 114
 115
 116
 117
 118
 119
 120
 121
 122
 123
 124
 125
 126
 127
 128
 129
 130
 131
 132
 133
 134
 135
 136
 137
 138
 139
 140
 141
 142
 143
 144
 145
 146
 147
 148
 149
 150
 151
 152
 153
 154
 155
 156
 157
 158
 159
 160
 161
 162
 163
 164
 165
 166
 167
 168
 169
 170
 171
 172
 173
 174
 175
 176
 177
 178
 179
 180
 181
 182
 183
 184
 185
 186
 187
 188
 189
 190
 191
 192
 193
 194
 195
 196
 197
 198
 199
 200
 201
 202
 203
 204
 205
 206
 207
 208
 209
 210
 211
 212
 213
 214
 215
 216
 217
 218
 219
 220
 221
 222
 223
 224
 225
 226
 227
 228
 229
 230
 231
 232
 233
 234
 235
 236
 237
 238
 239
 240
 241
 242
 243
 244
 245
 246
 247
 248
 249
 250
 251
 252
 253
 254
 255
 256
 257
 258
 259
 260
 261
 262
 263
 264
 265
 266
 267
 268
 269
 270
 271
 272
 273
 274
 275
 276
 277
 278
 279
 280
 281
 282
 283
 284
 285
 286
 287
 288
 289
 290
 291
 292
 293
 294
 295
 296
 297
 298
 299
 300
 301
 302
 303
 304
 305
 306
 307
 308
 309
 310
 311
 312
 313
 314
 315
 316
 317
 318
 319
 320
 321
 322
 323
 324
 325
 326
 327
 328
 329
 330
 331
 332
 333
 334
 335
 336
 337
 338
 339
 340
 341
 342
 343
 344
 345
 346
 347
 348
 349
 350
 351
 352
 353
 354
 355
 356
 357
 358
 359
 360
 361
 362
 363
 364
 365
 366
 367
 368
 369
 370
 371
 372
 373
 374
 375
 376
 377
 378
 379
 380
 381
 382
 383
 384
 385
 386
 387
 388
 389
 390
 391
 392
 393
 394
 395
 396
 397
 398
 399
 400
 401
 402
 403
 404
 405
 406
 407
 408
 409
 410
 411
 412
 413
 414
 415
 416
 417
 418
 419
 420
 421
 422
 423
 424
 425
 426
 427
 428
 429
 430
 431
 432
 433
 434
 435
 436
 437
 438
 439
 440
 441
 442
 443
 444
 445
 446
 447
 448
 449
 450
 451
 452
 453
 454
 455
 456
 457
 458
 459
 460
 461
 462
 463
 464
 465
 466
 467
 468
 469
 470
 471
 472
 473
 474
 475
 476
 477
 478
 479
 480
 481
 482
 483
 484
 485
 486
 487
 488
 489
 490
 491
 492
 493
 494
 495
 496
 497
 498
 499
 500
 501
 502
 503
 504
 505
 506
 507
 508
 509
 510
 511
 512
 513
 514
 515
 516
 517
 518
 519
 520
 521
 522
 523
 524
 525
 526
 527
 528
 529
 530
 531
 532
 533
 534
 535
 536
 537
 538
 539
 540
 541
 542
 543
 544
 545
 546
 547
 548
 549
 550
 551
 552
 553
 554
 555
 556
 557
 558
 559
 560
 561
 562
 563
 564
 565
 566
 567
 568
 569
 570
 571
 572
 573
 574
 575
 576
 577
 578
 579
 580
 581
 582
 583
 584
 585
 586
 587
 588
 589
 590
 591
 592
 593
 594
 595
 596
 597
 598
 599
 600
 601
 602
 603
 604
 605
 606
 607
 608
 609
 610
 611
 612
 613
 614
 615
 616
 617
 618
 619
 620
 621
 622
 623
 624
 625
 626
 627
 628
 629
 630
 631
 632
 633
 634
 635
 636
 637
 638
 639
 640
 641
 642
 643
 644
 645
 646
 647
 648
 649
 650
 651
 652
 653
 654
 655
 656
 657
 658
 659
 660
 661
 662
 663
 664
 665
 666
 667
 668
 669
 670
 671
 672
 673
 674
 675
 676
 677
 678
 679
 680
 681
 682
 683
 684
 685
 686
 687
 688
 689
 690
 691
 692
 693
 694
 695
 696
 697
 698
 699
 700
 701
 702
 703
 704
 705
 706
 707
 708
 709
 710
 711
 712
 713
 714
 715
 716
 717
 718
 719
 720
 721
 722
 723
 724
 725
 726
 727
 728
 729
 730
 731
 732
 733
 734
 735
 736
 737
 738
 739
 740
 741
 742
 743
 744
 745
 746
 747
 748
 749
 750
 751
 752
 753
 754
 755
 756
 757
 758
 759
 760
 761
 762
 763
 764
 765
 766
 767
 768
 769
 770
 771
 772
 773
 774
 775
 776
 777
 778
 779
 780
 781
 782
 783
 784
 785
 786
 787
 788
 789
 790
 791
 792
 793
 794
 795
 796
 797
 798
 799
 800
 801
 802
 803
 804
 805
 806
 807
 808
 809
 810
 811
 812
 813
 814
 815
 816
 817
 818
 819
 820
 821
 822
 823
 824
 825
 826
 827
 828
 829
 830
 831
 832
 833
 834
 835
 836
 837
 838
 839
 840
 841
 842
 843
 844
 845
 846
 847
 848
 849
 850
 851
 852
 853
 854
 855
 856
 857
 858
 859
 860
 861
 862
 863
 864
 865
 866
 867
 868
 869
 870
 871
 872
 873
 874
 875
 876
 877
 878
 879
 880
 881
 882
 883
 884
 885
 886
 887
 888
 889
 890
 891
 892
 893
 894
 895
 896
 897
 898
 899
 900
 901
 902
 903
 904
 905
 906
 907
 908
 909
 910
 911
 912
 913
 914
 915
 916
 917
 918
 919
 920
 921
 922
 923
 924
 925
 926
 927
 928
 929
 930
 931
 932
 933
 934
 935
 936
 937
 938
 939
 940
 941
 942
 943
 944
 945
 946
 947
 948
 949
 950
 951
 952
 953
 954
 955
 956
 957
 958
 959
 960
 961
 962
 963
 964
 965
 966
 967
 968
 969
 970
 971
 972
 973
 974
 975
 976
 977
 978
 979
 980
 981
 982
 983
 984
 985
 986
 987
 988
 989
 990
 991
 992
 993
 994
 995
 996
 997
 998
 999
 1000

INDEX.¹

| A | | PAGE | PAGE |
|--|--|--------------------|--|
| a, initial form of— | | 73 | Agnimitra, <i>Sunga k.</i> , 55 56, 75, 76 |
| ā, initial form of— | | 73 | agnishōma, a sacrifice. 4 |
| ā, medial form of— | | 59, 73 | agrahāra, 67, 69 |
| a, used for ri, | | 12 | aggrahāra, s. a. agraahāra, 67 |
| Abhi, m., | | 132, 134 | Aiḷa, dy., 85, 86 |
| abhishēka, | | 82 | Aindra-mahābhishēka, 82 |
| āchāras, five practices, | | 95 | ainūrvar = Svāmigaḷ (= five hundred Svāmins), 117, 121 |
| Ācharasa, a Sinda prince, 109, 110, 111, 114, 115, 119 | | | Aira, s. a. Aiḷa. |
| achāṣabhāṣapravēśyā, | | 124 | Aira (Aiḷa or Aiḷa), dy., 79, 80, 81, 82, 86 |
| Āchugi, s. a. Ācharasa I, | | 115, 119 | Aitarēya-Brahmana, a work, 82 |
| Āchugi I, a Sinda prince, | | 110, 111, 112 | Ajayagadh, fort, 134, 135 |
| Āchugi II, do. | | 110, 111, 112 | Ākāśa-Gangā, a celestial ri., 43, 45 |
| Āchugi III, do. | | 111, 113, 114 | Akkariga, 65 & n., 66 |
| Aḍavi(?)—Chā[ṁ]tisiri, wife of Khamdavisā- | | | akkariga-vritti, 66, 68, 70 |
| khamṇaḷa, | | 5, 13 | akshapaṭalika, an official, 128 |
| Aḍavi—Chātisiri, an Ikhāku princess, | | 13, 18, 26 | akshayanīvi (or akshaya-nīvi), 39, 44, 62, 63, 123 |
| āḍhaka, grain measure, | | 61 | aḷamā (= Skt. alinda ?), terrace in front of the |
| āḍhavāpa, land measure, | | 59, 61, 62 | house door, 27 |
| Adhichhatrā, vi., | | 75 | Alberuni, an author, 75, 87n. |
| adhishthān-ādhiparaka, City Council, | | 60, 61, 62 | Alinā copper-plate inscription of Śilāditya of |
| Adhapa, s. a. Mārgapati, | | 41 | Valabhipura dated Gupta Samvat 447, 98 |
| Adhvēśa, s. a. Mārgapati, | | 41 | Allūru, vi., 7 n., 10 |
| ādimaṇḍalika, an epithet of Āchugi I, | | 111 | alphabets— |
| Āditya, a god, | | 103 | Acute-angled or Siddhamātrikā (nail-head- |
| Āditya I, a Chōla k., 47, 48, 49 & n., 50 | | | ed or Kuṭila), 38 |
| Ādityadēva, a deity, | | 67, 69 | Brāhmī, 55 |
| Afghānistān, co., | | 76 | Dēvanāgarī, 38 |
| aga-pogala = Skt. agrya-pudgala, an epithet of | | | Gupta, 87n. |
| Buddha, | | 26 | Jaina, 64 letters of— 77 |
| āgara, | | 97, 99, 136 | Kannaḍa or Kanarese, 64, 90, 109 |
| Agāraghaṭṭavakatōka, | | 124 | Kharōṣṭhī, 76 |
| agidhema, mistake for agihōma (Skt. agnish- | | | Kuṭila lipi, 122 |
| tōma), | | 24 | Nāgarī, 125 |
| Agihāta, mistake for Agihōta (= Agnihōtra) | | 20 | Tamiḷ 47 |
| Agihōta, s. a. Agnihōtra, | | 17, 19, 21, 23, 24 | Amara, Amara-kōśa or Amarakōśa, a work, 39n., 81 |
| Agihot-Agithoma-Vājaṇey-Āsamēdha-yāji, an | | | Amarāvati, a Buddhist site, 2 |
| epithet of Siri-Chāntamūla, | | 26 | Amarāvati, a celestial city, 109, 115, 116, |
| agipathi (= Skt. agn-īshṭi ?), | | 79, 84 | 120 |
| agihōma, s. a. agnishōma, | | 17, 19, 20, 21 | Amarāvati, vi., 9, 10, 37 |
| agnihōtra, a sacrifice, | | 4 | Amarāvati inscription of Pulumāvi, 74 |
| | | | ā-mātrā, indication of —, by a wedge, 34 |

¹ My assistant Mr. N. Lakshminarayan Rao, M.A., has rendered immense help in checking this Index.

The figures refer to pages : n. after a figure, to footnotes; and add. to the additions. The following other abbreviations are used : —ch. = chief; co. = country; di. = district or division; do. = ditto; dy. = dynasty; E. = Eastern; f. = female; k. = king; m. = male; mo. = mountain; ri. = river; s. a. = same as; sur. = surname; te. = temple; vi. = village or town; W. = Western.

| | PAGE | | PAGE |
|---|----------------------------|--|---------------------------------------|
| Āmbūr inscription, | 49 | <i>aputrika-dravya, escheat property,</i> | 66 & n |
| Āṃga or Āṅga, co., | 57, 78, 80, 81, 85, 86, 88 | <i>Arahata-nisīdi,</i> | 80 |
| <i>Āṃga</i> or <i>Āṅga</i> , <i>Jaina canonical work</i> , | 77, 80, 89 & n. | <i>arahaṭṭa (=Skt. araghaṭṭa),</i> | 124 |
| Āṃgaja (=Cupid) | 117 | Āraṇyakūpagiri, | 97, 99 |
| Āṃṇigere, vi., | 113, 114 | Āraṇyavāsini, a form of <i>Durgā</i> , | 97, 99 |
| Āmōghavarsha I, a <i>Rāshtrakūṭa k.</i> , | 50 | Arasibīḍi, vi., | 111 |
| °amvu, mistake for °ambu, | 104 | <i>Arhat, Arahāt</i> or <i>Arihat, a Jina</i> , 60, 62, 63, 79, 86, 89, 89 | |
| Āṇahilapāṭaṇa, vi., | 81 | <i>arihaṃta, s. a. arhat,</i> | |
| <i>anaka, a suffix,</i> | 25 | Arikulakēsari s. a. Ariṇjaya, | |
| Āṇamalai inscription, | 51 | Ariṇjaya, a <i>Chōḷa prince</i> , | 47 |
| Ānanda or Ānanda, a <i>Buddhist teacher</i> or | | <i>Arthaśāstra, a work,</i> | 77 n., 81, 82, 87n. |
| monk, | 11, 17, 20, 27, 31 | Aruarni, s. a. Avarni, | |
| Ānanda Vāsēthiputra, an architect, | 83 | <i>asamedha, Skt. āsvamēdha</i> | |
| Anaṅga (=Cupid), | 127 | Āshādhasēna, a prince, | 75, 76 n. |
| <i>anāya,</i> | 94, 96 & n. | <i>Ashādhyāyī, a work</i> | 58 |
| Ānavas, | 81 | <i>Aśōka, a Maurya emperor,</i> | 8, 35, 56, 74, 77, 84, 85, 86n. |
| Āṇḍaja, family, | 102 | <i>Āsvamēdha, a sacrifice,</i> | 4, 18, 20, 21, 23, 55, 56, 57, 104 |
| Āṇḍanāṭṭu-Vēḷān, m., | 47, 52, 53 | Āṭapura inscription of Śaktikumāra, | 98 |
| Andhaka, a demon, | 101 | āṭavika, an officer, | 131 and n. |
| Andhraka, a <i>Śuṅga k.</i> , | 55 | <i>aṭmaṃga-maga-dhamachaka-pavataka (=Skt. ashṭāṅga-mārga-dharmachakra-pravartaka), an</i> | |
| Āndhras, people, | 84 | <i>epithet of Buddha,</i> | 22, 23, 26 |
| <i>aneka-hiraṃṇa-koṭi-go-satasahasā-hala-satasa-</i> | | <i>Atikāri (Adhikāri), a title,</i> | 94, 97 |
| <i>hasa-padāyi, an epithet of Siri-Chāṇṭamūla,</i> | 18, 24, 25, 26 | <i>aticchhita (i.e., atichchhita)=atita,</i> | 26 |
| <i>Āṅguttara-Nikāya, a work,</i> | 33 | Ava, dy., | 84, 88 |
| Āṇhilwada, s. a. Āṇahilapāṭaṇa, | | Ava, s. a. Avarni, | |
| <i>antarāṅga, an official,</i> | 102 | <i>Ava-rāja,</i> | 79, 84 |
| Antiochus III, a <i>Syrian k.</i> , | 76 | Avarāṃta or Avarānta, s. a. Aparānta or °ka, | |
| <i>anusvāra, initial forms of—,</i> | 72 | Avararasa, ch., | 112 |
| <i>anusvāra, medial forms of—,</i> | 72 | Avaraśaila, a <i>Buddhist convent</i> , | 9 |
| <i>anusvāra, omission of—,</i> | 11 | Avaraśilā, s. a. Avaraśaila | 9 |
| <i>anusvāra, used for m,</i> | 97 | Avarni, people, | 85 |
| <i>anusvāra, used for n,</i> | 122 | <i>Āvaśyakavṛitti, a Jaina work,</i> | 88n. |
| <i>anusvāra, used for nasals,</i> | 72 | <i>ayaka (=Skt. āryaka),</i> | 26 |
| <i>anusvāra, superfluous,</i> | 97, 122 | āyaka, | 2 and n. |
| Aparājita, a <i>Guhila k.</i> , | 98, 99 | āyaka-khambha or pillar, | 2, 3, 4 & n., 7, 9 |
| Aparājita, a <i>Pallava k.</i> , | 48, 49 & n., 50 | Āyagāvunḍa, m., | 67, 69 |
| Aparajita (=Skt. Aparājita), title of Demetrios, | 76 | <i>ayikā (ayyikā) (=Skt. āryikā),</i> | 26 |
| Aparamahāvinaseliya, a <i>Buddhist sect</i> , 4, 10, 14, 17, 19, 20, 21, 22, 26 | | ayira, s. a. Skt. ārya, | 13 |
| Aparānta(ka), co., | 7, 8, 22, 35 | <i>ayira-haṃgha or ayira-haṅga (=Skt. ārya-saṅgha),</i> | |
| Aparasela, a <i>Buddhist convent</i> , | 11 | <i>Buddhist community,</i> | 11, 17, 20, 26 |
| Apara-selika, a <i>Buddhist sect</i> , | 10 | Ayōdhyā, vi., | 6, 54, 56, 57, 75, 109, 115, 116, 120 |
| Aphaṣṭ stone inscription of Ādityasēna, | 38 | | |
| <i>appane,</i> | 94, 96 | | |
| apsidal shrine at Nāgārjunikoṇḍa, | 14, 36 | | |

The figures refer to pages : n. after a figure, to footnotes ; and add. to the additions. The following other abbreviations are used :—ch.=chief ; co.=country ; di.=district or division ; do.=ditto ; dy.=dynasty ; f.=female ; k.=king ; m.=male ; mo.=mountain ; ri.=river ; s. a.=same as ; sur.=surname ; te.=temple ; vi.=village or town ; W.=Western.

| | PAGE | | PAGE |
|--|--------------------------------------|--|-------------------------------------|
| Ayôdhe, <i>s. a.</i> Ayôdhyā, | | Betwā, <i>ri.</i> , | 135 |
| Ayuktaka, <i>official</i> , | 59, 61 and <i>n.</i> | Bezawādā, <i>vi.</i> , | 9 |
| B | | Bhada (= Skt. Bhadra), <i>m.</i> , | 22, 23, 25, 32 |
| Bactria, <i>co.</i> , | 76 | Bhadalapura, <i>s. a.</i> Bhadrapura or Bhadrā-
chalam, | |
| Baḍagāma, <i>s. a.</i> Bargaum, | 42 <i>n.</i> | Bhadalapura, <i>vi.</i> , | 85 |
| Bādube, <i>new-moon day of Vaiśākha</i> , | 65 and <i>n.</i> , 68, 70 | Bhadasiri (= Skt. Bhadrāsīrī), <i>f.</i> , | 22, 23, 32 |
| Bāgaḍage, <i>vi.</i> , | 115 | Bhadila, <i>m.</i> , | 22 |
| Bāgaḍage-70, <i>di.</i> , | 110, 113, 115, 118, 121 | Bhadrabāhu, <i>a</i> <i>Jaina author</i> , | 42 <i>n.</i> |
| Bagge-setti, <i>m.</i> , | 94, 97 | Bhadrabahu II, <i>a</i> <i>Jaina monk</i> , | 60 |
| Bahasatimita or ^o mitra, <i>s. a.</i> Brihaspatimitra,
<i>Magadha k.</i> , | 75, 76, 80, 84, 85, 88 and <i>n.</i> | Bhadrapa, <i>ch.</i> , | 91 |
| bāhirikā (= suburb), | 42 | bhāga-bhōga, | 133, 136 |
| Bāhlē, <i>m.</i> , | 131 | bhāga-bhōga-kara, | 107, 128 |
| Bāhūr plates | 48 | bhāga-bhōga-paṣu-hraṇya-karaśulka,
<i>Bhāgalabbe, a Chālukya queen</i> , | 130
69 |
| Bahusutiya (= Skt. Bahuśrutiya), <i>a</i> <i>Buddhist sect</i> ,
. | 11, 24, 31 | Bhāgavata-Purāṇa, <i>a</i> <i>work</i> , | 55, 84 |
| Bālāditya, <i>k.</i> , | 39, 40, 43, 44, 46 and <i>n.</i> | Bhāgiyabbēśvara, <i>te.</i> , | 67, 69 |
| Baḷagāmve, <i>vi.</i> , | 114 | bhājanta, <i>s. a.</i> bhadanta, | 17, 31 |
| Bali, <i>myth. k.</i> , | 81, 127 | bhāmkaṁ, mistake for khambham, | 11, 20 |
| Ballāḷa (or Ballāḷa), | 94, 96 and <i>n.</i> | Bhañja, <i>dy.</i> , | 100, 101, 102 |
| Bamḍāri Birusāmaṇi, <i>m.</i> , | 94, 97 | Bhānu, <i>a</i> <i>Jaina sage</i> , | 90, 92, 95 |
| Bamhni, <i>vi.</i> , | 134 | Bharadhavasa or Bharatavasa (= Bhāratavarsha),
<i>co.</i> , | 73, 78, 79, 82,
88 and <i>n.</i> |
| Bammarasa, <i>a</i> <i>Sinda prince</i> , | 109, 111, 112, 114, 115, 119 | Bharata, <i>an author</i> , | 83 |
| Bāṇa, <i>an author</i> , | 110, 118, 121 | Bharata, <i>myth. k.</i> , | 93, 96 |
| Banavāsi, <i>vi.</i> , | 8, 36, 84 <i>n.</i> | Bhārhut, <i>vi.</i> , | 75 |
| Bandhumati, <i>f.</i> , | 39, 41, 43, 45 | Bhasatimita, <i>s. a.</i> Bahasatimita,
Bhatidevā, <i>an</i> <i>Ikhāku princess</i> , | 5, 15, 24, 31 |
| Bankāpura, <i>vi.</i> , | 91 | Bhaṭṭa, | 65 |
| Bapisiriṇikā, <i>an</i> <i>Ikhāku queen</i> , | 4, 14, 19, 20, 31 | bhāṭṭa (= bhaṭa ?), <i>an official</i> , | 102 |
| Barābar caves, | 72 | Bhaṭṭa, <i>title of a Brāhmin</i> , | 66 |
| Barābar hills, | 78 | Bhaṭṭakajāṅka, <i>an author</i> , | 93 <i>n.</i> |
| Bārakūru, <i>di.</i> , | 90, 91, 93, 95 | bhaṭṭa-vṛitti, | 66, 67, 70 |
| Basārḥ, <i>a site</i> , | 7 | Bhaṭṭōji Dikshita, <i>a</i> <i>grammarian</i> , | 86 <i>n.</i> |
| Baudh plates of Raṇabhañja | 100 | Bhavabhūti, <i>an author</i> , | 40 |
| Bēdsā, inscriptions at—, | 84 | Bhāvana = Skt. Bhāpana, | 88 <i>n.</i> |
| Bellittage, <i>vi.</i> , | 114 | Bhāvaprakāśa, <i>a</i> <i>work</i> , | 39 <i>n.</i> |
| Belugula (= Śravaṇa-Belgoḷa), <i>vi.</i> , | 92, 94, 97 | bhayā, <i>s. a.</i> bhariyā = Skt. bhāryā, | 13 |
| Belvola, <i>di.</i> , | 66 | Bhikhu-rāja, <i>epithet of Khāravela</i> , | 80 |
| Belvola-Three Hundred, <i>di.</i> , | 64, 65, 67, 69 | Bhikkhu, <i>a</i> <i>Buddhist monk</i> , | 12 |
| Beṇachamatti, <i>vi.</i> , | 109 | Bhillama or Bhillamadēva, <i>a</i> <i>Yādava k.</i> , | 113 |
| Bendeyabhaṭāra, <i>m.</i> , | 67, 69 | Bhima Kratha, <i>a</i> <i>Yādava k.</i> , | 81 |
| Bettāda-Bhagavati, <i>a</i> <i>goddess</i> , | 67, 69 | bhīṅgāra or bhīṅgāra (= bhṛīṅgāra), | 79, 87 and <i>n.</i> |
| | | Bhoja, <i>title</i> ? | 84 |
| | | Bhōjadēva, <i>a</i> <i>Paramāra k.</i> , | 105, 106 |

The figures refer to pages : *n.* after a figure, to footnotes ; and *add.* to the additions. The following other abbreviations are used :—*ch.* = chief ; *co.* = country ; *di.* = district or division ; *do.* = ditto ; *dy.* = dynasty ; *E.* = Eastern ; *f.* = female ; *k.* = king ; *m.* = male ; *mo.* = mountain ; *ri.* = river ; *s. a.* = same as ; *sur.* = surname ; *te.* = temple ; *vi.* = village or town ; *W.* = Western.

| | PAGE | PAGE | |
|---|---|---|----------|
| Bhojaka, people, | 74, 78, 79, 84, 87 and n. | Budhā, f., 25, 31 | |
| Bhojaka, s. a. Mahābhōja, | 78 | Budhagupta, a Gupta k., 59, 61 | |
| Bhōjavarmadēva, a Chandēlla k., | 135 | Budhamnikā, f., 22, 23, 31 | |
| Bhujagabbarasi, a queen, | 66n. | Budhavānikinā, f., 22, 23, 31 | |
| bhukti, a territorial division, | 61 | Budhi (= Buddhi), f., 37 | |
| Bhūtaraprana (Bhūtārātī ?)-parvan, | 105, 107, 108 | Budhinna or Budhinaka, m., 22, 23 | |
| Bhūtapallikā, vi., | 126, 127 | Budhi[vā]niya, m., 22, 23, 31 | |
| Bhūti-Vikramakēsari, a Koḍumbālūr ch., | 47 | Bundelkhandi, dialect of Hindi, 125 | |
| Bhuvanaikamalladēva, a Chālukya k., | 111 | | |
| Bhuvaneśvar, vi., | 71 | C | |
| Bidar, vi., | 91 | Ceylon, an island, 10, 48 | |
| biḍāra, possibly s. a. birāḍa (a tax), | 94, 96 and n. | Ceylonee Convent, s. a. Sīhaḷa-vihāra 10 | |
| Bihār, vi., | 40n. | Chachcha, m., 123, 124 | |
| Bijjala or Bijjaladēva, a Sinda prince, | 110, 117, 121 | Chaidya, dy., 81 | |
| Bijjana (or ja), a Kalachurya k., | 109, 110, 112, 115,
118, 120 | chaitra-pavitra, 117, 121 | |
| bilama, s. a. bilma, | | chaka-lakhana-sukumāra-sujāta-chārana (= Skt.
chakra-lakṣaṇa°), an epithet of the Buddha, 22, 23 | |
| bilma, a helmet? | 79, 87 and n. | Chakrakōṭṭa, vi., 78 | |
| Birumāla Dugga, m., | 94, 97 | Chakra-kotyā, s. a. Chakrakōṭṭa, | |
| biffi, | 94, 96n. | Chakravartin, a title, 82, 110, 118, 121 | |
| Bodh-Gayā, vi., | 38, 42 | Chalikireṃmaṇaka = Chalikiranaṅka = Moon, 25, 28 | |
| Bodh-Gayā inscription of Mahānāman, | 38 | Chāluka or Chālukya, dy., 10, 67, 69, 75, 80, 81, 87n. | |
| Bōdhi, | 31 | Chālukya (Western), dy., 109, 110, 112, 115. | |
| Bodhi, f., | 22 | | 118 |
| Bōdhi image, | 46n. | Chālukya-Chōla, family, 78 | |
| Bōdhi or Sambōdhi, | 44, 46 | Chambā, a state, 57, 58 | |
| Bodhika, m., | 22, 31 | Chanda (= Skt. Chandra), m., 22, 23 | |
| Bodhi-rukha-pāsāda (= Skt. Bōdhi-vriksha-prā- | | Chandaladēvi, a Sinda queen, 110, 114, 116, 119 | |
| sāda), | 10, 22, 31, 36 | Chandamukha, a Buddhist monk, 12, 22, 23, 28 | |
| Bōdhisarṃma (= Skt. Bōdhi-Sarman), m., | 22, 23, 31. | Chāmṭa (= Kshānta or Chāndaka °), 26 | |
| Bodhisiri, f., | 7, 9, 12, 14, 22, 23, 31, 36 | Chāmtamūla, s. a. Siri-Chāmtamūla, | |
| Bodhi-tree, | 10 | Chāmtisiri or °rī, an Ikkhaku princess, 4 and n.,
5, 6, 7, 11, 13, 15, 16 and n., 17, 19, 21, 28 | |
| brahmādēya, | 47, 49, 54 | Chāmtisiripikā, s. a. Chāmtisiri, | |
| Brāhmaṇāntara (ōttara), | 106 | Chāṇḍala or Chāṇḍāla, 130, 133, 136 | |
| Brahmānda-Purāṇa, a work, | 81 | Chandēlla, dy., 126, 127, 129, 132, 133, 134, | |
| Brāhmaṇ-ōttara, | 61 | | 135 |
| Brahmaputra, vi., | 40 | Chandikā, a goddess, 97, 99 | |
| Brahmasōmabhautaka, name of a field, | 124 | Chandramañji (or °dēva), a teacher 110, 117, | |
| Brihadratha, a Maurya k., | 55 | | 120, 121 |
| Brihaspati-sūtra, a work, | 86n. | Chandragnpta, a Maurya k., 77 and n., 88n. | |
| Buddha, | 15, 17, 20, 21, 22, 23, 33, 39, 41, 42,
43, 44, 45, 46 and n., 129 | Chandragutti, di., 91 | |
| Buddhaghōṣa, an author, | 81 | Chandranātha, a Tirthamkara, 94, 97 | |
| Buddharāja, a Kaḷachuri k., | 80 | Chandrātreyā, s. a. Chandēlla, | |
| Buddhiam, a religion, | 10, 36, 88n. | Chandrēśvara, a family, 132, 133 | |
| Budha, s. a. Buddha, | | | |

The figures refer to pages: *n.* after a figure, to footnotes; and *add.* to the additions. The following other abbreviations are used:—*ch.*=chief; *co.*=country; *di.*=district or division; *do.*=ditto; *dy.*=dynasty; *E.*=Eastern; *f.*=female; *k.*=king; *m.*=male; *mo.*=mountain; *ri.*=river; *s. a.*=same as; *sur.*=surname; *te.*=temple; *vi.*=village or town; *W.*=Western.

| | PAGE | | PAGE |
|---|-----------------------------------|---|------------------------|
| days, lunar :— | | Dēvashamū, m., | 132, 133 |
| bright fortnight : | | Dēvavarmmadēva, a <i>Chandēlla k.</i> , | 126, 127 |
| 1st, | 90, 93 | Dēyīngere, a <i>tank</i> , | 65, 66, 68, 70 |
| 7th, | 129, 130 | <i>dha</i> , used for <i>tha</i> , | 11 |
| 5th, | 65, 67, 122, 123, 132, 133 | Dhama, m., | 25, 29, 37 |
| 12th, | 105, 106, 108 | <i>Dhama-chaka</i> (wheel of law), | 22, 23 |
| chaturdaśi | 110, 118 | <i>Dhama-rāja</i> , epithet of <i>Khāravela</i> , | 80 |
| 15th, | 105, 107, 108, 126, 127 | Dharmmaghosa (=Skt. Dharmaghōsha), | 24, 25, 29 |
| dark fortnight : | | Dhammagiri (=Skt. Dharmagiri), s. a. Nāha- | |
| 12th, | 135, 136 | rāḷlabōḍu, | |
| 13th, | 91 | <i>dhamma-mahāmāta</i> , an official, | 8, 35 |
| amāvāsyā, | 110, 117 | Dhammanandi, a <i>Buddhist monk</i> , | 12, 22, 23, 29 |
| days of the fortnight :— | | Dhammarakkhita, <i>do.</i> | 8 |
| 5th, | 4, 21, 22 | Dhana (°dēva, °bhūti), m., | 55, 56, 57 |
| 10th, | 4, 16, 17, 18, 19 | Dhānāidaha copper-plate, | 59 |
| 13th, | 22, 23 | Dhanaka, a <i>clan</i> or <i>family</i> , | 5, 18, 29 |
| days of the month :— | | Dhanakāṭaka or Dhāṇākāṭaka (Skt. | |
| 7th, | 61, 63, 64 | Dhānyakāṭaka, co., | 9 and n., 10, |
| days of the week :— | | | 11 |
| Ādityavāra, | 67 | Dhanapati (=Kubēra), a <i>demigod</i> , | 116, 120 |
| Monday, | 50, 51, 65n., 110, 117, 122, 129, | Dhanika, a <i>prince</i> , | 123 |
| | 130, 132 | Dhanōp inscription of Chachcha of Sam. 1063, | 123 |
| Monday (Sōmavāra), | 110, 117, 118, 126, 127 | Dhārā, vi., | 78, 106, 108 |
| Saturday, | 110, 121 | Dharanikōṭa, vi., | 9 |
| Sunday, | 65, 69, 90, 95, 135, 136 | Dhārāvarsha, <i>biruda</i> of <i>Rāshtrakūṭa k. Dhruva</i> , 48n. | |
| Sunday (Ādityavāra), | 93 | <i>dharma</i> , a <i>suffix</i> , | 40 |
| Tuesday, | 47, 50, 51, 53, 65, 110 | Dharmamita, s. a. Demetrios, | |
| Tuesday (Sevāy-kkiḷamai), | 52 | Dharmapāla, a <i>Pāla k.</i> , | 60 |
| Dēbuvaka, a <i>locality</i> , | 98, 99 | Dharmapuri plates of Vākpatirāja of V. S. 1031, | 105 |
| Dēmaladēvi, a <i>Sinda queen</i> , | 111, 114 | Dharmarāja, | 55, 57 |
| Demetrios, <i>Indo-Greek k.</i> , | 76, 79, 84, 87 | <i>Dharmasāstra</i> , | 67 |
| Demetrios II, <i>do.</i> | 76 | Dharmma, s. a. Dharmmanātha, | 93 |
| Denarius, a <i>Roman k.</i> , | 29 | <i>Dharmmalēkhin</i> , | 131 |
| dentals, cerebralisation of —, | 73 | Dharmmanātha, a <i>Jaina Tīrthamkara</i> , 90, 92, 93, 95, 96 | |
| desaka, a <i>preacher</i> , | 19, 29 | <i>Dharmmarājūā</i> mistake for <i>Dharmmarājēna</i> , | 55, 57 |
| dese, | 94, 96 | <i>dhātuvāra-parigahita</i> , | 16, 18, 19, 20, 29, 30 |
| Dēvabhūmi, a <i>Śuṅga k.</i> , | 56 | Dhāuli, vi., | 8 |
| Dēvachandradēva, a <i>Jaina teacher</i> , | 90, 92, 93, 96 | Dhāuli, inscriptions of Aśoka at—, | 84 |
| dēvadāna, | 49 | Dhāvagarttā, vi., | 122, 123, 124 |
| Dēvagiri, a <i>hill</i> (?), | 22, 23, 36 | Dhavalappadēva, a <i>Paramāra k.</i> , | 122, 123 |
| dēvakula (=a temple), | 97, 99, 116 | dhivara, | 136 |
| dēvāngas, one of the 18 <i>paṇas</i> , | 90n. | Dhōr, s. a. Dhāvagarttā. | |
| Dēvapālādēva, a <i>Pāla k.</i> , | 37 | Dhṛitipura, vi., | 102 |
| dēvarāja-sakata (=Skt. <i>dēvarāja-satkrīta</i>), an | | Dhruva, a <i>Rāshtrakūṭa k.</i> , | 48n. |
| epithet of the <i>Buddha</i> | 16, 18, 19, 20, 29 | Dhṛitivishṇu, m., | 62 |
| Dēvaśarmman, m., | 106, 108 | | |

The figures refer to pages : n. after a figure, to footnotes ; and *add.* to the additions. The following other abbreviations are used :—*ch.*=chief ; *co.*=country ; *di.*=district or division ; *do.*=ditto ; *dy.*=dynasty ; *E.*=Eastern ; *f.*=female ; *k.*=king ; *m.*=male ; *mo.*=mountain ; *ri.*=river ; *s. a.*=same as ; *sur.*=surname ; *ta.*=temple ; *vi.*=village or town ; *W.*=Western.

| | PAGE | | PAGE |
|--|---------------|---|-------------------|
| Gandhāra or Gandhāra, co., | 7, 22, 23, 35 | Gōvinda (=Krishṇa), | 116, 120 |
| gāṃvātī, | 68, 70 | Gōvinda II, a Rāshtrakūṭa k., | 84 |
| gaṇa, | 90n. | Govinda III, do. | 49, 50, 123 |
| ganana (=accountancy). | 79, 82 | Gōvinda-Bhaṭṭa, m., | 65, 69, 70 |
| gane wana, communal and professional guilds, | 90, 94 | Guhānandin, a Jaina monk, | 60, 62, 63 |
| Gandharva, a class of demi-gods, | 87 | Guhila, progenitor of the Guhila dy., | 123 |
| Gangā dy., | 49, 66 and n. | Guhila, dy., | 97, 98 |
| Ganges, ri., | 45, 88n. | Guhilot, a family, | 123 |
| Gārgī-śamhitā, a work, | 76 | Gummaḍidura, vi., | 10 |
| Garuda emblem, | 105 | Gummatanātha, s. a. Bāhubali (a Jaina saint), | 94, 97 |
| Garuda-Purāṇa, a work, | 58, 69n. | guṇasāsana, | 67, 68, 70 and n. |
| Gautama Buddha, s. a. Buddha, | 42 | Gupta, dy., | 60 |
| Gautamiputra Śātakarṇi, k., | 35, 74 | Gupti-Gupta, a Jaina pontiff, | 60 |
| Gautamiputra Śrī Yajña-Śātakarṇi, an Āndhra k., | 74 | Gurjara, co., | 123 |
| gentive case, use of—, | 58 | Gutta (= Gupta), | 116, 120 |
| gha, forms of—, | 73 | Gutti, vi., | 114 |
| ghatya, | 67, 69 | | |
| Ghattavāsini, a name of Durgā, | 122, 124 | H | |
| Ghōścārīvā Buddhist inscription, | 40n. | h, used for s in Kanarese, | 25 |
| Ghōsūndī inscription, | 56 | Hagasiri, m., | 25, 35 |
| Ghugrahāti copper-plates, | 60 | Hagharina, m., | 22, 23, 35 |
| Girivāja, s. a. Rājagriha, | 78 | Haihaya, dy., | 80 |
| Girnār, mo., | 92 | kala, a land measure, | 105, 107 |
| Girnār, Inscriptions of Aśoka at—, | 84 | half chronogram, | 100 |
| Giyaka, m., | 122, 123, 125 | hālū-dhāre, | 94, 96 |
| Goa, vi., | 35 | hanṅha (=Skt. sanṅha), | 35 |
| Gōgga, name of a field, | 124 | Hammasari, s. a. Hammasiri, | |
| Gōha, s. a. Guhila, Guhadatta or Guhāditya,
founder of the Guhila family, | 98 | Hammasiri, an Ikkhaku princess, | 4, 14, 19, 20, 35 |
| Gohālīka, vi., | 63 | Hammasirigikā, s. a. Hammasiri, | |
| Gōkarṇa, vi. and tirtha, | 92, 95, 97 | Hammiravarṃmadēva, a Chandelā k., | 134, 135 |
| Gōmmatasāra, a Jaina work, | 77, 89n. | Hamsasoma, an author, | 42n. |
| Goradhagiri (Gōrathagiri), s. a. Barābar hills, 73, 78, 79, | 87 | Haribhadra, do. | 88n. |
| | 87 | Hārībhadriya-vritti, a work, | 88n. |
| gō-rakshakas, one of the 18 paṇas, | 90n. | Haridāsa, m., | 62 |
| Gōshētapuñjaka. vi., | 61, 62, 63 | Haripāla, m., | 132, 133 |
| Gōtamiputa, an epithet of Śātakarṇi, | 6 | Harivaṃśa, an epic, | 11 |
| gōtias :— | | Harivaṃśa-Purāṇa, a Jaina work, | 81, 36 |
| Bhāradvāja, | 136 | Hastināpura, vi., | 116, 120 |
| Kātyapa, | 132, 133 | Hāthīgumphā, a cave, | 71, 72 |
| Kātyāyana, | 105, 106, 108 | Hebbāl inscription of Mārasimha II, | 66n. |
| Krishṇatrēya, | 126, 127 | Hemachandra, an author, | 88n. |
| Vatsa, | 130 | Hēmādri, do. | 88n. |
| Govagāma (=Gōpagrāma), vi., | 22, 23, 35 | Himālaya, mo., | 45 |
| Govapurī (=Skt. Gōpakapuri) s. a. Goa, | 35 | Hiramākha, a clan, | 5, 18, 19, 35 |

The figures refer to pages: *n.* after a figure, to footnotes; and *add.* to the additions. The following other abbreviations are used: *ch.*=chief; *co.*=country; *di.*=district or division; *do.*=ditto; *dy.*=dynasty; *E.*=Eastern; *f.*=female; *k.*=king; *m.*=male; *mo.*=mountain; *ri.*=river; *s. a.*=same as; *sur.*=surname; *t.*=temple; *vi.*=village or town; *W.*=Western.

| | PAGE | | PAGE |
|---|---|---|-----------------------------|
| <i>hiramṇa-kṣi-go-sahasahasa-hala-sahasahasa-pad-</i> | | J | |
| <i>āyi</i> , epithet of <i>Siri-Chāntamūla</i> , | 19, 20, 24, 35 | <i>Jagadēva</i> , <i>m.</i> , | 132, 133 |
| <i>Hirēmaṇṇūr</i> , <i>vi.</i> , | 113 | <i>Jagatēśvara</i> , a <i>god</i> , | 118, 122 |
| <i>Hirumuthuva</i> , a <i>locality</i> , | 22, 23, 36 | <i>Jaggayyapeṭa</i> , a <i>Buddhist site</i> , | 2, 3, 7, 10, 12 |
| <i>Hiuēn Tsiang</i> , a <i>Chinese pilgrim</i> , | 8, 9, 10, 11, 40, 60 | <i>Jainism</i> , <i>religion</i> , | 77, 88 <i>n.</i> , 95 |
| <i>hma</i> , form of—, | 59 | <i>Jaitugi</i> , a <i>Yādava k.</i> , | 113, 114 |
| <i>Horiuzi</i> palm-leaf manuscript, | 38 | <i>Jajhanti</i> , <i>s. a. Jējākabhukti</i> , | 126 and <i>n.</i> |
| <i>Hosūr</i> record, | 65 | <i>Jālihālu</i> , <i>co.</i> , | 91 |
| <i>Hoṭtūr</i> inscription (of <i>Saka 959</i>), | 65 | <i>Jambudēva</i> , <i>vi.</i> , | 61, 62 |
| <i>Hoysaḷa</i> , <i>dy.</i> , | 109, 112, 113, 114, 116, 119 | <i>Jambūdvipa</i> , | 109, 115, 118 |
| <i>Hugha</i> , <i>m.</i> , | 25, 35 | <i>janapada</i> , | 79 <i>n.</i> , 88, 106, 107 |
| <i>Hulgūr</i> inscription of <i>Saka 960</i> , | 65 | <i>Jānapada</i> , | 79, 87 <i>n.</i> |
| <i>Hūṇas</i> , a <i>tribe</i> , | 40, 41 | <i>Janēndra</i> , <i>s. a. narēndra</i> , | 40 <i>n.</i> |
| <i>Hutāśana</i> , a <i>god</i> , | 103 | <i>Jaśas</i> , mistake for <i>yaśas</i> , | 101, 102 |
| <i>Huvishka</i> , a <i>Kuṣāṇa k.</i> , | 7 | <i>Jayādbhudaya</i> , mistake for <i>Jayābhyudaya</i> , | 93 |
| | | <i>Jayakēśi</i> , a <i>Kādamba ch.</i> , | 112 |
| I | | <i>Jayamaṅgalā</i> , a <i>commentary on the Kāmasūtras</i> | |
| <i>i</i> , initial form of—, | 73 | of <i>Vātsyāyana</i> , | 83 |
| <i>ī</i> , medial form of—, | 73 | <i>Jayanandin</i> , a <i>Jaina monk</i> , | 60 |
| <i>Idaiyārru-nādu</i> , <i>di.</i> , | 46, 47, 51, 52, 53 | <i>Jayaśakti</i> , a <i>Chandēlla k.</i> , | 126, 129, 132, 133 |
| <i>Ikhāku</i> , <i>dy.</i> , | 2, 3, 4, 6, 7, 10, 16, 17, 18, 19, 20, 21, 22, 23, 24, 26, 27 | <i>Jayaimha</i> (II), a <i>W. Chālukya k.</i> , | 65 |
| <i>Ikhaku</i> (<i>Ikkhāku</i> = <i>Ikshvāku</i>), <i>myth. k.</i> , | 6 | <i>Jayastambha</i> , a <i>Chambā k.</i> , | 57 and <i>n.</i> |
| <i>Ikhāku-rāja-pavara-risi-sata-pabhava-vaṁsa-sambhava</i> (= <i>Skt. Ikshvāku-rāja-pravara-rishi-sata-prabhava-vaṁsa-sambhava</i>), an <i>epithet of the Buddha</i> , | 22, 27 | <i>Jayasvāmin</i> , <i>m.</i> , | 127 |
| <i>Ikkēri</i> - <i>Keḷadi</i> , <i>family</i> , | 91 | <i>jē</i> , used for <i>yē</i> , | 125 |
| <i>Ilā</i> or <i>Ilā</i> , <i>father</i> or <i>mother of Purūras</i> , | 80 | <i>Jējāka</i> , <i>s. a. Jayaśakti</i> , | 126 |
| <i>Ilamperunkāy-irukkai</i> , <i>vi.</i> , | 47, 51, 53 | <i>Jējākabhukti</i> , <i>kingdom</i> , | 126 and <i>n.</i> |
| <i>Ilāṅgōvēlār</i> , <i>ch.</i> , | 47 | <i>Jēntaka</i> , <i>m.</i> , | 97, 99 |
| <i>Immaḍi Sadāśiva-Nāyaka</i> , <i>sur. of Bhadrappa</i> , | 9 <i>n.</i> , 92 | <i>Jijhōti</i> , <i>s. a. Jējākabhukti</i> , | |
| <i>Indra</i> , a <i>god</i> , | 43, 45, 116, 120 | <i>Jina</i> , <i>Arhat</i> , | 60, 62 <i>n.</i> , 88 |
| <i>Indu-vāk-vīśanti-varīṣē</i> (= <i>Indu-vāk-vimśati-varīṣē</i>), | 100, 104 | <i>Jina</i> (= <i>Buddha</i>), | 44, 46 |
| <i>Inscription of Chitōr</i> dated <i>V. S. 1331</i> , | 98 | <i>jita-kāma-kodha-bhaya-harisa-tarisa-moha-dosa-sad[ā]pita-Māra-bala-dapa-māna-pasamana-kara</i> (= <i>Skt. jita-kāma-krodha-bhaya-harsha-tarsha-mōha-dvēsha-sadbāpita-Māra-bala-darpa-prasamana-kara</i>), an <i>epithet of the Buddha</i> , | 22, 28 |
| <i>īrai</i> , a <i>tax</i> , | 54 | <i>jita-rāga-dosa-moha-vipamuta</i> (= <i>Skt. jita-rāga-dvēsha-mōha-vipramukta</i>), an <i>epithet of the Buddha</i> , | 16, 29 |
| <i>Isānabhata</i> , <i>k.</i> , | 123 | <i>Jiva-Khaṇḍa</i> , a <i>part of the Gōmātasāra</i> , | 77, 89 <i>n.</i> |
| <i>Isvara</i> , <i>te.</i> , | 109 | <i>Jñān-āchāra</i> , | 95 <i>n.</i> |
| <i>Isvara-Bhaṭṭāraka</i> , a <i>god</i> , | 53, 54 | <i>Jodhpur</i> inscription of <i>Pratihāra Bāuka</i> , | 122 |
| <i>Iṭikarāḷlabōḍu</i> , a <i>mound</i> , | 3 | <i>Jōgimāra</i> cave inscription, | 81 <i>n.</i> |
| | | <i>jugala</i> , mistake for <i>yugala</i> , | 101 |
| | | <i>Junāgaḍh</i> rock-inscription of <i>Rudradāman</i> , | 35, 92 |
| | | <i>Justin</i> , an <i>author</i> , | 76 |

The figures refer to pages: *n.* after a figure, to footnotes; and *add.* to the additions. The following other abbreviations are used: —*ch.* = chief; *co.* = country; *di.* = district or division; *do.* = ditto; *dy.* = dynasty; *E.* = Eastern; *f.* = female; *k.* = king; *m.* = male; *mo.* = mountain; *ri.* = river; *s. a.* = same as; *sur.* = surname; *te.* = temple; *vi.* = village or town; *W.* = Western.

| | | PAGE | | | PAGE |
|--|---|---------------------------------|---|----------------------------|---------------------------|
| K | | | | | |
| <i>k.</i> doubling of —, after <i>r</i> , | | 59 | Kanakādri, <i>s. a.</i> Mēru, | | 115 |
| <i>k.</i> doubling of —, before <i>r</i> , | | 59 | <i>kānam</i> , a coin, | | 47, 52, 53, 54 |
| <i>k.</i> doubling of —, before <i>y</i> . | | 59 | Kanauj, <i>vi.</i> , | | 40 |
| Kadambapadraka, <i>vi.</i> , | | 105, 106, 108 | Kāñchi (Conjeeveram), <i>vi.</i> , | | 49 |
| Kaikēyī, <i>myth. queen</i> , | | 87 <i>n.</i> | <i>kanda</i> , | | 25 |
| Kailāsa, <i>mo.</i> , | | 43, 45 | Kaṇha-bemṇā, Krishṇavēṇī or Krishṇa- | | |
| Kaiśika, a Yādava <i>k.</i> , | | 81 | vēṇṇa, <i>s. a.</i> Krishṇā | | 83 |
| <i>kākupada</i> , a sign, | | 72 | Kanhārgaḍh, <i>s. a.</i> Seondhā, | | 132 |
| Kaḷachuri, <i>dy.</i> , | | 80 | Kānhēri, inscriptions at —, | | 84 |
| Kaḷachurya, <i>dy.</i> , | 109, 110, 111, 112, 113, 117, 120 | | <i>kāṇi</i> , a land measure, | | 53, 54 |
| Kaḷakappanagudḍa, <i>vi.</i> , | | 114 | Kannapa, <i>m.</i> , | | 65, 66 |
| Kalamēśvara, <i>te.</i> , | | 64 | Kannapayya, <i>m.</i> , | | 66 <i>n.</i> |
| Kālāñjara, <i>fort.</i> , | 126, 129, 132, 133, 135 | | Kannapennā or Kannabannā, <i>s. a.</i> Krishṇā | | |
| Kaḷantōpatina-bālke, a locality, | | 94, 96 | Kannavannā, <i>s. a.</i> Krishṇā, | | 1 |
| <i>kalañja</i> , a weight, | | 47, 53, 54 | Kāpūgra-gaṇa, mistake for Kāpūr°, | | 93 |
| Kalāra-kkūrram, <i>di.</i> , | | 53, 54 | Kāpūr-gaṇa, subdivision of the Jainas, | | 90, 92, 93, |
| Kalāra-kūrram, <i>vi.</i> , | | 47 | | | 95, 96 |
| <i>kaḷe</i> , a musical instrument, | | 65, 68, 70 | Kāp, Kāpi or Kāpu, <i>vi.</i> , | 89, 90, 92, 93, 94, 95, 96 | |
| Kali, <i>age</i> , | 115, 117, 118, 119, | 120 | Karabēṇā, <i>s. a.</i> Kaṇhabemṇā | | 83 |
| Kāldāsa, an author, | 8 <i>n.</i> , 55, 56, 75 | | Karaḍihalli record of Śaka 933, | | 65 <i>n.</i> |
| Kalīnga or Kalinga, <i>co.</i> , | 8, 36, 72, 73, 74, 77, | | <i>Karanika</i> , an official, | | 40, 42, 44, 45 |
| | 79, 80, 81, 82, 83, 84, 85, 86 and <i>n.</i> , 87, 88 | | Kārapuṇṇime, a parvan, | | 65 and <i>n.</i> , 68, 70 |
| <i>Kalīṅga-ādhipati</i> , title of Khāravela, | | 79, 81 | <i>kare</i> , | | 94, 96 |
| <i>Kalīṅga-chakravati</i> or <i>ādhipati</i> , title of Khāravela, | | 86 <i>n.</i> | Kariviḍi-30, <i>di.</i> , | 110, 112, 115, 118, 121 | |
| <i>Kālīṅga-Jina</i> , | | 80, 85, 88 <i>n.</i> | Karkkataṭaka, name of a tank, | | 124 |
| Kalīṅga, <i>dy.</i> , | | 86 <i>n.</i> | Karṇātaka, <i>co.</i> , | | 66, 111 |
| Kalīṅga or Kalīṅganagarī, <i>vi.</i> , | 77, 79, 83, 86 | | <i>Karṇātaka-Bhāṣhābhūṣhaṇa</i> , a work, | | 65 <i>n.</i> |
| Kalīṅgapatanam, <i>vi.</i> , | | 77, 83 | Karṇa, an epic hero, | | 127 |
| Kallūru, <i>vi.</i> , | 115, 117, 121 | | Karrali, <i>s. a.</i> Karṇalippirāṭṭiyār, | | 47 |
| <i>Kalpa-ūtra</i> , a work, | | 7 <i>n.</i> , 42 <i>n.</i> | Karṇalippirāṭṭiyār, queen of Parāntakan | | |
| Kāsi, Inscriptions of Aśoka at —, | | 84 | <i>Ṭāṅgōvēḷār</i> , | | 47 |
| Kalyāṇi, <i>te.</i> , | | 111 | <i>kārshāpaṇa</i> , a coin, | | 81 |
| <i>Kāṇṇadakṛṇa-nīṭisāra</i> , a work, | | 85 <i>n.</i> , 88 <i>n.</i> | Karumbudhina, <i>m.</i> , | | 22, 23, 27 |
| Kāmanṛpa (or Kāmadēva), a Pāṇḍya <i>ch.</i> , | 109, 112, | 116, 120 | Kasīā, <i>vi.</i> , | | 42 |
| <i>Kāma-ūtra</i> , a work, | | 83 and <i>n.</i> | <i>Kāśikā</i> , a work, | | 58 |
| Kambha, a Rāshtrakūṭa prince, | | 48 <i>n.</i> | <i>Kāśika-paṇcha-stūpa-nikāyika</i> , | | 62 |
| Kanadasiri, a Pāṇḍya <i>ch.</i> , | 4, 16 and <i>n.</i> , 17, 27 | | Kāsmira (Kashmir) (=Skt. Kāśmīra), <i>co.</i> , | 7, 22, 23, | 35, 40 |
| Kānta-setti, <i>m.</i> , | | 94, 97 | <i>kāsu</i> , a coin, | | 47, 52 and <i>n.</i> , 53 |
| Kampavarman, a Pallava <i>k.</i> , | | 48 and <i>n.</i> , 49 <i>n.</i> | Kāśyapēya, name of a field, | | 124 |
| Kānta (or Kānta°) kasala (=Skt. Kāntakaśaila), | | | Katgēri, <i>vi.</i> , | | 111, 112 |
| a locality | | 9, 10, 22, 23, 35 | Kātyāyana, an author, | | 90 <i>n.</i> |
| | | | Kausalyā, <i>myth. queen</i> , | | 87 <i>n.</i> |
| | | | Kauśāmbī, <i>vi.</i> , | | 81 |
| | | | Kauśikī, <i>f.</i> , | | 55, 57 |
| | | | Kautalya or Kauṭilya, an author, | | 81, 87 <i>n.</i> |

The figures refer to pages. *n.* after a figure, to footnotes; and *add.* to the additions. The following other abbreviations are used. —*ch.* = chief; *co.* = country; *di.* = district or division; *do.* = ditto; *dy.* = dynasty; *E.* = Eastern; *f.* = female; *k.* = king; *m.* = male; *mo.* = mountain; *ri.* = river; *s. a.* = same as; *sur.* = surname; *te.* = temple; *vi.* = village or town; *W.* = Western.

| | PAGE | | PAGE |
|---|-------------------------------|---|-----------------------------------|
| <i>kavaṇa</i> (=Skt. <i>kṛipana</i>), | 16, 27 | <i>Kōśālas, people</i> , | 83 |
| <i>Kāvyamīmāṃsā, a work</i> , | 88n. | <i>Kosam or Kauśāmbi, vi.</i> , | 75 |
| <i>kāya-nisīdi</i> , | 80 | <i>Kōtavumachgi, vi.</i> , | 64, 67 |
| <i>Kāyaastha, a caste</i> , | 123 | <i>Kōṭṭē-kōlāhala, a title</i> | 91 |
| <i>kāyaastha, scribe</i> , | 130, 133, 136 | <i>Koṭhākārika</i> (=Skt. <i>Kōṣṭhāgārika</i>), an official, | 7 |
| <i>Kaṣṭhadi, family</i> , | 91 | and n., 22, 23, 28 | |
| <i>Keḷavaḍi, vi.</i> , | 115 | <i>Kōṭṭitīrtha</i> , | 127 |
| <i>Keḷavaḍi-300, di.</i> , | 110, 113, 115, 118, 121 | <i>kōṭṭa, cow-pen</i> , | 68, 70 |
| <i>Kōraḷa, co.</i> , | 91, 123 | <i>Kottampalugu, a Buddhist site</i> , | 3, 5, 6, 15 |
| <i>Kēsaṇa, m.</i> , | 94, 97 | <i>krami</i> , mistake for <i>kṛimi</i> , | 135 |
| <i>Kēśavarasa, m.</i> , | 65 and n., 66 | <i>Krishṇā, vi.</i> , | 1, 2, 77 and n., 79, 83, 113, 114 |
| <i>Kēśavayya, m.</i> , | 64, 65, 67, 69 | <i>Krishṇavarṇā, s. a. Krishṇā</i> , | 1 |
| <i>kha</i> , forms of —, | 73 | <i>Krishṇavarṇā, s. a. Krishṇavēṇī</i> , | 83 |
| <i>Khaṇḍa</i> (=Skanda), | 26, 28 | <i>ksha</i> , form of —, | 59 |
| <i>Khaṇḍachalikireṇmaṇaka, ch.</i> , | 5, 18, 19, 28 | <i>kshaurakas, one of the 18 paṇas</i> , | 90n. |
| <i>Khaṇḍasāgarāṇṇ(or ṇ)aka</i> , | 4, 16 and n., 17, 21 | <i>Kuḍā, inscriptions at—</i> , | 84 |
| <i>Khaṇḍasāgarāṇṇaka, s. a. Khaṇḍasāgarāṇ-</i> | | <i>Kūḍepasiri or Kūḍepa, a Kalinga k.</i> , | 80, 82 |
| <i>naga</i> , | 28 | <i>kula</i> , | 90n. |
| <i>Khaṇḍavisākhanaka (or Khaṇḍavisākham-</i> | | <i>Kulahaka, a clan or family</i> , | 5, 10, 18, 19, 28 |
| <i>ṇaka), ch.</i> , | 5, 18, 28 | <i>Kulaha-vihāra, a monastery</i> , | 9, 22, 23, 28 |
| <i>khaniya</i> =pillar, | 24, 28 | <i>Kulaśēkhara, ch.</i> , | 112 |
| <i>khedā</i> , | 85 | <i>Kulōttuṅga-Chōḷa I, a Chōḷa k.</i> , | 78 |
| <i>Khāravēla, a Kalinga k.</i> , | 72, 73, 74, 75, 76, 77, 79, | <i>kūḷya, measure of grain</i> , | 61 |
| 80, 81, 82, 83, 84n., 85, 86 and n., 87n., | 88n., 89 | <i>kūḷyavāpa, land measure</i> , | 60, 61, 62, 63 |
| <i>Khatri, a caste</i> , | 7n. | <i>Kumārāmātya, an official</i> , | 102 |
| <i>Khema-rāja, epithet of Khāravēla</i> , | 80 | <i>Kumāranandin, a Jaina monk</i> , | 60 |
| <i>Khilīra-isi-tīla</i> , | 79, 83 | <i>Kumāri or Kumāri-pavata, a hill</i> , | 77, 80, 88 |
| <i>Khibīra, a fish</i> , | 86 | <i>kumbhālikas, one of the 18 paṇas</i> , | 90n. |
| <i>Khiṇḍjali-maṇḍala, di.</i> , | 100, 102 | <i>Kumbha-saṁkrānti</i> , | 110 |
| <i>Kikkana, m.</i> , | 126, 128 | <i>Kumbhaṭṭibhaṭagrāma, vi.</i> , | 126, 127 |
| <i>Kirāḍi, identified with Kirāyida</i> , | 129 | <i>Kuṇāla, son of Aśoka</i> , | 86n. |
| <i>Kirāta, a co. or a people</i> , | 7, 8 | <i>kūṇḍe</i> , | 64, 68, 70 |
| <i>kīrātas, one of the 18 paṇas</i> , | 90n. | <i>Kuntala, co.</i> , | 109, 115, 119 |
| <i>Kirāyida, di.</i> , | 129, 130 | <i>Kūrmēśvara, t.</i> , | 53 |
| <i>kirtti, pious deed</i> , | 39, 44, 46 | <i>kuraṇṭakas (kuraṇṭakas ?), one of the 18 paṇas</i> , | 90n. |
| <i>Kistna, s. a. Krishṇā</i> , | 1, 9, 10, 26 | <i>Kuru, myth. k.</i> , | 81 |
| <i>Kisukāḍu-70, di.</i> , | 110, 111, 112, 113, 114, 115, | <i>Kurugōḍ, vi.</i> , | 114 |
| 118, 121 | | <i>Kurukshētra, vi.</i> , | 68, 70 |
| <i>Kodabalisiṇi, a queen</i> , | 5, 15, 24, 28 | <i>kurura</i> (=kurube=a tender cocoanut?), | 68, 70n. |
| <i>Koḍumbāḷūr, dy.</i> , | 47 | <i>Kushāṇa, dy.</i> , | 73 |
| <i>Kō(or Kī)kaḍagrāma, vi.</i> , | 135, 136 | <i>Kusumadhvaṇa</i> , | 76 |
| <i>koḷaga, a measure</i> , | 117, 121 | <i>kutānta</i> , mistake for <i>kṛitānta</i> , | 101 |
| <i>Koṇika, k.</i> , | 88n. | <i>Kuṭumbin</i> , | 130, 133 |
| <i>Kopana, s. a. Kopaḷ, a Jaina ārtha</i> , | 92, 94, 97 | | |
| <i>Kōsala, co.</i> , | 55, 57, 75 | | |

L

| | |
|--|----|
| <i>l</i> , change of —, into <i>r</i> , | 80 |
| <i>la</i> , change of —, into <i>r</i> , | 86 |

The figures refer to pages : n. after a figure, to footnotes ; and *add.* to the additions. The following other abbreviations are used :—*ch.*=chief ; *co.*=country ; *di.*=district or division ; *do.*=ditto ; *dy.*=dynasty ; *E.*=Eastern ; *f.*=female ; *k.*=king ; *m.*=male ; *mo.*=mountain ; *ri.*=river ; *s. a.*=same as ; *sur.*=surname ; *te.*=temple ; *vi.*=village or town ; *W.*=Western.

| | PAGE |
|--|---|
| <i>Mahāpratihāra</i> , an official, | 7 |
| <i>Mahara</i> , | 136 |
| <i>Mahārabalikā</i> , mistake for <i>Mahārājābalikā</i> , | 4, 19 |
| <i>Mahārāja</i> , a title, | 5, 6, 73, 79, 84, 106, 135 |
| <i>Mahārājādhirāja</i> , a title or epithet, | 67, 69, 93, 95,
105, 106, 108, 117, 120, 122, 123, 126, 129,
133, 135 |
| <i>māhārājya</i> , | 86 |
| <i>Mahārakkhita</i> , a Buddhist teacher, | 36 |
| <i>Mahārāshtra</i> , co., | 78, 84n. |
| <i>Mahārāthi</i> , people, | 78 |
| <i>Mahārāthis</i> = <i>Rāthika</i> , | 78 |
| <i>Mahāsāmanta</i> , | 100, 102 |
| <i>Mahāsāmanta-dhipati</i> , | 64, 65 |
| <i>Mahāsandhivigrahādhipati</i> , official, | 65 |
| <i>Mahāsānghika</i> , a Buddhist sect, | 10 |
| <i>Mahāsēna</i> (Skanda), a god, | 6, 16, 17, 19, 20, 21, 23 |
| <i>Mahāsēnāpati</i> , a title, | 4, 5, 6, 7, 16, 17, 18, 19, 20,
21, 32 |
| <i>Mahāsēnāpatini</i> , an epithet, | 5, 7, 13, 18, 19, 32 |
| <i>Mahātālavara</i> , a title, | 4, 5, 6, 7 and n., 16, 17,
18, 19, 20, 21, 32 |
| <i>Mahātālavari</i> or <i>°rī</i> , a title, | 4, 5, 7, 13, 14, 16, 17,
19, 21, 32 |
| <i>Mahatara</i> , s. a. <i>Mahattara</i> . | |
| <i>Mahattara</i> , | 61, 97, 98, 130 |
| <i>Mahāvāda-vādīśvara</i> , biruda of <i>Munichandra-</i>
<i>dēva</i> , | 93 |
| <i>Mahāvagga</i> , a Buddhist work, | 81 |
| <i>Mahāvamsa</i> , a work, | 7 and n., 8, 10 n.,
28, 35, 48 |
| <i>Mahāvanaśūlā</i> , | 10 |
| <i>Mahāvihāra</i> , | 22, 23, 32 |
| <i>Mahāvijaya</i> , a palace, | 79, 86n., 88 |
| <i>Mahāvinaseliya</i> , s. a. <i>Apāramahāvinaseliya</i> ? | 10 |
| <i>Mahāvira</i> , a Jaina Tīrthankara, | 42, 72 |
| <i>Mahāyāna</i> , a sect, | 9 |
| <i>Mahēśvara</i> (= <i>Śiva</i>), a god, | 132 |
| <i>Māhēśvaras</i> , | 52, 53, 54 |
| <i>Mahisāsaka</i> , a Buddhist sect, | 11, 24, 25, 32 |
| <i>Mahisha</i> , co., | 81 |
| <i>Māhishmatī</i> , s. a. <i>Mahisha</i> , | 81 |
| <i>Mahōba</i> plates of Samvat 1230, | 128 |
| <i>Maisōlia</i> , co., | 9 |
| <i>Maisōlos</i> , s. a. the <i>Kṛishnā</i> , | 9 |
| <i>Majjhantika</i> , a Buddhist teacher, | 35 |

| | PAGE |
|---|--------------------------------------|
| <i>Majjhima-nikāya</i> , a Buddhist work, | 11, 17, 19, 32,
42n. |
| <i>malabathron</i> (<i>tamālapatram</i>), | 8 |
| <i>Mālāda</i> , m., | 39, 41 and n., 43, 44, 45, 46 and n. |
| <i>Malaprabhā</i> , ri., | 113, 114 |
| <i>Mālava</i> , co., | 123 |
| <i>Mālavikāgnimitra</i> , a work, | 55, 75 |
| <i>Malik</i> , a title, | 41 |
| <i>Malla</i> , co., | 81 |
| <i>Malla</i> , a demon, | 65n. |
| <i>Malla-dēsa</i> , co., | 91 |
| <i>Mallāri</i> , a form of <i>Śiva</i> , | 65n. |
| <i>Mallāru</i> , vi., | 91, 92, 94, 96 |
| <i>Mallinātha</i> , a commentator, | 7, 58 |
| <i>Mallūru</i> , s. a. <i>Mallāru</i> , | 92 |
| <i>Mamneya</i> , a religious division, | 117, 120n. |
| <i>māna</i> , a measure, | 117, 121 |
| <i>Mañaiyil-nādu</i> , di., | 49 |
| <i>Maṇakkāl</i> , <i>Maṇakkāl</i> or <i>Maṇakkāl</i> , vi., | 47, 51, 53, 54 |
| <i>māna-kuṭumbin</i> , | 136 |
| <i>Maṇamutti-ttiḍal</i> , a mound, | 53, 54 |
| <i>Mānavadharmasāstra</i> , a work, | 82 and n. |
| <i>Mañchapurī</i> , a cave, | 72 |
| <i>Mañchapurī</i> Cave inscription or record, | 80, 82, 86n. |
| <i>maṇḍala</i> , di., | 105 |
| <i>Mandara</i> , mythical mo., | 116, 119 |
| <i>Mandāraka</i> , name of a division, | 105, 106, 108 |
| <i>Mandasor</i> stone inscription, | 40 |
| <i>Māndhātā</i> plates of Jayasingha of V. S. 1112, | 105 |
| <i>māni</i> , | 66 and n., 68, 70 |
| <i>Maṅgala</i> (ā)-trayōdaśī, | 91, 94, 96 |
| <i>Mamgalūr</i> , vi., | 94, 97 |
| <i>Maṅgalūru</i> , di., | 90, 91, 93, 95 |
| <i>Maṇigārakēri</i> , vi., | 91 |
| <i>Maṇigaya</i> , mistake for <i>Majjhima</i> , | 20 |
| <i>Manōja</i> (= Cupid), | 116 |
| <i>Mānsēhra</i> , Inscriptions of Aśoka at—, | 84 |
| <i>maṇṭapa</i> (= Skt. <i>maṇḍapa</i>), | 14 |
| <i>Mantrin</i> , an official, | 39, 41, 43 |
| <i>Manu</i> , a sage, | 82, 87n. |
| <i>Manusmṛiti</i> , a work, | 66n., 67n. |
| <i>mānya</i> , a grant, | 67, 68, 69, 70 |
| <i>Māra</i> , a demon, | 22, 23 |
| <i>Mārakabbe-Bhaṭṭāri</i> , a deity, | 67, 70 |
| <i>Māraṇḍaiyaq</i> , a <i>Pāṇḍya</i> k., | 47, 48, 53 |

The figures refer to pages : s. after a figure, to footnotes ; and *add.* to the additions. The following other abbreviations are used :—*ch.* = chief ; *co.* = country ; *di.* = district or division ; *do.* = ditto ; *dy.* = dynasty ; *E.* = Eastern ; *f.* = female ; *k.* = king ; *m.* = male ; *mo.* = mountain ; *ri.* = river ; *s. a.* = same as ; *sw.* = surname ; *te.* = temple ; *vi.* = village or town ; *W.* = Western.

| | PAGE | | PAGE |
|---|--|---|--------------------------------------|
| Nārāṇjadaiyaṇ, s. a. Varaguna-Mahārāja I, | 48, 50, | months :— | |
| | 52 | Āśvina, | 91, 132, 134 |
| Mārasimha II, a Gaṅga ch., | 66n. | Bhādrapada, | 122, 123, 135, 136 |
| Māravaṇ Pūdiyār, s. a. Parāntakan Ilaṅgōvēlār, | 47 | Chaitra, | 110, 129, 130 |
| Māravarman, a Pāṇḍya k., | 50 | Dhanus, | 47, 53 |
| Mārgapa, Mārgapati or Mārgēśa, | 39, 41, 43 | Kārttika, | 90, 93, 95, 105, 106, 108 |
| Marmmakabhavaka, name of a field, | 124 | Katika, s. a. Kārttika, | 98, 99 |
| Maruṇnandana (= Bhīma), an epic hero, | 116 | Māgha, | 61, 63, 64, 105, 107 |
| Masalia, co., | 8, 9 | Mārgaśira, | 126 |
| Masulipatam, vi., | 9 | Mārgaśirsha, | 110 |
| Māt, ri., | 7 | Mārgasira, | 127 |
| Māthari (or ri) puta, an epithet, | 21 | Pausha, | 105, 107 |
| Māthariputa, s. a. Māghariputa, | 14 | Pushya, | 64, 65 and n., 67, 69, 110, 117, 121 |
| Mathurā, vi., | 26, 74, 76, 78, 87 | Vriśchika, | 50, 52 |
| Mattamayūra, a sect, | 105 | Mōśalas, s. a. Mūshikas, | 83 |
| matṭar, a land measure, | 66, 67, 68, 69, 70, 117, 118, 121, 122 | Mrichchhakatikā, a work, | 28 |
| mātuka, | 19 | Mt. Ābū inscription of Samarasimha, | 98 |
| Maunara Śrīdhara-Bhaṭṭa, m., | 64, 67, 69 | Mudrārākshasa, a work, | 75, 83n. |
| Maurya, dy., | 55, 73, 75, 77, 83, 88n. | Mukhalingēśvara, te., | 83 |
| Mēda, | 130, 133 | Muktāpīḍa Lalitāditya, a Kashmir k., | 40 |
| media changed into tenuis and vice versa, | 12 | Mūla, m., | 22 |
| Mēdini, a work, | 81 | Mūlarnnikā, f., | 22, 23 |
| Mēghadūta, a work, | 8n. | Mūla-Nāgiraṭṭa, vi., | 61, 62 |
| Menander, an Indo-Gk. k., | 76 | Mūla-saṃgha, a subdivision of the Jainas, | 90, 92, 95 |
| Mēru, a mythical mo., | 109, 115, 118 | Mūlavāṇiya, m., | 22, 23 |
| Mēruvarman, a Chāmbā k., | 57 and n., 58 | Mūlūra Belile, m., | 94, 97 |
| metres :— | | Munijaya-Sāhaṇi, m., | 110, 118, 121, 122 |
| Anushtubh, | 101, 106 | Munichandradēva, guru of Dēvaṇḍradēva, | 90, 92, 93, 96 |
| Indravajrā, | 106 | Murāri, ch., | 91 |
| Pushpitāgrā, | 101, 106 | murc, | 94, 96 |
| Śālinī, | 106 | Muriya-kāla, | 75, 80 |
| Śārdūlavikrīditam, | 39, 43n., 44n., 101 | Mūshikas or Musikas, people, | 83, 84n., 87 |
| Sragidharā, | 39, 43n., 44n. | Mūsī, ri., | 77 and n., 83 |
| Vasantatilakā, | 39, 44n., 101, 106 | Mūsika or Musika, co., | 83, 84 and n. |
| Mihirakula, a Hūṇa k., | 40 and n. | Mūsika-nagara or anagaram, vi., | 77, 79, 83, 84 |
| Milindapañha, a work, | 7, 8n., 35, 36 | Musika-nagara, s. a. Muziris (?), | 77n. |
| Mīmāṃsā, a school of Philosophy, | 66 | Mutāutha or Mutāutha-Bhaṭṭāgrahāra, | 129, 130 |
| Misā, f., | 25 | Mūvarkōvil inscription, | 47 |
| Misi (Skt. Miśri), f., | 22, 23 | Muziris, a port, | 84n. |
| mithuna, | 15 | | |
| mitra, name ending in, | 56 | | |
| Moda, m., | 37 | | |

N

| | |
|--------------------------------------|----|
| n, doubling of —, after r, | 59 |
| n, used for ñ, | 39 |

The figures refer to pages : n. after a figure, to footnotes; and add. to the additions. The following other abbreviations are used :—ch.=chief; co.=country; di.=district or division; do.=ditto; dy.=dynasty; E.=Eastern; f.=female; k.=king; m.=male; mo.=mountain; ri.=river; s. a.=same as; sur.=surname; te.=temple; vi.=village or town; W.=Western.

| | PAGE | | PAGE |
|--|---|---|-------------------------------------|
| <i>n</i> , used for <i>n</i> , | 97 | Nandivarman III, a <i>Pallava k.</i> , | 48, 49 and <i>n.</i> , 50 |
| <i>n</i> , used for <i>n</i> , | 90, 97 | Naṅgai-Varaṅga-Perumāṇār, a <i>princess</i> , | 47 |
| <i>na</i> , erratic use of —, | 72 | <i>nāpita</i> , | 51, 53, 54 |
| <i>naḍa</i> or <i>nala</i> , a <i>land measure</i> , | 63 and <i>n.</i> | Narasimha II, a <i>Hoysala k.</i> , | 136 |
| <i>nāḍu</i> , <i>assembly</i> , | 90 <i>n.</i> | Naravarmadēva, a <i>Paramāra k.</i> , | 105, 106, 107, 108 |
| Nāga, a <i>Buddhist monk</i> , | 12, 22, 23, 30 | Nārāyaṇa, a <i>god</i> , | 67, 69 |
| Nāgabōdhinikā, <i>f.</i> , | 22, 23, 30 | Nārāyaṇa, <i>m.</i> , | 105, 106, 108 |
| Nāgadāman, <i>m.</i> , | 122, 123 | <i>nārāya-nāḷi</i> , a <i>measure</i> , | 52, 53 |
| Nāgadēsiga, <i>m.</i> , | 66, 68, 70 | Nārddarikā, a <i>streamlet</i> ?, | 39, 43, 44, 46 |
| Nāgādityabhata, | 124 | Naregal, <i>vi.</i> , | 67 |
| Nāgamna, <i>m.</i> , | 22, 23, 30 | Nareyaṅgal-Twelve (12), <i>di.</i> , | 64, 67, 69, 110, 112, 115, 118, 121 |
| nāgakēsara, one of the four fragrant articles, | 39 <i>n.</i> | Nareyaṅgal, <i>vi.</i> , | 67, 115 |
| Nagara-śrēṣṭhīn, an official, | 61, 63 | Nareyaṅgal, <i>s. a.</i> Naregal, | 67 |
| Nagari, <i>vi.</i> , | 56 | nasal, changed into <i>anusrāra</i> , | 90 |
| Nāgārjuna, a <i>Buddhist monk</i> , | 9 | Nāsik cave inscription, | 35 |
| Nāgārjunikoṇḍa, a <i>Buddhist site</i> , | 2, 3, 4, 7, 9, 10, 11, 12, 15 | Nāthasārman (°rmā), <i>m.</i> , | 59, 61 and <i>n.</i> , 62, 63 |
| Nāgārjunikoṇḍa, a <i>hill</i> , | 1, 37 | Nāṭya-śāstra, a <i>work</i> , | 83, 87 <i>n.</i> |
| Nagatara, <i>m.</i> , | 25, 30 | navakama or navakamma, <i>foundation</i> , | 12, 17, 19, 20, 22, 30 |
| Nāgavarmā, an author, | 65 <i>n.</i> | navakammika, a <i>superintendent of building operations</i> , | 11, 12, 22, 23, 30 |
| Nāgiraṭṭa-maṇḍala, <i>di.</i> , | 60, 61 | Nava-rāṣṭra-maṇḍala, <i>di.</i> , | 126, 128 |
| Nāharāḷlabōḍu, a <i>mound or hill</i> , | 3, 14, 36 | Navy-Āvakāśikā, | 62 <i>n.</i> |
| Nāka or Nāki, a <i>Sinda prince</i> , | 109, 114, 115, 119 | Nēyanikā, an <i>Andhra queen</i> , | 74, 83 |
| nakshatras :— | | ñchchhya, form of—, | 59 |
| Aśvinī, | 50 | nēda (mēda), | 136 |
| Pushya, | 135, 136 | Neḍuñjaḍaiyaṇ, a <i>Pāṇḍya k.</i> , | 50, 51 |
| Sadaiyam or Satabhisaj, | 47, 50, 52, 53 | Nēminātha, a <i>Jaina Tirthamkara</i> , | 92, 95 |
| Nālanda, mistake for Nālandā, | 42 | Nēmiśvara, <i>s. a.</i> Nēminātha, | 94, 97 |
| Nālandā, <i>vi.</i> or <i>ancient site</i> , | 37, 38, 39 and <i>n.</i> , 40 and <i>n.</i> , 41, 42 <i>n.</i> , 43, 45, 46, 87 <i>n.</i> | Nibagutṭa, a <i>mound</i> , | 3 |
| nāḷi, a <i>measure</i> , | 46, 47, 52, 53 | nidhi, | 102 |
| nāḷinavaru, corrupt form of nāḷinavaru, | 90 <i>n.</i> | Nigraṇtha or Digambara Jains, | 60, 63 and <i>n.</i> |
| nāḷinavaru (assembly), | 90 and <i>n.</i> , 94 | nikapanika, | 21, 30 |
| Nallimaṅgalam, <i>vi.</i> , | 46, 51, 52 | nikāya, | 62 <i>n.</i> |
| Nambi, a <i>saint</i> , | 110 and <i>n.</i> , 117, 121 | nikkil, | 94, 96 |
| Namda or Nanda (Namda-rāja), <i>k.</i> , | 75, 84, 87 and <i>n.</i> , 88 and <i>n.</i> | nilaikkaḷam, | 52 and <i>n.</i> , 53, 54 |
| Nānāghāt inscriptions, | 74, 83 | Niḷgund inscription of Taila II, | 65 |
| Nanda, <i>dy.</i> , | 84 | Nirmalā, <i>f.</i> , | 39, 41, 44, 46 |
| Nanda or Nanda Vardhana, <i>k.</i> , | 75 | nishēpa (= nishēpa), | 136 |
| Nandi-Kampēsvara, <i>te.</i> , | 48 | Nishidī or Nishidhī, a <i>Jaina tomb</i> , | 89 <i>n.</i> |
| Nandippōttaraiyar, <i>s. a.</i> Nandivarman, | 52 | nithapita, or neṭhapita, | 19, 20, 30 |
| Nandippōttaraiyar, a <i>Pallava k.</i> , | 46 | | |
| Nandivarman, <i>do.</i> , | 48, 49 and <i>n.</i> , 50, 51 | | |
| Nandivarman II, <i>do.</i> , | 48, 50 | | |

The figures refer to pages : *n.* after a figure, to footnotes ; and *add.* to the additions. The following other abbreviations are used :—*ch.*=chief ; *co.*=country ; *di.*=district or division ; *do.*=ditto ; *dy.*=dynasty ; *E.*=Eastern ; *f.*=female ; *k.*=king ; *m.*=male ; *mo.*=mountain ; *ri.*=river ; *s. a.*=same as ; *sur.*=surname ; *ta.*=temple ; *vi.*=village or town ; *W.*=Western.

| | PAGE | | PAGE |
|--|----------------------|--|--|
| Nitva-Gôhâli, vi., | 61, 62, 63 | <i>paduka-paṭa</i> (= <i>pāduka-paṭṭa</i> or <i>pātuka</i> °, or | |
| <i>nivartana</i> , a land measure, | 105, 106, 108 | <i>patuka</i> °), footprint slab, | 37 |
| <i>nivāsa</i> =Skt. <i>nirvāsa</i> , | 80, 85, 88n. | Paduma, m., | 25, 30 |
| Northern Kshatrapa, dy., | 55 | Padumā (= Padmā), f., | 25, 30 |
| Nripatunga, a Pallava k., | 48 and n., 49, 50 | Padumavāni, f., | 15, 25, 30 |
| Nripatungavarman, do., | 47 | Pāhārpur, vi., | 59, 60 |
| numerical sign or symbol for:— | | Pahupappakapālī, | 124 |
| 1, | 12, 59 | Palāsātṭa, vi., | 61, 62 |
| 3, | 12, 22 | Pālēr, ri., | 2 |
| 4, | 12, 22, 59 | Pālhapā, an engraver, | 129, 131 |
| 5, | 12, 21, 22 | Pallava, dy., | 9n., 10, 46, 48, 49, 84 |
| 6, | 12, 21 | Pallavamalla, epithet of Nandivarman II, | 48, 49 and n., 50 |
| 7, | 22, 59 | Palura, s. a. Dantapura, | 8, 36 |
| 8, | 12, 21, 22 | [Pa]lura, vi., | 22, 23 |
| 9, | 59 | <i>pañchamahāpātaka</i> , | 69 |
| 10, | 12, 22, 23 | <i>pañcha-mātuka</i> , | 17 |
| 50, | 59 | Pañḍa=Skt. Pāṇḍya, | 85 |
| 70, | 12, 19 | <i>pañdu</i> , mistake for <i>pañcha</i> , | 19 and n. |
| 100, | 12, 19, 59 | Pamḍa-Rāja, | 78, 80 |
| 700, | 99 | Pañnagāma(=Skt. Parna-grāma), vi., | 17, 19, 36 |
| Nyāsa, a work, | 66 and n., 67, 70 | <i>paṇa</i> , a sectarian division, | 90n. |
| O | | <i>paṇa</i> , a coin, | 66, 68, 70 |
| O, initial form of—, | 73 | <i>pañc-āchāra</i> , five religious practices, | 95 |
| O, use of—, in mas. stems ending in a, | 73 | Pañchāla, co., | 76 |
| Ōdra, co., | 81 | <i>pañchāla</i> , one of the 18 <i>paṇas</i> , | 90n. |
| Ōdraka, a Śuṅga k., | 75, 76 and n. | Pañchaladēva, a Gaṇya chief, | 66 |
| Ōhila, a saint, | 110 and n., 117, 121 | <i>pañcha-mahā-śabda</i> , | 100, 102 |
| Om or Siddham, symbol for—, | 43n. | <i>pañc-ānantarya</i> , five sins, | 39, 44 |
| omission of doubling of consonants, | 73 | <i>pañcha-nikāyika</i> , | 62n. |
| omission of top lines in <i>sa</i> , <i>ma</i> and <i>ya</i> , | 38 | Pañcha-stūpa, | 62n. |
| Ōmpur, s. a. Sōmapura, | 60 | <i>Pañcha-stūpa-kula-nikāyika</i> , | 62, 62n. |
| Orkhon Inscriptions, | 41 | <i>Pañcha-stūpa-nikāya</i> , | 60 |
| <i>ovaraka</i> (=Skt. <i>apavaraka</i>), | 27 | <i>Pañchatantra</i> , a work, | 8 |
| P | | Pāṇḍi, m., | 104 |
| <i>p</i> changed to <i>v</i> , | 12, 25 | Pāṇḍu, epic k., | 85 |
| <i>pa</i> , standing for <i>pakṣa</i> , | 16, 18, 19, 20, 21 | Pāṇḍulēṇa cave inscription, | 74, 83 |
| <i>pa</i> , forms of—, | 73 | Pāṇḍya, dy., | 48, 49, 50, 77, 85, 88, 109, 112, 116, 119 |
| Pabhosā, vi., | 75, 76n. | Pāṇḍyakulapati, a title of Varaguṇa-Mahārūya, | 47, 52, 53 |
| <i>padhāna-sālā</i> (=Skt. <i>pradhāna-sālā</i>), | 30 | Paṅguṣa-bāji, | 90, 93, 95 |
| <i>paḍihāra</i> =(Skt. <i>pratihāra</i>), | 85 | Pāṇini, a grammarian, | 58, 86n., 88n. |
| <i>pāḍiyo</i> , | 79, 83 | Pāpē, m., | 130 |
| <i>Padma-Purāna</i> , a work, | 82, 83 | Papilā, a locality, | 22, 23, 36 |
| Padmini, a class of women, | 43, 45 | Pāpinadi, a field, | 94, 96 |

The figures refer to pages : *n.* after a figure, to footnotes; and *add.* to the additions. The following other abbreviations are used:—*ch.*=chief; *co.*=country; *di.*=district or division; *do.*=ditto; *dy.*=dynasty; *E.*=Eastern; *f.*=female; *k.*=king; *m.*=male; *mo.*=mountain; *ri.*=river; *s. a.*=same as; *sup.*=surname; *te.*=temple; *vi.*=village or town; *W.*=Western.

| | PAGE | | PAGE |
|---|---|--|---|
| Parachakrakōlāhala, (Śrīmāra Śrīvallabha—), | | Perma-Jagadēkamalla, a <i>Chāḥukya k.</i> , | 112 |
| a <i>Pāṇḍya k.</i> , | 48 | Permmāḍi III, a <i>Sinda prince</i> , | 111, 112 |
| Parakēsarivarman, a <i>Chōḷa k.</i> , | 47 | Perumāṇaḍigal, a <i>god</i> , | 53, 54 |
| <i>Paramabhāṭṭāraka</i> , a <i>title</i> , | 61, 63, 67, 69, 105,
106, 108, 117, 120, 122, 123, 126, 129, 133,
135 | <i>Perumāṇaḍigal-aḍiyāṇ</i> , a <i>title</i> , | 49n. |
| <i>Paramāgama</i> (sacred Jaina literature), | 77 | Phalgudēva, | 55, 56, 57 |
| <i>Paramamāhēśvara</i> , a <i>title</i> , | 129, 133,
135 | <i>pitalahāra</i> , <i>brazier</i> , | 129 |
| <i>Paramarddidēva</i> , a <i>Chandēlla k.</i> , | 129, 132,
133, 135 | Pīthumḍa, <i>vi.</i> , | 73, 78, 85, 88 |
| <i>Paramēśvara</i> , a <i>title</i> , | 67, 69, 105, 106, 108, 117,
120, 122, 123, 126, 127, 129, 133, 135 | Pitinakas, <i>people</i> , | 84 |
| Parāntaka, <i>title of Neduṇjaḍaiyaṇ</i> , | 51 | <i>pituchchā</i> , a <i>father's sister</i> , | 10, 31 |
| Parāntaka I, a <i>Chōḷa k.</i> , | 47 | <i>Pitundra</i> , s. a. Pīthumḍa, | 78, 79 |
| Parāntakan Ilaṅgōvēlār, <i>ch.</i> , | 47 | Pkt. <i>chau</i> > <i>ho</i> , | 73 |
| Pārāsari, <i>f.</i> , | 56 | Podhiya, s. a. pāḍiyo (?) | 83 |
| <i>parigaḥa</i> (=Skt. <i>parigraha</i>), | 30 | Polugubōḍu, a <i>mound</i> , | 15 |
| <i>parigahita</i> , | 17, 19, 20, 21, 23 | <i>Pora</i> (=Skt. <i>Paura</i>), | 79, 87n. |
| <i>parigamhita</i> , mistake for <i>parigahita</i> , | 20 | Prabhākara, an <i>author</i> , | 66 |
| <i>parihāra</i> , | 85 | <i>Prabhākara</i> , a <i>work</i> , | 66, 67, 70 |
| <i>parikeliti</i> (<i>parikelettēvāru</i> ?), one of the 18 <i>paṇas</i> , | 90n. | <i>Prakīrṇaka</i> , | 77 |
| <i>pārikkhāya</i> , | 68, 70 | <i>Prathama-Pustapāla</i> , | 62 |
| <i>parināmetuna</i> [m], | 19n., 20, 31 | <i>prastha</i> , a <i>measure</i> , | 61 |
| <i>parisara</i> (enclosure), | 88n. | <i>pratijāgarāṇaka</i> , <i>di.</i> , | 105, 106, 108 |
| <i>parva</i> , a <i>measure</i> , | 106, 108 | <i>prāṭila-Tikina</i> , | 39, 41, 43 |
| Parvata, identified with Śrīśaila, | 92, 94, 97 | <i>pratinivāsina</i> , | 106 |
| <i>pasada ka</i> (=Skt. <i>prasādaka</i>), | 21, 31 | pravaras:— | |
| <i>pāsaṁḍa</i> , | 80 | Atri-Archchanānasa-Śyāvāśva, | 127 |
| <i>pasana</i> (= <i>pāshāna</i>), | 136 | Kātyāyana-Kapila-Viśvāmitra, | 106, 108 |
| <i>paṭa</i> , a <i>slab</i> , | 25, 30 | Vatsa-Bhārggava-Chyavan-Apnuvān- | |
| <i>Paṭalaka</i> ? | 89 | Aurvva-Jāmadagnya, | 130 |
| <i>Pāṭila-khaṇḍa</i> , a <i>section of the Padma-Purāṇa</i> , | 83 | Prithvidhara Vāstavya, <i>m.</i> , | 129 |
| <i>Pāṭaliputra</i> , <i>vi.</i> , | 75, 76, 77, 85 | Prithvirāja, a <i>Chāhamāna k.</i> , | 132 |
| <i>Patañjali</i> , an <i>author</i> , | 55 | Prithvipati, I, a <i>Western Gaṅga k.</i> , | 49, 50 |
| <i>patipadā</i> (=Skt. <i>pratipadā</i>), | 37 | <i>Prithvivallabha</i> , a <i>title</i> , | 67 |
| <i>patraka</i> , one of the four <i>fragrant articles</i> , | 39n. | Prithvivarmmadēva, a <i>Chandēlla k.</i> , | 129 |
| <i>Paṭṭakila</i> , <i>official</i> , | 106, 107, 108 | Prishthima-pōttaka, <i>vi.</i> , | 61, 62, 63 |
| <i>paṭṭamahādēvi</i> , a <i>title</i> , | 113 | Prithu, <i>myth. k.</i> , | 82 |
| <i>Paurava</i> , a <i>clan</i> , | 81 | Ptolemy, an <i>author</i> , | 8, 9, 78, 84, 85 |
| <i>pravajita</i> (=Skt. <i>pravarjita</i>), | 21, 31 | Pubba-sela, a <i>Buddhist convent</i> , | 11 |
| <i>pavitra</i> , | 117, 121 | Pubba-selika, a <i>Buddhist sect</i> , | 10, 11 |
| <i>Perggaḍe</i> , <i>official</i> , | 66n. | Pūdi-Ādichchapidāriyār, <i>queen of Arikula-</i> | |
| <i>Periplus</i> , a <i>work</i> , | 8 and n., 9 | <i>kēsari</i> , | 47 |
| <i>Perma</i> , a <i>Sinda prince</i> , | 109, 112, 114, 116, 119 | Pūdiyār, | 47 |
| <i>Permmāḍi</i> , a <i>Sinda ch.</i> , | 112, 113, 114 | Pugiya, Pūgiya, Pūgiya, Pūkiya or Pūkiya, | 4n.,
5, 12, 16n., 17, 19, 20, 21, 31 |
| | | Puligere-Three Hundred, <i>di.</i> , | 64, 65, 69 |
| | | Pulindaka, a <i>Suṅga k.</i> , | 55 |
| | | <i>puḷḷi</i> or <i>virāma</i> , | 47 |

The figures refer to pages : n. after a figure, to footnotes ; and add. to the additions. The following other abbreviations are used :—*ch.*=chief ; *co.*=country ; *di.*=district or division ; *do.*=ditto ; *dy.*=dynasty ; *E.*=Eastern ; *f.*=female ; *k.*=king ; *m.*=male ; *mo.*=mountain ; *ri.*=river ; *s. a.*=same as ; *sur.*=surname ; *te.*=temple ; *vi.*=village or town ; *W.*=Western.

| | PAGE | | PAGE |
|--|------------------------|---|----------------------------|
| Pulunāvi, an <i>Āndhra k.</i> , | 74 | Rajapāla, <i>m.</i> , | 131 |
| Puṇḍra, <i>co.</i> , | 81 | Rājaparamēśvara, a <i>title</i> , | 93 & <i>add.</i> |
| Puṇḍravardhana, <i>di.</i> , | 60, 61, 63 | rājapurusha, | 131, 133 |
| Puṇḍravardhana, identified with Mahāsthāngarh, | 61 | Rājasūmha, a <i>Pāṇḍya k.</i> , | 50, 51 |
| Puphagiri (=Skt. Pushpagiri), a <i>hill</i> ? | 22, 23, 36 | Rājasi-Tasū-kula-viniśrito, <i>epith t of Khāvela</i> , | 80 |
| Purāṇas, | 55, 56, 58 | Rājasūya, a <i>sacrifice</i> , | 56, 79, 84, 87 |
| Purigere, <i>di.</i> , | 66 | Rājataranginī, a <i>work</i> , | 41n. |
| Purikā or Purikā-grāma, <i>vi.</i> , | 87n. | Rājāvali-tray-ōpēta, a <i>title</i> , | 135 and n. |
| Purisaḍata, <i>s. a.</i> Siri-Virapurisaḍata, | 2 | Rājendra Chōla II, <i>s. a.</i> Kulōttuṅga Chōla I, | 78 |
| purisa-yuga, | 79, 86n. | Rājgir, <i>s. a.</i> Rājagriha, | 78 and n. |
| Pūrṇēndrasēna, a <i>Buddhist monk</i> , | 39, 42, 44, 46 | Rakkhita, a <i>Buddhist monk</i> , | 8, 36 |
| Purūravas, <i>myth. k.</i> , | 80 | Rāmabhadra (=Rāma), an <i>epic hero</i> , | 69 |
| Pūrvadēśachaitya-paripāṭi, a <i>work</i> , | 42n. | Rāmadāsa, <i>m.</i> , | 62 |
| Pūrvaśaila, a <i>Buddhist convent</i> , | 9 | Rāmarājayya, a <i>Vijayanagara k.</i> , | 90, 91, 93, 95 |
| Pūrvaśailiya, a <i>Buddhist sect</i> , | 10 | Rāmī, <i>f.</i> , | 62, 63 |
| Pūrvaśillā, <i>s. a.</i> Pūrvaśaila, | 9 | Raṇabhañja, a <i>Bhañja k.</i> , | 100 |
| Pūsamitta, (<i>Prakrit form of Pushyamitra</i>), | 56 | Rāṇaka, a <i>title</i> , | 100, 102 |
| Pushkarinighālī, | 124 | Rinaka Niyārnama, <i>ch.</i> , | 100, 102 |
| Pushpamitra, mistake for Pushyamitra, | 56, 75 | Ranod inscription, | 105 |
| Pushpapura, <i>s. a.</i> Pātaliputra, | 76 | Rānopālī, name of an <i>enclosure</i> , | 54 |
| Pushyamitra, a <i>Sūnga k.</i> , | 55, 56, 57, 58, 75, 76 | Rāshtrakūṭa, <i>dy.</i> , | 48 and n., 49, 50, 77, 83. |
| | and n. | | 123 |
| Pustapāla, | 62 | Rāshtrakūṭas of Dhanop, | 123 |
| Pūva-rāja, mistake for Ava-rāja, | 84 | Ratana, <i>m.</i> , | 130 |
| Puvaseḷa, <i>s. a.</i> Pūrvaśaila, a <i>hill</i> , | 9, 22, 23, 36 | Raṭhika or Raṭhaka, <i>people</i> , 74, 78, 79, 84, 87 and n. | |
| | | Raṭhika, <i>s. a.</i> Mahārāṭhi, | 78 |
| | | Raum(Rāma)pāla, <i>m.</i> , | 135, 136 |
| | | Rāūta, a <i>title</i> , | 132, 133 |
| | | Rāyagiha (=Skt. Rājagriha), | 42n. |
| | | Rāya-nāyaka, a <i>title</i> , | 91 |
| | | Rāya-rāja-guru-maṇḍal-āchārya, <i>biruda of Muni-</i> | |
| | | chandraḍēva, | 93 |
| | | Rāya-vādi-pitāmaha, <i>do.</i> , | 93 |
| | | Revata, <i>m.</i> , | 22, 23 |
| | | Revatimnikā, <i>f.</i> , | 22, 23 |
| | | Ristikas, <i>s. a.</i> Raṭhikas, | 84 |
| | | Rōṇa (Ron), <i>vi.</i> , | 64, 67, 69 |
| | | Rudradāman, a <i>Kshatrapa k.</i> , | 4 |
| | | Rudradharabhaṭārikā, a <i>queen</i> , | 4, 5, 13, 19 and n. |
| | | Rudrasēna, a <i>Kshatrapa k.</i> , | 4 |
| | | Rudrasimha, <i>do.</i> , | 4 |
| | | rūpa, <i>currency</i> , | 79, 81, 82 |
| | | Rūpa-darśaka (Examiner of coins), | 81 |
| | | Rūpa-sūtra, | 81 |
| | | rūpa <i>s. a.</i> rūpya, | 81 |

R

| | |
|--|----------------|
| r, antique form of—, | 39 |
| r and ḷ, used for r and ḷ, | 64 |
| ra, use of—, | 73 |
| Raghuvamśa, a <i>work</i> , | 57, 58 |
| rāja, a <i>title</i> , | 102, 131, 133 |
| Rāja (or jya)dēva, <i>ch.</i> , | 108 and n. |
| Rājagaha or °griha, <i>vi.</i> , | 42, 78, 79, 87 |
| | and n. |
| rajakas, one of the 18 paṇas, | 90n. |
| Rājakēsarivarman (=Āditya I), | 47, 49n., 53 |
| Rājakēsarivarman, <i>sur. of Rājendra Chōla II</i> , | 78 |
| Rājamārttāṇḍa, <i>title of Aparājita</i> , | 49n. |
| Rājānaka, a <i>title</i> , | 102 |
| Rājanirghaṇṭa, a <i>work</i> , | 39n. |

The figures refer to pages : n. after a figure, to footnotes; and *add.* to the additions. The following other abbreviations are used :—*ch.*=chief; *co.*=country; *di.*=district or division; *do.*=ditto; *dy.*=dynasty; *E.*=Eastern; *f.*=female; *k.*=king; *m.*=male; *mo.*=mountain; *ri.*=river; *s. a.*=same as; *sur.*=surname; *te.*=temple; *vi.*=village or town; *W.*=Western.

| | PAGE | | PAGE |
|---|--------------------|---|---------------------------------|
| S | | | |
| <i>s</i> , initial, changed into <i>h</i> in personal names, . . . | 13 | <i>saṅghāta</i> , | 88n. |
| <i>s</i> , used for <i>ś</i> , | 122 | <i>saṅghayana</i> , assemblage, | 80, 85, 89n. |
| <i>s</i> , use of—, for <i>ś</i> and <i>sh</i> , | 72, 90 | <i>saṅkā</i> , mistake for <i>śaṅkā</i> , | 103 |
| <i>Sābaṭa</i> name of a field, | 124 | <i>Samkaī-Sēnabōva</i> , m., | 94, 97 |
| <i>Śabdakalpadrūma</i> , a work, | 39n., 58 | <i>Samma-sambudha</i> (= Skt. <i>Samyak-sambuddha</i>),
a title of the Buddha | 16, 18, 19, 20, 34 |
| <i>Śabdamālā</i> , do. | 81 | <i>Samma-sambuga</i> , mistake for <i>Samma-sambuddha</i> , . . . | 18 |
| <i>Śabdānuśāsana</i> , do. | 93n. | <i>Sammēlaśikharatīrthamālā</i> , a work, | 42n. |
| <i>Sadāśiva-Nāyaka</i> , a <i>Keladi</i> ch., | 90, 91, 93, 95 | <i>Sāmōlī</i> , vi., | 97, 98 |
| <i>Sadāśivarāya</i> , a <i>Vijayanagara</i> k., | 90, 93, 95 | <i>Samprati</i> , a grandson of <i>Aśoka</i> , | 86n. |
| <i>Sacsādai</i> , s. a. <i>Chilāda</i> , | 8 | <i>saṁthara</i> (= Skt. <i>saṁstara</i>), a layer, | 34 |
| <i>Sagauḍō</i> , vi., | 129, 130 | <i>Samudragupta</i> , a Gupta emperor, | 10 |
| <i>Sagara</i> , a myth. k., | 69 | <i>sandhi</i> , violation of—, | 59, 97, 122 |
| <i>Sāgarasūpaka</i> , a clan, | 25 | <i>saṅgha</i> , Buddhist community, | 12, 39, 40, 44,
45, 46, 88n. |
| <i>Sāhasōttuṅga</i> , title of <i>Bijjala</i> and <i>Vikrama</i> , | 110,
118, 121 | <i>Śaṅkaragaṇa</i> , a <i>Kaṭachuri</i> k., | 80 |
| <i>Sāhi</i> , a title, | 135 | <i>Śaṅkhā</i> , queen of <i>Nandivarman III</i> , | 48 |
| <i>Saigoṭṭa</i> , title of <i>Śivamāra II</i> , | 40 | <i>saṁkrānti</i> :—
uttarāyana, | 65, 67, 69, 110, 117, 121 |
| <i>Saka</i> , dy., | 37 | <i>saṇāya</i> , | 94, 96 and n. |
| <i>Sākala</i> (= <i>Siālkoṭ</i>), vi., | 40 | <i>saptadramāṣakalakūṭaka</i> , | 124 |
| <i>Sākala-vidvajjana-chakravartin</i> , viruda of <i>Muni-</i>
<i>chandrādēva</i> , | 93 | <i>Saptarishīśvara</i> , te., | 46 |
| <i>Śaka-Yavana</i> , | 8 | <i>saptika</i> , group of seven Jaina texts | 77 |
| <i>Śākēta</i> , co., | 76 | <i>sarada-sasi-soma-darśana</i> (= Skt. <i>śārada-śaśi-</i>
<i>saumya-darśana</i>), an epithet of the Buddha, | 22, 34 |
| <i>Śākās</i> :—
<i>Bāhvriha</i> , | 127 | <i>Sarasvatī</i> , goddess of learning, | 57 |
| <i>Chhandōga</i> , | 130 | <i>Sari°</i> , mistake for <i>Siri°</i> , | 20 |
| <i>Mādhyandina</i> , | 105, 106, 108 | <i>°sarai</i> , mistake for <i>°sarai</i> , | 102 |
| <i>Śākyātmajās</i> (= Buddhist monks), | 39, 44, 46 | <i>Sarpa</i> , a cave, | 72 |
| <i>Samābhāga</i> , a <i>Śunga</i> k., | 56 | <i>Sarua</i> , fort, | 132 |
| <i>saṁāja</i> , | 79, 87 | <i>sarvamānya</i> , a tenure, | 94, 96 |
| <i>saṁaṇa-baṁhaṇa-kavaṇa-vaṇijaka-dīn-ānugaha-</i>
<i>velāmi[ka]-dāna-paṭibhāga-vochhina-dhāra-</i>
<i>padāyini</i> (= Skt. <i>śramaṇa-brāhmaṇa-kriṣṇa-</i>
<i>vaṇijaka-dīn-ānugriha-vailāmiḥ-dān-āprati-</i>
<i>bhāg-avyavachhanna-dhāra-pradāyini</i>), an epi-
thet of <i>Chāṁtisiri</i> , | 16, 34 | <i>sarvanamasya</i> , do. | 67, 69, 118, 122 |
| <i>saṁaṇa</i> (Skt. <i>śramaṇa</i>), monk, | 89 | <i>Sarvatāta</i> , m., | 56 |
| <i>Śāmaṇi Saṁhara-seṭṭi</i> , m., | 94, 97 | <i>Sarvābhyaṁtara-siddhi</i> , | 67 |
| <i>Samā-sambudha</i> , s. a. <i>Samma-sambudha</i> , | 24 | <i>śaśi</i> , mistake for <i>śaśi</i> | 101 |
| <i>Samastabhuvanāraya</i> , a title, | 67 | <i>Śaśinandin</i> , m., | 62 |
| <i>Samastabhuvanāraya</i> , title of the <i>Kalachurya</i>
king <i>Bijjaṇa</i> , | 117 | <i>Śāstā</i> , | 39 and n., 44 |
| <i>Śambhu</i> (= <i>Śiva</i>), a god, | 109, 116, 118, 120 | <i>sata</i> (= Skt. <i>sapta</i>), | 34 |
| | | <i>Sātakamni</i> , or <i>Sātakarpi</i> , an <i>Andhra</i> k., | 74
79, 83, 86 |
| | | <i>Sātakarpi I</i> , do. | 74 |
| | | <i>Sātakarpi II</i> , do. | 74 |
| | | <i>Satapatha-Brāhmaṇa</i> , a work, | 82 |
| | | <i>satari-satam</i> (= one hundred and seventy), | 19, 34 |
| | | <i>Sātavāhana</i> , dy., | 74 and n., 75, 83, 84 |
| | | <i>Saṭhēla</i> , m., | 136 |

The figures refer to pages : n. after a figure, to footnotes ; and *add.* to the additions. The following other abbreviations are used :—*ch.*=chief ; *co.*=country ; *di.*=district or division ; *do.*=ditto ; *dy.*=dynasty ; *E.*=Eastern ; *f.*=female ; *k.*=king ; *m.*=male ; *mo.*=mountain ; *ri.*=river ; *s. a.*=same as ; *sur.*=surname ; *te.*=temple ; *vi.*=village or town ; *W.*=Western.

| | PAGE | | PAGE |
|--|-------------------|--|---|
| Satī record of Samvat 1346, | 135 | Śīla, abbreviated form of Śīlāditya, | 98 |
| Satī stone record, | 134 and n. | Śīlabhañja, a Bhañja k., | 100, 101 |
| satika s. a. sapika. | | Śīlachandra, m., | 40, 42, 44 |
| Śatrubhañja, a Bhañja k., | 100, 101 | Śīlāditya, a Guhila k., | 97, 98, 99 |
| Śatrusaptāṅgaharaṇa, a title, | 91 | Śīlāditya VI of Valabhīpura, | 98 and n. |
| sattra, | 44, 45 | Śīlāditya VII, a Valabhī k., | 98n. |
| Satyāśraya, a biruda, | 67, 69 | Śīlāmēgha Sēna I, a Ceylon k., | 48 |
| Satyatapa, a sage, | 117, 120 | Siṁdhujā or Siṁdhujā, a queen of Siṁhapatha, | 80, 86, 89 |
| Śauddhōdani, s. a. Buddha, | 43, 45 | | |
| Saudyumna, a clan, | 81 | Siṁga, s. a. Siṁha. | |
| Sāūlla, name of a street, | 124 | Siṁgaṇṇadēva, s. a. Siṁgaṇa, | 114 |
| Savarṇu (= Skt. sarvajña), | 16, 19, 34 | Siṁha, a Sinda ch., | 109, 111, 112, 114, 115, 119 |
| Sava-loka-chita-mahita (= sarvalōka-chita-mahita),
an epithet of the Buddha, | 22, 34 | Siṁhapatha, co., ? | 80, 89 |
| sava-niyuta (= Skt. sarva-niyukta), | 34 | Siṁhēśvara-maṭha, a monastery, | 110, 117, 121 |
| Sava-sādhu-vachhalā (= Skt. sarva-sādhu-vat-
salā), an epithet of Chāṁtisiri, | 16, 34 | Simuka, an Andhra k., | 74 |
| Sava-sat-ānukampaka (= Skt. Sarva-sattva-ānu-
kampaka), an epithet of the Buddha, | 16, 18, 19, 34 | Sind, ri., | 132 |
| Savathesu apatihata-saṁkapa (= Skt. Sarvārthēshu
apatihata-saṁkalpa), an epithet of Siri Chāṁ-
tamūla, | 16, 26 | Sinda, dy., | 109, 110, 111, 112, 114, 115, 116, 119 |
| seasons :— | | Siṁdhurājadēva, a Paramāra k., | 105, 106, 108 |
| Hēmanta (Winter), | 4, 21, 22, 23, 35 | Siṁga I, a Sinda prince, | 111 |
| Rainy, | 4, 16, 19, 20, 21 | Siṁgaṇa or Siṁgaṇadēva, a Yādava k., | 113, 114 |
| sela-khaṁbha (= Skt. śaila-skambha), | 18, 19, 21, 34 | Siṁgaṇṇadēva, ch., | 111 |
| sela-maṁṭava (or -maṁḍava) (= Skt. śaila-maṇ-
ḍapa), | 21, 22, 34 | Siṁgi (II), a Sinda ch., | 110, 111 |
| sela-ṭhaṁbha (= Skt. śaila-stambha), | 19, 34 | Siṁṇamaṇḍur Plates, | 48 |
| selavaḍḍhāki, stone mason, | 12, 22, 34 | Siri-Chāṁtamūla (or Siri Chāṭa°), an Ikhāku k., | 3, 5, 6, 11, 13, 17, 18, 19, 20, 21, 24, 28, 34 |
| Sēnāpati, a title, | 55, 57, 75 | Siridēvi, a Sinda queen, | 110, 117, 121 |
| śennirveṭṭi, a tax, | 54 | Siri-Ehuvuḷa (or Ehuvala)-Chāṁtamūla (or Chāṁ-
tamūla), an Ikhāku k., | 3 and n., 5, 6, 24, 34 |
| Seundhā, s. a. Sōndhī, | 132 | | |
| sey or chey, | 53, 54 | Siripavata (or Siripavvata = Skt. Śrīparvata),
mo., | 9, 22, 23, 36 |
| Seyya-Aparājita, m., | 49n. | Siri-Puḷumāyi, an Andhra k., | 6 |
| Shābazgarhī, Inscriptions of Aśoka at— | 84 | Siri-Virapurisadata or °Vira°, an Ikhāku k., | 2, 3 |
| shaṭ-karma, probably six yōga practices, | 126 and n., 128 | and n., 4, 5, 6, 7, 11, 13, 14, 15, 16, 17,
18, 19, 20, 21, 22, 24, 34 | |
| Shujā-ud-daula, a Nawab of Audh, | 54 | Siriyādēvi, s. a. Siridēvi, | 111, 113, 114 |
| Sidha (= Skt. Siddha), | 79, 86 | Śirriyārrūr, vi., | 49 |
| Siddhāntakaumudī, a work, | 86n., 88n. | Śirugavūr, vi., | 53, 54 |
| Siddhattha, m., | 2 | Sirūr inscription of the Rāshtrakūṭa king
Amōghavarsha I, | 123 |
| Siddhāyatana, | 99 | Śīṭalanātha, a Jaina Tīrthamkara, | 85 |
| Siḍha, m., | 130 | Siva, a god, | 65n., 100, 110, 117, 120, 121, 123 |
| Siḥala, co., | 36 | Śivamāra II, a W. Gaṅga k., | 49, 50 |
| Siḥala-vihāra, a monastery, | 9, 10, 22, 23, 36 | Śivānāga, m., | 104 |
| | | Śivaskandavarman, a Pallava k., | 9n., 84 |
| | | Śivatataratnākara, a work, | 91n., 92 |

The figures refer to pages : n. after a figure, to notes ; and add. to the additions. The following other abbreviations are used :—ch. = chief ; co. = country ; di. = district or division ; do. = ditto ; dy. = dynasty ; E. = Eastern ; f. = female ; k. = king ; m. = male ; mo. = mountain ; ri. = river ; s. a. = same as ; sw. = surname ; te. = temple ; vi. = village or town ; W. = Western.

The figures refer to pages; *n.* after a figure, to footnotes; and *add.* to the additions. The following other abbreviations are used:—*ch.*=chief; *co.*=country; *di.*=district or division; *do.*=ditto; *dy.*=dynasty; *E.*=Eastern; *f.*=female; *k.*=king; *m.*=male; *mo.*=mountain; *ri.*=river; *s. a.*=same as; *sur.*=surname; *te.*=temple; *vi.*=village or town; *W.*=Western.

| | PAGE | | PAGE |
|---|-----------------------------------|--|---|
| <i>upanidhi</i> , | 102 | Varaṇsa, <i>co.</i> ? | 31 |
| Upēndrapura- <i>maṇḍala</i> , <i>di.</i> , | 105, 106, 108 | <i>Vamśāvali</i> of the Chamba Rājas, <i>a work</i> , | 57, 58 |
| <i>uri</i> , <i>a measure</i> , | 47, 53, 54 | Vanavāsa (North Kanara), <i>co.</i> , | 5, 6, 7 and <i>n</i>
8, 15 |
| <i>urkka mrdde</i> ? | 94, 96 | Vanavāsas or Vanavāsikas, <i>people</i> , | 83, 84 <i>n</i> . |
| Čroḍeya, <i>village officer</i> , | 65, 66, 68, 70 | Vanavāsī, Vanavāsi or Vanavāsa, <i>co.</i> , | 22, 23, 24
36 |
| Utarāpadha or Utarāpatha (=Skt. Uttarāpatha),
<i>co.</i> , | 73, 78, 79, 88 and <i>n</i> . | Vanga, <i>co.</i> , | 22, 23, 31 |
| Utkala, <i>co.</i> , | 81 | Varaṇṣa I, <i>a Pāṇḍya k.</i> , | 50 and <i>n.</i> , 51 |
| Uttaramallūr inscription, | 49 <i>n</i> . | Varaṇṣa II, <i>do.</i> , | 50 and <i>n</i> |
| V | | Varaṇṣa II, <i>s. a.</i> Varaṇṣavarman II, | 49 |
| <i>v</i> , cursive form of—, | 109 | Varaṇṣā, <i>queen of Bhutivikramvikēsurin</i> , | 47 |
| <i>v</i> , used for <i>b</i> , | 39 | Varaṇṣa-Mahārāja, <i>a Pāṇḍya k.</i> , | 47, 48, 52, 53 |
| <i>vā</i> , contraction of <i>varsha</i> , | 16, 18, 19, 20, 21 | Varaṇṣa-Mahārāja I, <i>do.</i> , | 48, 50 |
| <i>va</i> , secondary form of —, | 90 | Varaṇṣa-Mahārāja II, <i>do.</i> , | 49 |
| <i>va</i> , written like <i>ra</i> , | 90 | Varaṇṣavarman II, <i>do.</i> , | 48 |
| Vaḍaga (or ka) rai-Maḷa-nāḍu, <i>di.</i> , | 47, 53, 54 | <i>varāha</i> , <i>coin</i> , | 91 and <i>n.</i> , 94 |
| <i>Vaddha-mangala</i> , <i>a symbol</i> , | 74 | Vārāṇāsī, <i>vi.</i> , | 68, 70 |
| <i>vaddhāpita</i> , | 107, 108 | Varddhamāna Mahāvīra or Mahāvīra, <i>Jaina</i>
<i>Tīrthamkara</i> , | 88 <i>n.</i> , 90, 92, 95 |
| Vadhamāna (= Vardhamāna), <i>s. a.</i> , Mahāvīra. | | Varddhamāna, mistake for Varddhamāna, | 92 |
| Vaḍha-rāja, <i>epithet of Khāravela</i> , | 80 | Varuṇa, <i>a god</i> , | 103 |
| Vāhira(Bāhira)vādā, <i>vi.</i> , | 100, 102 | Vāsethīputa, <i>an epithet of Siri-Ehuvuḷa-Chāta-</i>
<i>mūla</i> , | 3, 5 |
| Vāhiyālī, <i>name of a field</i> , | 124 | Vāsethīputa, <i>s. a.</i> Vāsithīputa, | 21, 24 |
| <i>Vaidagdhi-viśvakarman</i> , <i>a title</i> , | 128, 131 | Vāsithīputa, <i>s. a.</i> Vāsithīputa, | 16, 17 |
| Vaidya (Kāyastha-dūta-Vaidya-mēda°), | 130, 133 | Vāsisthīputra Śiva-śri- Śātakarṇi, <i>an Andhra k.</i> , | 74 |
| Vaidya Yaśōdēva, <i>m.</i> , | 123 | Vāsithīputa, <i>a metronymic</i> , | 6 |
| Vaiśālī, <i>s. a.</i> Basārḥ, <i>a site</i> , | 7, 10 | Vāsithīputa, <i>an epithet of Kāṇḍasiri</i> , | 4, 16, 17 |
| Vaiśālī, <i>vi.</i> , | 88 <i>n</i> . | Vāsithīputa, <i>an epithet of Khamdachalikireṁ-</i>
<i>maṇaka</i> , | 4, 18, 19 |
| Vājapēya, <i>a sacrifice</i> , | 4, 20, 21, 23, 24 <i>n.</i> , 104 | Vāsithīputa, <i>an epithet of Mahākāṇḍasiri</i> , | 5, 20, 21 |
| <i>Vajaveja</i> , mistake for <i>Vājapēya</i> , | 24 | Vāsithīputa, <i>an epithet of Sri Chāṁtamūla</i> , | 3, 16
and <i>n.</i> , 17, 18, 19, 20 |
| Vajragriha or Vajragadha, <i>original form of Vajira-</i>
<i>ghara</i> , | 78 | Vāsithīputa, <i>an epithet of Siri-Puḷmāyi</i> , | 6 |
| Vajrākara, <i>s. a.</i> Vayirāgara | 78 | Vāstavya, <i>a Kāyastha family</i> , | 132 |
| Vajiraghara, <i>vi.</i> , | 78, 87 | <i>vastra-bhēdakas</i> , <i>one of the 18 paṇas</i> , | 90 <i>n</i> . |
| Vajramitra, <i>a Śuṅga k.</i> , | 56 | <i>vastra-rakshakas</i> , <i>one of the 18 paṇas</i> , | 90 <i>n</i> . |
| <i>Vajrāsanastha</i> (= Buddha), | 44, 46 and <i>n</i> . | Vasū or Vasu, <i>k.</i> , | 80, 81, 86, 88, 89 |
| <i>vāk</i> (= 1)? | 100 and <i>n</i> . | Vāsudēvanāyaka, <i>ch.</i> , | 114 |
| <i>vāk</i> (= 4)? | 100 <i>n</i> . | Vasujyēshtha, <i>a Śuṅga k.</i> , | 55, 56 |
| <i>vakaṭā</i> , | 124 | Ṣasumitra, <i>do.</i> , | |
| ° <i>vala</i> , mistake for ° <i>bala</i> , | 101 | Vaṭa-Gōhālī, identified with Gōālbbhītā, | 60, 61, 62 |
| Valabhī or Valabhīpura, <i>vi.</i> , | 98 | Vaṭa-Gōhālī, <i>vi.</i> , | 60, 61, 62, 63 |
| Vallabha, <i>an official</i> , | 102 | Vaṭanagara, <i>vi.</i> , | 97, 98, 99 |
| Vamga (Bengal), <i>co.</i> , | 7, 8, 36 | Vaṭanagara, <i>s. a.</i> Vaṭa or Vaṭapura, | 98 and <i>n.</i> , 99 |

The figures refer to pages: *n.* after a figure, to footnotes; and *add.* to the additions. The following other abbreviations are used: —*ch.*=chief; *co.*=country; *di.*=district or division; *do.*=ditto; *dy.*=dynasty; *E.*=Eastern; *f.*=female; *k.*=king; *m.*=male; *mo.*=mountain; *ri.*=river; *s. a.*=same as; *sur.*=surname; *te.*=temple; *vi.*=village or town; *W.*=Western.

| | PAGE | | PAGE |
|---|------------------------------|---|--|
| Vaṭapura, s. a. Vasantagaḍh, | 98 | Vilāta, mistake for Chilāta, | 8 |
| Vāṣṭyāyana, an author | 83 | Vinayavijaya, an author, | 7n. |
| vaṇahāra (= Skt. vyavahāra), Civil law, | 79, 82 | Vindhya, mo., | 8n., 63 |
| Vāvaṇarasa, m., | 65, 66 | vinḍu, mistake for bindu, | 104 |
| Vayirāgara, s. a. Vajirāghara, | 78 | Vipṇukaḍa Chutukulānanda, m., | 84 |
| Vāyu, a god | 117, 120 | Viphusiri (= Skt. Vishṇusīri), ch., | 5, 21 |
| Vāyu-Purāṇa, a work, | 58, 75, 81 | Vira-Ballāla, a Hoysala k., | 113, 114 |
| Vēḍesaitha, dī., | 133, 136 | Vira-Bijjala, °ṇa or °Vijjaṇa, s. a. Bijjala, | 110, 111, 113, 114, 117, 118, 121 |
| veḍṇai, a tax, | 54 | Viracharitra, a Jaina work, | 88n. |
| Velāma, | 33 | Viramitrōdaya, a work, | 90n. |
| Velānaka-sutta, | 33 | Viramna, m., | 22, 23 |
| velāmika, a gift, | 16 and n., 17, 33 | Viramnikā, f., | 22, 23 |
| vēli, | 54 | Virapratāpa, a title of Vijayanagara kings, | 93, 95 |
| Vēlūrpālaiyam plates, | 48 | Vira-Vikrama or °dēva, s. a. Vikrama, | 110, 111, 113, 114, 117, 118, 121, 122 |
| Vēlvikuḍi grant, | 51 | Virōchana, m., | 62 |
| Vēna, a mythical k., | 79, 82, 86 | Vīrūpakha, | 6 and n. |
| Vettappēru | 53, 54 | Vīrūpakhapati, a title of Mahāsēna, | 6, 16, 17, 19, 20, 21, 23 |
| veṭṭi, a tax, | 54 | Vira-Pāṇḍya, a Pāṇḍya ch., | 112 |
| Vibhaṇḍaṭṭha-kathā, a work, | 33 | Viravarmmadēva, a Chāṇḍella k., | 132, 133, 135 |
| Vidarbha, a Yādava king, | 81 | Vīry-āchāra, | 95n. |
| Vidarbha, co. or vi., | 82 | Viśākha-āchārya, a Jaina pontiff, | 60 |
| vidhi, religious law | 79, 82 | Viśākhanaka, a clan, | 25 |
| Vidhika, a stone mason, | 12, 22, 23 | visarga, omission of—, | 97 |
| Vidiśā, vi., | 8n., 75 | visarga, wrong use of—, | 97 |
| Vidyādhara, m., | 136 | Vishṇu, a god, | 100, 127 |
| Vidyādhara, class of demigods, | 43, 45, 87 | Vishṇu-Purāṇa, a work, | 55, 58, 83, 84 |
| Vidyādhara-dēva, a Chāṇḍella k., | 126, 127 | Vishṇusōma, name of a field, | 124 |
| Vigrahēśvara, a teacher, | 110, 116, 120 | Vishṇuvardhana, | 40n. |
| Vijādhara-ādhivāsa, | 79 | Vishṇuvardhana, a Hoysala k., | 112 |
| Vijaya-chaka, | 88n. | visika (= Skt. vaiśmika), an architect (?), | 85 |
| Vijayanagara, vi., | 90, 91 | Visvēśvara (= Śiva), a god, | 129, 133, 135 |
| Vijayapālādēva, a Chāṇḍella k., | 126 | vochhina (= Skt. vyavachchhinna), | 33 |
| Vijayapāṇḍyadēva, s. a. Kāmādēva, | 112 | Vrā(Brā)hmaṇa, a caste, | 102 |
| Vijayapuri, vi., | 22, 23, 36 | Vriddhināga, m., | 123, 125 |
| Vijayaśakti, a Chāṇḍella k., | 129, 132, 133 | vritti, | 66 |
| | 135 | Vyāsa, a sage, | 63 |
| Vijayēśara (Vijayēśvara), a Śiva līnga, | 100, 102 | vyatipāta, a yōga, | 110, 117, 121 |
| vijñānin, artisan, | 129 | Vyāvahārika, one of the 18 paṇas, | 90n. |
| Vikrama, a Sinda prince, | 110, 117, 121 | Vyōmakēśa (= Śiva), a god, | 106, 107 |
| Vikramāditya, k., | 75 | | |
| Vikramāditya, s. a. Vīra-Vikrama, | 113, | | |
| | 114, 121 | | |
| Vikramāditya VI, a Chāḷukya k., | 75, 87n., 111, 112 | | |
| Vikramādityadēva (V), a W. Chāḷukya k., | 64, 65 and n., 67, 69 and n. | | |
| Vilāsapura, vi., | 129, 130, 132, 133 | | |

W

| | |
|------------------------------|--------|
| Wairagaḍh, s. a. Vayirāgara, | 78 |
| Western Gaṅga, dy., | 49, 50 |

The figures refer to pages: n. after a figure, to footnotes; and add. to the additions. The following other abbreviations are used:—ch.=chief; co.=country; dī.=district or division; do.=ditto; dy.=dynasty; E.=Eastern; f.=female; k.=king; m.=male; mo.=mountain; ri.=river; s. a.=same as; sur.=surname; te.=temple; vi.=village or town; W.=Western.

| Y | PAGE | | PAGE |
|--|----------------------------------|---|--------------------|
| <i>y</i> , cursive form of—, | 109 | regnal : | |
| <i>y</i> , doubling of —, after <i>r</i> , | 59 | 4th, | 74 |
| <i>ya</i> , bipartite form of—, | 38 | 6th, | 4, 13 |
| <i>ya</i> , tripartite form of —, | 38 | 11th, | 6 |
| <i>Yādava</i> , <i>dy.</i> , | 81 | 14th, | 7, 14, 23 |
| <i>Yādavas</i> of Dēvagiri, <i>dy.</i> , | 113, 114 | 15th, | 49 n. |
| <i>Yājñavalkya-smṛiti</i> , a work, | 58, 67 n. | 16th, | 114 |
| <i>Yajur-vēda</i> , a work, | 87 n. | 17th, | 48, 51 |
| <i>°yalana</i> , mistake for <i>°jvalana</i> , | 101 | 18th, | 4, 21, 49 |
| <i>Yama</i> , god of death, | 98 | 20th, | 2, 3 |
| <i>Yamunā</i> , <i>ri.</i> , | 126, 127 | 21st, | 49, 114 |
| <i>yāpa</i> , religious life, | 85 n., 89 n. | 22nd, | 49 |
| <i>Yāpa-nāvaka</i> (Skt. <i>jñāpaka</i>), | 80, 85, 89 n. | 26th, | 49 |
| <i>Yasōdharachariyā</i> , a <i>Jaina</i> work, | 91 & add. | 52nd, | 49 |
| <i>Yasōdharma</i> , <i>k.</i> , | 40 | 65th, | 49 |
| <i>Yasōnandin</i> , a <i>Jaina</i> monk, | 60 | Saka : | |
| <i>Yasōvarmmadēva</i> , <i>k.</i> , | 39, 40 and n., 41, 43, 45 | 692, | 84 |
| <i>Yasōvarmapura</i> , <i>vi.</i> , | 40 n. | 934, | 65, 67, 69 |
| <i>Yavana</i> , <i>co.</i> , people or tribe, | 7, 8, 22, 23, 36, 56, 79, 84, 87 | 1088, | 110, 117, 121 |
| <i>Yavana-rāja</i> , | 76 | 1286, | 92 |
| years:— | | 1488, | 91 |
| Chālukya-vikrama : | | Sālivāhana-Saka : | |
| 7, | 111 | 1479, | 90, 91, 93, 95 |
| 94, | 113 | Samvat : | |
| of the cycle : | | 1108, | 126, 127 |
| Dandubhi, | 91 | 1154, | 105, 106, 108 |
| Kshaya, | 91 | 1159, | 105, 107, 108 |
| Nāla, | 90, 93, 95 | 1187, | 105, 106, 107, 108 |
| Paridhāvin, | 65 and n., 67, 69 | 1311, | 132, 134 |
| Plavaṅga, | 110, 118, 121 | Vikrama Samvat : | |
| Vijaya, | 113, 114 | 1236, | 129, 130 |
| Vikrama, | 114 | 1346, | 135, 136 |
| Virōdhin, | 113 | Yeḍarāve inscription of Chālukya Vikramāditya | |
| Vyaya, | 110, 117, 121 | VI, | 75, 87 n. |
| Gupta-Samvat : | | Yeḍava, <i>ch.</i> , | 91 |
| 159, | 61, 63, 64 | Yeḍava-Murāri, title of <i>Sadāśiva</i> , - <i>Nāyaka</i> | 91 |
| (Harsha) Samvat : | | Yeliśirūr record, | 65 |
| 207, | 122, 123 | Yōgēśvara-yati, a teacher, | 110, 117, 120 |
| Mālava : | | Yōmēgha, a <i>Śunga</i> <i>k.</i> , | 56 |
| 589, | 40 | Yona, <i>s. a.</i> <i>Yavana</i> , | 7 |
| Mālava-Vikrama : | | Yonaka-Dhammarakkhita, <i>m.</i> , | 35 |
| 703, | 98 | Yuan Chwang, a <i>Chinese</i> pilgrim, | 126 |
| Nanda : | | Yudhishtira, an epic hero, | 63, 127 |
| 103, | 75, 84, 87 n. | Yuga-Purāṇa, a part of the <i>Gārgi-samhitā</i> , | 76 |
| | | yūti, | 107, 108 |
| | | Yuramahārāja, an epithet, | 9 n. |

¹ The figures refer to pages: n. after a figure, to footnotes; and add. to the additions. The following other abbreviations are used:—*ch.*=chief; *co.*=country; *di.*=district or division; *do.*=ditto; *dy.*=dynasty; *E.*=Eastern; *f.*=female; *k.*=king; *m.*=male; *mo.*=mountain; *ri.*=river; *s. a.*=same as *sur.*=surname; *te.*=temple; *vi.*=village or town; *W.*=Western.


70324

CARA 13 (FD)






F. SECTION-1.



F. SECTION-2.



F SECTION-3.



F. SECTION-4.



Central Archaeological Library,

NEW DELHI.

70824

Call No. R 417.05/E.I.

Author— Epigraphia Indica

Epigraphia Indica

